

TAMILNADU COOPRATIVE MILK PRODUCERS' FEDERATION LIMITED,  
Marketing Unit, Aavin Illam, 3-A, Pasumpon Muthuramalingam Salai, Nandanam,  
Chennai-600035.

Ref.No.4229/Mkg/Civil/2024

Date: 04.07.2024

To

The Related Firms,

Sir,

Sub: TCMPF Limited – **Shifting and repair works of old Dippo structure 10'X6' of size from Nandanam to Kotturpuram vacant land and providing chain link fencing with front flooring arrangements for Kotturpuram - Sealed quotations – Called for – Regarding.**

We invite competitive sealed quotations for the work of “**Shifting and repair works of old Dippo structure 10'X6' of size from Nandanam to Kotturpuram vacant land and providing chain link fencing with front flooring arrangements for Kotturpuram**”. We enclose a detailed specification and price schedule to be downloaded from the Aavin website [www.aavin.tn.gov.in](http://www.aavin.tn.gov.in).

The willing related firms can send their filled up quotations in the attached format along with the copies of necessary documents and should reach this office on or before **15.07.2024 at 3.00 PM.**

The sealed quotations should be addressed to “**The General Manager (Marketing), Tamilnadu Cooperative Milk Producers' Federation Limited, Aavin Illam, No.3-A, Pasumpon Muthuramalingar Salai, Nandanam, Chennai-600 035.**”

The TCMPF Limited will not be responsible for any delay in receipt of quotations beyond the specified time and date. Quotations for the above work should be sent in the sealed cover superscribing the name of work and last date on the cover itself. The Managing Director, TCMPF Limited reserves the right to reject any or all the quotations without assigning any reasons thereof.

**General Manager (Mkg)**  
TCMPF Ltd.,

Encl: Price Schedule, Terms & conditions

CC: Notice board, Head office Nandanam

## **Terms & Conditions**

1. Kindly mention your Company Name, Address with proof, Contact details along with GST registration copy mentioning the business/activity of the firm, PAN etc.
2. Details of Contractor registration/Live certificate empaneled with Government/MSME registration/others and work experience certificate for last 2 years with proof for satisfactory completion of the work to be enclosed. (if any)
3. Payments shall be released after completing the work satisfactorily.
4. Quotation to be addressed to "The General Manager (Marketing.), TCMPF Ltd. No.3A, Pasumpon Muthuramalingam salai, Nandanam, Chennai-35".
5. Superscribe on the cover "Ref. No.4229/Mkg(Civil)/2024 and name of work "Shifting and repair works of old Dippo structure 10'X6' of size from Nandanam to Kotturpuram vacant land and providing chain link fencing with front flooring arrangements for Kotturpuram".
4. TCMPF Ltd, reserves the right to alter the quantity as required / cancel the service.
5. Advance payment not accepted and kindly inspect the site/ before quoting the rates. Mentioned like "at actual" or "extra" is not accepted.

**Signature**

**With Date & seal**

**TAMILNADU COOPERATIVE MILK PRODUCERS' FEDERATION LIMITED,**  
**Marketing Unit, Aavin Illam, 3-A, Pasumpon Muthuramalingam Salai, Nandanam, Chennai-600035.**

**Price Schedule**

Ref .No      4229/Mkg(Civil)/2024

Date:

1      Name of the Firm

2      Address details

3      Contact No & Email ID

4      GST No.

**Name of work : Shifting and Repair works of old Dippo Structure parlour 10'X6' of size from Nandanam to Kotturpuram and providing chain link fencing for parlour**

S.No	Qty	Description	Unit	Rate	Amount
1	6.00	Earth work narrow excavation for foundation in all soils and sub-soils and to full depth as may be directed except hard rock requiring blasting inclusive of shoring, shuttering and baling out water wherever necessary, refilling the sides of foundation with excavated earth in layers of not more than 15 cm thick, watered, well rammed, consolidated and depositing the surplus earth on bank with initial lead of 10 m & initial lift of 2 m, clearing and leveling the site etc., complete as directed by the Federation officers and as per standard specification.	Cum		
2	3.50	Supplying and filling Stone dust in basement and foundation laid in layers,watering and consolidation etc complete as per standard specification	Cum		
3	1.30	Plain Cement Concrete 1:5:10 [one part cement, five parts sand and ten parts aggregate]using 40 mm size hard granite broken stones for foundation including de-watering if found necessary and laid in layers of not more than 15 cm thick for flooring including rendering the top surface rough to take floor finish etc., and including side shuttering if required and compaction, curing etc., complete as directed by the Federation officers and as per standard specification.	Cum		
4	2.80	Brick work in cm 1:5 using stock brick of size 9"x4.5"x3"including curing etc complete with standard specifications.	Cum		
5	10.70	Plastering in C.M 1:5 - 12 mm thick including the cost and conveyance of all to site and all labour charges etc complete and as per standard specifications.	Sqm		

S.No	Qty	Description	Unit	Rate	Amount
6	5.65	Supply and laying of Stain Free Nano Polish Vitrified Tiles 600 x 600 x 8mm of approved colour, shade and quality laid in cement mortar 1:3 (one cement and three m-sand) 10mm thick in all floors and the top pointed with the white cement mixed same colour pigments etc., complete complying with standard specification.	Sqm		
7	5.90	Supplying and laying Pathway tiles for a size of 0.30*0.30m of approved quality and color set in C.M 1:3 20mm thick including the cost and conveyance of all to site and all labour charges etc complete and as per standard specifications.	Sqm		
8	9.25	Providing MS powder coated 0.47mm thick sheet roofing / side walling including the cost and conveyance of all to site and all labour charges and as per standard specifications and as per design etc complete.	Sqm		
9	35.00	Painting two coats over old iron works such as steel doors, windows, ventilators, window bar balustrades etc., with best approved first quality synthetic enamel paint of approved colour in all floors. The rate is inclusive of all materials, brushes and scaffolding charges etc., complete complying with standard specification	Sqm		
10	10.50	Painting two coats of old wall surface with ready mixed plastic emulsion paint (exterior) of first class quality and of approved colour including scaffolding etc., complete as directed by the departmental officials.	Sqm		
11	11.20	Removing & refixing of damaged Alco panel sheet 3 mm thick in front of the parlour with equivalent fixing with spacer tape and the ACP sheet bounded with special type structural sealant of dow corning 789 or equivalent in dust free conditions the gaps between ACP sheet to be filled with whether sealant and backer rod or 12mm foam sheet to ensure water and air tightness etc complete	Sqm		
12	3.00	Labour charges for repairing the door & opening sheet . cutting and removing damaged sheets & tubes including welding & fixing charges etc complete	Nos		
13	50.00	Supply and fixing 18 gauge MS sheet panels for structural Parlour including the cost and conveyance of all to site and all labour charges and as per standard specifications and as per design etc complete.	Kg		
14	2.00	Repair of Rolling shutter which includes replacement of damaged spring, servicing the shutter, for allowing them to move freely, removal & refixing of Alco panel including material & labour charges , scaffolding charges etc	Nos		
15	1.00	Shifting of parlour from Nandanam to kottupuram including crane hire charges, welding charges, labour charges & fixing charges etc complete as directed	Job		

S.No	Qty	Description	Unit	Rate	Amount
16	12.00	Supply and providing Vinyl stickers to support with "AAVIN" product printed on digitally with lamination to cover internal , external wall of kiosk external wall of the kiosk Including fixing with suitable polymer based adhesive , transportation labour charges.	Sqm		
17	17.00	Manufacturing of RCC fencing post cast-in-situ of size 0.12x0.12x2.60 musing 20 mm metal cost including moulding, concrete, reinforcement grill, positioning and curing etc., complete.	Nos		
18	52.00	Supply and fixing GI Chain link fencing PVC coated 2" x 2", 10 G of ISI quality and tying with suitable intervals by using GI wire including materials, transportation cost etc complete as directed.	Sqm		
19	0.50	Clearing the trees, bushes, debris in the adjacent sides and rear side of the vacant land using machinaries including labour charges , hire charges , conveyance etc complete as directed by the Federation officers	day		
20	7.50	Plain Cement Concrete 1:4:8 (One Cement, Four M-sand and eight hard broken stone jelly) using 40 mm gauge hard broken granite stone jelly for foundation including dewatering for flooring and foundation and including side shuttering, compaction, curing etc., complete as directed by the departmental officers	Cum		
21	30.00	Paving the floor with pre-polished concrete anti-skid tiles (Required shape and design) of 20mm thick of approved quality and colour laid in Cement Mortar 1:3 (One Cement and Three sand) 20mm thick and pointed with white cement mixed with colouring pigment at the rate of 0.40 Kg. / sq.m., curing, etc., complete complying with standard specification and as directed by the departmental officers.	Sqm		
22	1.00	Supply and fixing LED type sign board with frame with approved logo design including labour charges etc complete	Nos		
23	100.00	Fabricating, supplying and fixing of Mild steel grills for following size square rod windows, corridor & ventilators including labour charges cutting, welding with red oxide priming one coat etc.complete and as directed by the departmental officers.	Kg		
		<b>Sub - Total</b>			
		<b>GST @ 18%</b>			
		<b>Total</b>			