

TAMILNADU COOPRATIVE MILK PRODUCERS' FEDERATION LIMITED,
Marketing Unit, Aavin Illam, 3-A, Pasumpon Muthuramalingam Salai, Nandanam,
Chennai-600035.

Ref.No.4071/ Mkg/Civil/2024

Date: .12.2024

To

The Related Firms,

Sir,

Sub: TCMPF Limited – Repair works to the flooring in Kitchen & replacement of glass door in Anna nagar tower parlour, park road hitech parlour due to infestation of rats and replacement of damaged roof tiles in Madhavaram and Repair to the borewell in Ambattur parlour – Sealed quotations - Called for – Regarding.

We invite competitive sealed quotations for the work of “Repair works to the flooring in Kitchen & replacement of glass door in Anna nagar tower parlour, park road hitech parlour due to infestation of rats and replacement of damaged roof tiles in Madhavaram and Repair to the borewell in Ambattur parlour”. We enclose a detailed specification and price schedule to be downloaded from the Aavin website www.aavin.tn.gov.in.

The willing related firms can send their filled up quotations in the attached format along with the copies of necessary documents and should reach this office on or before 11.12.2024 at 3.00 PM.

The sealed quotations should be addressed to “The General Manager (Marketing), Tamilnadu Cooperative Milk Producers’ Federation Limited, Aavin Illam, No.3-A, Pasumpon Muthuramalingam Salai, Nandanam, Chennai-600 035.”

The TCMPF Limited will not be responsible for any delay in receipt of quotations beyond the specified time and date. Quotations for the above work should be sent in the sealed cover superscribing the name of work and last date on the cover itself. The Managing Director, TCMPF Limited reserves the right to reject any or all the quotations without assigning any reasons thereof.

General Manager (Mkg)
TCMPF Ltd.,

Encl: Price Schedule, Terms & conditions

CC: Notice board, Head office Nandanam

Terms & Conditions

1. Kindly mention your Company Name, Address with proof, Contact details along with GST registration copy mentioning the business/activity of the firm, PAN etc.
2. Details of Contractor registration/MSME registration/others and work experience details to be enclosed. (if any available)
3. Payments shall be released after completing the work satisfactorily.
4. Quotation to be addressed to "The General Manager (Marketing.), TCMPF Ltd. No.3A, Pasumpon Muthuramalingam salai, Nandanam, Chennai-35".
5. Superscribe on the cover "Ref. No.4071/Mkg(Civil)/2024 and name of work **Repair works to the flooring in Kitchen & replacement of glass door in Anna nagar tower parlour, park road hitech parlour due to infestation of rats and replacement of damaged roof tiles in Madhavaram and Repair to the borewell in Ambattur parlour**".
6. TCMPF Ltd, reserves the right to alter the quantity as required / cancel the service.
7. Advance payment not accepted and kindly inspect the site/ before quoting the rates. Mentioned like "at actual" or "extra" is not accepted.

Signature

With Date & seal

TAMILNADU COOPERATIVE MILK PRODUCERS' FEDERATION LIMITED,
Marketing Unit, Aavin Illam, 3-A, Pasumpon Muthuramalingam Salai, Nandanam, Chennai-600035.
Price Schedule

Ref .No 4071/Mkg(Civil)/2024

Date:

1 Name of the Firm

2 Adress details

3 Contact No & Email ID

4 GST No.

Name of work : Repair works to the flooring in Kitchen & replacement of glass door in Anna nagar tower parlour, park road hitech parlour due to infestation of rats and replacement of damaged roof tiles in Madhavaram and Repair to the borewell in Ambattur parlour

S.No	Qty	Description of work	Rate in figures & words) (in Rs.)	Unit	Amount
1	2.00	Dismantling PCC by manual / by using deploying machineries including labour cost,hire for machineries etc complete		Cum	
2	5.00	Dismantling Floor finish and dadoing with mosaic tiles / glazed tiles / cuddapah slabs in cement mortar walls under 3m high etc all complete complying with relevant standard specification and as directed by the departmental officers.		Sqm	
3	3.50	Plain Cement Concrete 1:2:4 (one cement, two sand and four hard broken stone jelly) using 20mm jelly for wearing coat including laying, compacting, finishing and curing, etc including cost of weld mesh and glass peices etc., complete as per standard specificatins and as directed by the departmental officers.		Cum	
4	6.00	Paving the floor with best quality Vertified Tiles of size 600 x 600 x 8mm of approved colour, shade and quality laid in cement mortar 1:3 (one cement and three sand) 20mm thick in all floors and the top pointed with the white cement mixed same colour pigments etc., complete complying with standard specification.		Sqm	
5	3.30	Providing door with aluminum anodized fully glazed door with shutter frame, Using aluminium box section of size 95.25mm x 44.45 mm x1.70 mm @ 1.301 kg/m at top using aluminium box section of size 47.62 mm x 44.45 mm x 1.74 mm at 0.881 kg/m bottom and top panel covered with 12 mm thick prelaminated board with necessary accessories such as rubber beeding alu clip of size 19mm x 17.30x0.90 mm at 0.124 Kg/m , L angles, door stopper , handle, mortice lock 150 mm tower bolt, 125mm hinges, screws, pvc woodern felt etc, complete the rate inclusive of labour power, clipping, dismantling rcc column for fixing etc complete		Sqm	
6	3.30	Repair and servicing of front aluminium door including fixing of Aluminium door closure and labour charges etc complete		Sqm	
7	2.00	Supplying and fixing position CI Nahani Trap / Floor Trap of the 100 x 75mm sizes with best stainless steel gratings of approved brand and quality, fixed over a bed of brick jelly lime concrete 1:2:5 (One part of lime, two part of m-sand and five part of 40mm gauge brick jelly) and finished with Cement Mortar 1:3 (One Cement, Three m-sand) including dismantling masonry works wherever found necessary and making good the dismantled portions to the original condition and giving connection to the CI / PVC pipes, etc., complete complying with standard specification		Nos	

8	0.60	Brick work in Cement Mortar 1:5 (one part cement and five parts m-sand) using best quality II class table moulded chamber burnt bricks of size 9" x 4-1/2" x 3" of size 9" x 4-1/2" x 3" to line, level and to plumb on one face including necessary scaffolding, racking out joints, curing etc., complete as directed by the departmental officer and as per standard specification.		Cum	
9	2.00	Plastering with Cement Mortar 1:5 (One cement and Five m-sand), 12mm thick in all floors including scaffolding neatly finishing, curing etc. complete complying with standard specification and as directed by the departmental officers.		Sqm	
10	4.00	Labour charges for alteration of waste line from chamber and fixing of PVC hose for sink including material charges etc complete		Nos	
11	7.00	Painting two coats of old plastered wall surface with ready mixed plastic emulsion paint (interior) of first class quality and of approved color over one coat of priming coat including priming coat and also make good of the surface with sand paper, putty, scaffolding etc., complete as directed by the departmental officers.		Sqm	
12	75.00	Repointing of pressed tiles in CM 1:3 with waterproof compound of 12 mm thick including material and labour charges etc complete as directed		Sqm	
13	1.00	Removing and Replacement of damaged manglore roof from the roof including material and labour cost, scaffolding hire charges etc complete		Lot	
14	1.00	Supply and fixing 32 mm dia orient Foot valve including fixing in position cost of conveyance and labour charges for fixing in position etc., complete and necessary specials as directed by the Federation Officers and as per standard specifications		Nos	
15	6.00	Labour charges for inserting casing pipes assembly in the drilled hole after repair including welding the joint etc., complete		Nos	
16	20.00	Supply and laying of vinyl flooring including labour charges etc complete		Sqm	
17	1.00	Labour charges for cleaning the drainage chamber and removing the waste from the site etc., complete		Job	
		Sub - Total			
		GST 18%			
		Grand Total			

Signature of the Offerer