TAMILNADU COOPRATIVE MILK PRODUCERS' FEDERATION LIMITED, Marketing Unit, Aavin Illam, 3-A, Pasumpon Muthuramalingam Salai, Nandanam, Chennai-600035.

Date: 12.03.2025

# Ref.No. 2231/ Mkg/Civil/2025

To

The Related Firms,

Sir,

Sub: TCMPF Limited - Repair works to the damaged compound wall and glass door repair works in MMDA Hitech parlour, Arumbakkam - Sealed quotations -Called for – Regarding.

We invite competitive sealed quotations for the work of Repair works to the damaged compound wall and glass door repair works in MMDA Hitech parlour, **Arumbakkam**". We enclose a detailed specification and price schedule to be downloaded from the Aavin website www.aavin.tn.gov.in.

The willing related firms can send their filled up quotations in the attached format along with the copies of necessary documents and should reach this office on or before 17.03.2025 at 3.00 PM.

The sealed quotations should be addressed to "The General Manager (Marketing), Tamilnadu Cooperative Milk Producers' Federation Limited, Aavin Illam, No.3-A, Pasumpon Muthuramalingar Salai, Nandanam, Chennai-600 035."

The TCMPF Limited will not be responsible for any delay in receipt of quotations beyond the specified time and date. Quotations for the above work should be sent in the sealed cover superscribing the name of work and last date on the cover itself. The Managing Director, TCMPF Limited reserves the right to reject any or all the quotations without assigning any reasons thereof.

> General Manager (Mkg) TCMPF Ltd.,

Encl: Price Schedule, Terms & conditions

CC: Notice board, Head office Nandanam

## **Terms & Conditions**

- 1. Kindly mention your Company Name, Address with proof, Contact details along with GST registration copy mentioning the business/activity of the firm, PAN etc.
- 2. Details of Contractor registration/MSME registration/others and work experience/workorder details to be enclosed. (if any available)
- 3.Payments shall be released after completing the work satisfactorily.
- 4.Quotation to be addressed to "The General Manager (Marketing.), TCMPF Ltd. No.3A, Pasumpon Muthuramalingam salai, Nandanam, Chennai-35".
- 5.Superscribe on the cover "Ref. No.777/Mkg(Civil)/2024 and name of work "Dismantling of side wall for entry into kitchen portion and fixing of shelf for display portion and bottom counter,pavement concrete for vehicle entry in MMC parlour, Madhavaram".
- 6.TCMPF Ltd, reserves the right to alter the quantity as required / cancel the service.
- 7. Advance payment not accepted and kindly inspect the site/before quoting the rates. Mentioned like "at actual" or "extra" is not accepted.

Signature

With Date & seal

## TAMILNADU COOPERATIVE MILK PRODUCERS' FEDERATION LIMITED,

# Marketing Unit, Aavin Illam, 3-A, Pasumpon Muthuramalingam Salai, Nandanam, Chennai-600035. Price Schedule

Ref .No 2231/Mkg(Civil)/2024
1 Name of the Firm
2 Address details

#### 3 Contact No & Email ID

## 4 GST No.

4 GST No.  Name of work: Repair works to the damaged compound wall and glass door repair works in MMDA Hitech parlour, Arumbakkam							
S.No	Qty	Description of work	Unit	Rate (in words & figures)	Amount		
1	4.50	Dismantling, clearing away and carefully stacking materials useful for re-use for any thickness of walls - Brick / Stone Masonry in cement mortar walls under 3m high.	Cum				
2	4.50	Brick work in Cement Mortar 1:5 (one part cement and five parts m-sand) using best quality II class table moulded chamber burnt bricks of size $9$ " x $4$ - $1/2$ " x $3$ " to line, level and to plumb on one face including necessary scaffolding, racking out joints, curing etc., complete as directed by the departmental officer and as per standard specification.	Cum				
3	1.00	Reinforced Cement Concrete 1:2:4 (One Cement, Two sand and Four hard broken stonjelly) using 20 mm gauge hard broken granite stone jelly for all RCC items of works excluding cost of reinforcement grill and fabricating charges, centering and shuttering but including laying, vibrating with mechanical vibrators, finishing, curing, etc. and providing fixtures like fan clamps in the RCC floor / roof slabs wherever necessary and bearing surfaces of walls, beams etc. shall be finished smooth	Cum				
4	9.00	Supplying and erecting centering for sides and soffits including necessary supports and strutting upto 3.29 M height for plane surfaces as detailed below in all floors with all cross bracings using Mild Steel sheets of size 90 x 60 cm and 10 BG stiffened with welded Mild Steel angle of size 25mm x 25mm x 3 mm for boarding laid over silver oak joists of size 10cm x 6.50 cm spaced	Sqm				
5	1.00	At abote 00 cm coasts to control and supported by coasting space. Supplying, fabricating and placing in position Mild Steel / Ribbed Tor Steel grills for all RCC works as per design given including cost of steel and G.I. binding wire in all floors etc. complete complying with standard specification.	Qtl				
6	43.00	Plastering with Cement Mortar 1:5 (One cement and Five m- sand), 12mm thick in all floors including scaffolding neatly finishing, curing etc. complete complying with standard specification and as directed by the departmental officers.	Sqm				
7	175.00	Supply and fabrication of MS tubular section including the cost of all to site and all labour charges and as per standard specifications etc complete.	Kg				
8	90.00	Painting two coats of old wall surface with ready mixed plastic emulsion paint (exterior) of first class quality and of approved colour including scaffolding etc., complete as directed by the departmental officials.	Sqm				
9	40.00	Painting two coats over iron works such as steel doors, windows, ventilators, window bar balustrades etc., with best approved first quality synthetic enamel paint of approved colour in all floors. The rate is inclusive of all materials, brushes and scaffolding charges etc., complete complying with standard specification	Sqm				
10	1.00	Supplying and fixing in position best quality stainless steel sink of following sizes including cost of 32mm dia CP waste coupling, 32mm dia PVC waste pipe with rubber plug and chain, 15mm dia brass nipple including fixing the sink in position and testing for leakages etc., complete complying with standard specifications excluding CI brackets	No				

11	1.60	Solid PVC Door Shutters using 19 Gauge 19mm MS square tubes for styles and outer frames. 15mm MS square tubes for top, lock and bottom rails. The steel tubes shall be covered with 5mm thick solid PVC Sheets. Shutter using 5mm thick solid PVC Sheets for panelling shall rigidly fixed in position including necessary furniture and fittings. The over all size of styles shall be 50mm x 30mm etc complete		
12	1.00	Supply & fixing of Heavy duty 100 kg floor spring with 90 degree hold open feature and service charges for removing and refixing of new floor spring and service charges for civil work for removing and refixing of ACP sheet etc complete	Job	
13	4.00	Conveyance charges for removal of tree debris and other unwanted materials in and around the parlour etc complete as directed	Load	
		Sub - Total		
		GST 18%		
		Grand Total		

Signature of the Offerer