

TAMILNADU COOPERATIVE MILK PRODUCERS' FEDERATION LIMITED,
Marketing Unit, Aavin Illam, 3-A, Pasumpon Muthuramalingam Salai, Nandanam, Chennai-600035.

Price Schedule

Ref.No 763/Mkg(Civil)/2024

Date:

1 **Name of the Firm**

2 **Address details**

3 **Contact No & Email ID**

4 **GST No.**

Name of work : Repair works of Drainage rerouting with rising the manhole chamber and refixing of play equipments & providing roof sheet for EB panel in Virgumbakkam parlour

| Price Schedule | | | | | |
|----------------|-------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---------------------------------|-----------------|
| S.No | Qty | Description | Unit | Rate (in figures & words) | Amount (in Rs.) |
| 1 | 15.00 | Earth work open excavation in all soils and sub-soils and to full depth as may be directed except in rock requiring blasting inclusive of shoring shuttering, bailing out water wherever necessary and depositing the excavated earth with a lead of 10 mts. within the compound in places shown by the departmental officers and clearing and levelling the site, etc., complete complying with standard specification | Cum | | |
| 2 | 15.00 | Brick partition walls of 11.50cm thickness using best quality II class table moulded chamber burnt bricks of size 9" x 4-1/2" x 3" in Cement Mortar 1:3 (One Cement and Three Sand) using hoop iron reinforcement if found necessary including curing etc. complete and as directed by the departmental officers. | Sqm | | |
| 3 | 40.00 | Plastering with Cement Mortar 1:5 (One cement and Five m-sand), 12mm thick in all floors including scaffolding neatly finishing, curing etc. complete complying with standard specification and as directed by the departmental officers. | Sqm | | |
| 4 | 60.00 | Relaying of pipeline of dia 6" & 4" inside the drainage chamber including the removal of damaged pipeline cleaning the chamber etc complete as directed by the departmental officers. | Rm | | |
| 5 | | Supplying, laying and jointing PVC pipes (having working pressure 10 kg. / sq.cm) of approved quality and best variety conforming to BIS of the following dia including cutting, threading and fixing PVC specials using PVC adhesives (but excluding cost of such specials) and fixing into wall with teak wood plugs, PVC clamps and screws making holes on the wall (or) drilling holes in the roof and making good the dismantled portion to original condition with necessary brick work / cement concrete and plastering neatly wherever necessary with necessary scaffolding charges upto 4 metre height above ground level, etc., complete complying with standard specifications. | | | |

| Price Schedule | | | | | |
|----------------|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---------------------------|-----------------|
| S.No | Qty | Description | Unit | Rate (in figures & words) | Amount (in Rs.) |
| | 12.00 | 160 mm Pipe | Rm | | |
| | 12.00 | 110 mm Pipe | Rm | | |
| 6 | 45.00 | Relaying of existing damaged Paver Block in proper position etc all complete complying with relevant standard specification and as directed by the departmental officers | Sqm | | |
| 7 | 20.00 | Supplying and laying of Interlocking Paver Block Stone 83 mm the. Over a base layer of sand filling incl. Cost of materials laying and Labour charges etc., as directed by the departmental officials. | Sqm | | |
| 8 | 1350.00 | Charges for clearing the heavy jungle including hire charges for machinaries, labour & and clearing away the debris etc as directed | Sqm | | |
| 9 | 1.00 | Cutting and removing of play equipments from Nandanam to Virgumbakkam including transportation cost, labour cost , machinery cost etc complete as directed | Nos | | |
| 10 | 3.00 | Refixing of play equipments from Nandanam to Virgumbakkam including transportation cost including removal charges, cutting & welding charges, transportation charges, labour charges etc complete | Each | | |
| 11 | 0.65 | Plain Cement Concrete 1:5:10 (One Cement, Five sand and Ten hard broken stone jelly) using 40 mm gauge hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers of not more than 15 cm thick well rammed, consolidated and curing etc. complete complying with standard specification | Cum | | |
| 12 | 4.85 | Providing MS powder coated 0.47mm thick sheet roofing / side walling including the cost and conveyance of all to site and all labour charges and as per standard specifications and as per design etc complete. | Sqm | | |
| 13 | 50.00 | Supply and fabrication of MS structure for Parlour including the cost of all to site and all labour charges and as per standard specifications and as per design etc complete. | Kg | | |
| 14 | 4.80 | Labour charges for fixing granite benches from the park area to front portion of the parlour including fixing charges including cement mortaretc complete as directed | Sqm | | |
| 15 | 7.00 | Charges for cutting and removing trees fallen and clearing away the debris etc as directed | Nos | | |
| | | Sub - Total | | | |
| | | GST @ 18% | | | |
| | | Total (in Rs.) | | | |

**Signature
with Date & seal**