

TAMILNADU COOPRATIVE MILK PRODUCERS' FEDERATION LIMITED,  
Marketing Unit, Aavin Illam, 3-A, Pasumpon Muthuramalingam Salai, Nandanam,  
Chennai-600035.

---

Ref.No.3579/ Mkg/Civil/2024

Date:13.09.2024

To

The Related Firms,

Sir,

Sub: TCMPF Limited – Repair and maintenance works in Ambattur parlour - Sealed  
quotations – Called for – Regarding.

We invite competitive sealed quotations for the work of “Repair and maintenance works in Ambattur parlour”. We enclose a detailed specification and price schedule to be downloaded from the Aavin website [www.aavin.tn.gov.in](http://www.aavin.tn.gov.in).

The willing related firms can send their filled up quotations in the attached format along with the copies of necessary documents and should reach this office on or before 24.09.2024 at 3.00 PM.

The sealed quotations should be addressed to “The General Manager (Marketing), Tamilnadu Cooperative Milk Producers’ Federation Limited, Aavin Illam, No.3-A, Pasumpon Muthuramalingar Salai, Nandanam, Chennai-600 035.”

The TCMPF Limited will not be responsible for any delay in receipt of quotations beyond the specified time and date. Quotations for the above work should be sent in the sealed cover superscribing the name of work and last date on the cover itself. The Managing Director, TCMPF Limited reserves the right to reject any or all the quotations without assigning any reasons thereof.

General Manager (Mkg)  
TCMPF Ltd.,

Encl: Price Schedule, Terms & conditions

CC: Notice board, Head office Nandanam

## Terms & Conditions

1. Kindly mention your Company Name, Address with proof, Contact details along with GST registration copy mentioning the business/activity of the firm, PAN etc.
2. Details of Contractor registration/Live certificate empaneled with Government/MSME registration/others and work experience certificate for last 2 years with proof for satisfactory completion of the work to be enclosed. (if any)
3. Payments shall be released after completing the work satisfactorily.
4. Quotation to be addressed to “The General Manager (Marketing.), TCMPF Ltd. No.3A, Pasumpon Muthuramalingam salai, Nandanam, Chennai-35”.
5. Superscribe on the cover “Ref. No.3579/Mkg(Civil)/2024 and name of work “ Repair and maintenance works in Ambattur parlour”.
4. TCMPF Ltd, reserves the right to alter the quantity as required / cancel the service.
5. Advance payment not accepted and kindly inspect the site/ before quoting the rates. Mentioned like “at actual” or “extra” is not accepted.

Signature

With Date & seal

**TAMILNADU COOPERATIVE MILK PRODUCERS' FEDERATION LIMITED,**  
**Marketing Unit, Aavin Illam, 3-A, Pasumpon Muthuramalingam Salai, Nandanam, Chennai-600035.**

**Price Schedule**

Ref.No 2527/Mkg(Civil)/2024

Date:

- 1 Name of the Firm
- 2 Address details
  
- 3 Contact No & Email ID
  
- 4 GST No.

| <b>Name of work : Repair and Maintenance works in Ambattur parlour</b> |        |   |      |      |        |
|--|--------|---|------|------|--------|
| S.No   | Qty    | Description   | Unit | Rate | Amount |
| 1  | 2.74   | Providing Cup-board Shutter using Medium Density Fibre (MDF) Board - Exterior Grade - Plain 30 mm thick laminated with teakwook external lipping alround and are edge-banded with PVC tapes along with necessary furniture fittings, such as, hydraulic hinges, tower bolt, handles, multi purpose locks etc., as directed by the Departmental Officers.  | Sqm  |      |        |
| 2  | 440.00 | Painting two coats of plastered wall surface with ready mixed plastic emulsion paint (interior) of first class quality and of approved color over one coat of priming coat including priming coat and also make good of the surface with sand paper, putty, scaffolding etc., complete as directed by the departmental officers.  | Sqm  |      |        |
| 3  | 120.00 | Painting two coats over iron works such as steel doors, windows, ventilators, window bar balustrades etc., with best approved first quality synthetic enamel paint of approved colour in all floors. The rate is inclusive of all materials, brushes and scaffolding charges etc., complete complying with standard specification   | Sqm  |      |        |
| 4  | 17.00  | Removal charges for Doors and Windows including removal of frames, hinges and fastenings in counter portion etc as directed   | Sqm  |      |        |
| 5  | 4.00   | Providing and fixing at site heavy duty Hydraulic floor spring for 12.0mm thick toughened glass door with patch fitting of Godrej/Dorma Make only,along with connectors, top & bottom pivot patch fittings to be fixed at site, inclusive of all labour, materials, contingencies etc complete  | Nos  |      |        |
| 6  | 40.00  | Supplying and fixing in position of 4mm thick Alco panel CEILING ARRANGEMENTS with metal ' T' Section and 'L' angle frame work of grid size 60x60cm with metal T section and 'L' angel of size 25x25x2mm thick and the same is supported @ suitable intervals by adjustable type 6mm dia MS rod with suitable threaded nuts suspended rods hung from ceiling at 100cm c/c in both directions and fixing 60x60cmx6mm thick Ilux board in the grid so as to give a seat to false ceiling including painting the 6mm dia MS rod etc.,complete complying with standard speifications. | Sqm  |      |        |

| S.No | Qty   | Description  | Unit | Rate | Amount |
|------|-------|--|------|------|--------|
| 7    | 40.00 | Providing silicon weather proof sealants for the existing Aluminium composite panels including removing the old wear out sealant in all exposed part of ACP panels to arrest the water leakage in electrical fixtures & building as directed by Federation officers  | Rm   |      |        |
| 8    | 2.00  | Supply and fixing of natural granite stone benches of 3 seater without back rest of 5 feet X 2 feet with rough polished in garden area including labour, transportation cost, fixing cost etc as directed  | Nos  |      |        |
| 9    | 1.00  | Providing landscaping arrangements for ramp portion around including material , labour , transportation cost etc complete as directed  | Job  |      |        |
| 10   | 10.00 | Plastering with Cement Mortar 1:5 (One cement and Five m-sand), 12mm thick in all floors including scaffolding neatly finishing, curing etc. complete complying with standard specification and as directed by the departmental officers.  | Sqm  |      |        |
| 11   | 1.00  | Supplying and fixing in position best quality ss sink of 600X450 mm including cost of 32mm dia CP waste coupling, 32mm dia PVC waste pipe with rubber plug and chain, 15mm dia brass nipple including fixing the sink in position and testing for leakages etc., complete complying with standard specifications | Nos  |      |        |
| 12   | 3.00  | Labour charges for repairing the door & opening sheet . cutting and removing damaged sheets & tubes including welding & fixing charges etc complete  | Nos  |      |        |
|      |       | <b>Sub - Total</b>   |      |      |        |
|      |       | <b>GST @ 18%</b>   |      |      |        |
|      |       | <b>Total</b>   |      |      |        |