

# **TCMPF LIMITED** "AAVIN ILLAM" 3A - Muthuramalinganar Road, NANDANAM, CHENNAI - 35.

TWO PART TENDER

PART - A

# TECHNICAL BID

# CONSTRUCTION OF 10 TLPD ICE CREAM PLANT BUILDING AT TRICHY

THE TAMILNADU COOPERATIVE MILK PRODUCERS' FEDERATION LIMITED, AAVIN ILLAM, 3A - MUTHURAMALINGANAR ROAD, NANDANAM, CHENNAI – 600 035.



2

# TAMILNADU MILK PRODUCERS FEDERATION LIMITED

# AAVIN ILLAM, NO.3A, PASUMPON MUTHURAMALINGANAR SALAI, NANDANAM, CHENNAI - 35.

# Ref No:10379/Engg.3/2021

The Programme for the issue, receipt and opening of bids would be as under:

1	NAME OF WORK		Construction of 10 TLPD Ice Cream Plant Building At Trichy.
2	FORM OF CONTRACT		Lumpsum
3	ESTIMATED VALUE OF WORK PUT TO TENDER		<b>Rs.1280.00 Lakhs</b> (including GST @ 18%)
4	COST OF TENDER DOCUMENT	:	Rs.1,180/- in the form of DD in favour of " <b>The</b> Managing Director, TCMPF Limited," Payable at Chennai-35.(Non refundable).
5	EARNEST MONEY DEPOSIT	:	Rs.12,80,000/- in the form of DD in favour of " <b>The</b> Managing Director, TCMPF Limited," Payable at Chennai-35.
6	SALE OF TENDER DOCUMENT	:	07.04.2022 to 10.05.2022 from 11.00AM to 3.00 PM. Tender documents will not be sent by post.
7	PRE-BID MEETING	:	<b>21.04.2022 at 3.00 pm</b> at the Aavin illam,No.3A Pasumpon muthuramalinganar salai,Nandanam, Chennai-35.
8	Tender documents available with	:	<b>O/o the Managing Director</b> , TCMPF Ltd, Aavin illam, No.3A Pasumpon muthuramalinganar salai,Nandanam, Chennai-35.
9	LAST DATE & TIME OF RECEIPT OF TENDER (BOTH TECHNICAL & COMMERCIAL BIDS)	:	<b>11.05.2022 upto 3.00 PM</b> Tender document will also be available for e- submission on website <u>www.tntenders.gov.in</u> and the bidders can also participate in the tender through online.
10	DATE & TIME OF OPENING OF TECHNICAL BID	:	11.05.2022 at 3.30 PM

11	VENUE, DATE AND TIME OF OPENING OF BIDS	:	TCMPF Ltd, "Aavin illam", No.3A Pasumpon muthuramalinganar salai, Nandanam, Chennai-35.
12	DATE & TIME OF OPENING OF COMMERCIAL BID	:	After scrutiny of technical bid with prior individual information.
13	PROJECT COMPLETION PERIOD	:	18 MONTHS
14	QUALIFICATION CRITERIA	:	Refer the tender document of the work.
15	VALIDITY OF TENDER	:	<b>120 Days</b> from the date of opening of the tender.
16	SECURITY DEPOSIT	:	2% of accepted Value of the contract less EMD in the form of D.D in favour of " <b>The</b> <b>Managing Director, TCMPF Limited</b> ," Payable at Chennai-35.
17	ADDITIONAL SECURITY DEPOSIT	:	<ul> <li><u>A.5 to 15 %less tender:</u> 2% of Estimated value put to tender.</li> <li><u>B.More than 15% to 20% less tenders</u>: 50% of the difference Estimated Value over accepted Tender Value.</li> <li>Shall be in the form of D.D in favour of "The Managing Director, TCMPF Limited," Payable at Chennai-35.</li> </ul>

# ISSUE LETTER FOR TENDER DOCUMENT PART –A,

# TECHNICAL BID

This Two Part Tender document set containing Part – A Technical Bid and Drawings:

Issued to:

The fee for this set of Tender document is Rs. .....

Sale of Tender Document Vide Receipt No. .....

Dated: .....

For and on behalf of

The Tamilnadu Coop Milk Producers' Federation Limited, 'Aavin Illam', 3A - Muthuramalinganar Road, Nandanam,Chennai-35

ISSUED BY;

Deputy General Manager (Civil), T C M P F Limited Aavin Illam,Nandanam Chennai – 600 035.

#### **TWO PART TENDER APPLICATION**

To

The Managing Director, TCMPF Limited, Aavin Illam, 3A - Muthuramalinganar Road, Nandanam, Chennai 600035.

Sir

# Sub: Two-part tender for "CONSTRUCTION OF 10 TLPD ICE CREAM PLANT BUILDING AT TRICHY" - Submission of documents - reg.

~~~

Having examined the TWO PART TENDER documents consisting of PART - A pertaining to PRE-QUALIFICATION /TECHNICAL BID and PART - B COMMERCIAL BID with price quote, I / We hereby submit all the necessary documents and relevant information for bidding the above mentioned tender.

The application is made by me / us on behalf of \_\_\_\_\_\_ in the capacity of \_\_\_\_\_\_ duly authorized to submit this two part tender offer.

Necessary evidence admissible in law in respect of authority assigned to me on behalf of the bidding firm is herewith attached.

I / We submit the documents herewith taking into consideration of all the instructions, terms and conditions in the detailed two part tender notice.

I / We understand that the Managing Director, TCMPF, Chennai-35 reserves the right to reject any tender offer without assigning any reasons thereof.

I / We hereby agree to hold the tender offer valid for acceptance for a period of **120 days from the date of opening of the PART - A TECHNICAL BID**.

Signature of the Applicant including title capacity

Name (IN BLOCK LETTERS)

#### Enclosures:

- 1. Evidence of authority to sign
- 2. Latest brochures if any
- 3. Part A Pre-qualification / Technical bid in separate sealed cover Part - B Commercial bid with price quote in separate sealed cover.

Signature of the Tenderer

From

#### **1.MINIMUM CRITERIA FOR PRE - QUALIFICATION.**

#### 1.CRITERIA - I:

Tenderer Should furnish **EMD** amount of **Rs.12,80,000** /- (Rupees twelve lakhs eighty thousand only) to be drawn by means of Bank Demand Draft from any nationalized or scheduled Bank drawn in favour of "**The Managing Director**, **TCMPF Limited**," Payable at Chennai-35. IT SHALL BE ENCLOSED WITH THE PART-A. TECHNICAL BID ONLY. No other form of remittance shall be accepted. No exemption allowed.

#### 2.CRITERIA -II:

The Tenderer in the same "NAME" and "STYLE" should have been in the Civil Contract field.

#### **EVIDENCE TO BE PRODUCED:-**

- I). Audited Balance sheet with Chartered Accountant's Certificate for the past "Three years" in the case of individual Contractors, Partnership firms, Public / Private Limited Companies.
- **II).** Registered Partnership Deed in the case of Partnerahip Firms.
- **III)** Articles of Agreement and Memorandum of Association registered with Registrar of Companies as per 'Company Act' in the case of Public / Private Limited Companies.

#### 3.CRITERIA - III

The Tenderer should be Registered as **Class-I** State level Contractor of PWD/Highways / Any Department Government of Tamil Nadu/Central Government Department/ Central / State Government undertaking with monetary limit for taking up of works above **Rs.10.00 crores**(Rupees Ten crores Only). As per G.O (MS) No: 195 of PWD(G2), dt:14.12.2021.

#### EVIDENCE TO BE PRODUCED:-

- Attested true copy of the communication issued by the Registering Authority, Registering the name of the Tenderer as Class-I Contractor or Appropriate official notification as applicable.
- **II)** Copy of "**Live Certificate**" issued by the Registering Authority shall be enclosed or in case of Trust/Foundation Appropriate official notification as applicable.

#### 4.CRITERIA -IV

The Tenderer should produce **GST Registration Certificate** and GST Verification Certificate valid for the current period.

#### **EVIDENCE TO BE PRODUCED:-**

- i) Attested true copy of the Registration Certificate showing the GST Number assigned by the Commercial Tax Department issued by the Competent State / Central Commercial Tax Department Officials, valid for the current period.
- **II)** Attested true copy of the GST Verification Certificate issued by the Competent State / Central Government Commercial Tax Department.

#### 5. CRITERIA - V

The Tenderer should produce EPF Registration Certificate valid for the current period.

#### **EVIDENCE TO BE PRODUCED:-**

I) Attested true copy of the Registration Certificate showing the EPF Number assigned by the Provident fund Department issued by the Competent State / Central Provident fund Department Officials, valid for the current period.

#### 6.CRITERIA VI

The Tenderer should produce ESI Registration Certificate valid for the current period.

#### EVIDENCE TO BE PRODUCED.

I) Attested true copy of the Registration Certificate showing the ESI Number assigned by the Employee State Insurance Department issued by the Competent State / Central Employee State Insurance Officials, valid for the current period.

#### 7.CRITERIA VII

The tenderer should furnish **average annual sales turnover** for the last 3(Three) financial years which shall not be less than the tender value of contract in the same name & style and minimum annual sales turnover in last Three years shall not be **less than 50%** of the tender value of contract duly certified by the Chartered Accountant.

#### **EVIDENCE TO BE PRODUCED:-**

- I)Audited Balance Sheet, Profit and Loss Account, etc, clearly showing the Contract Amount received for executing Civil Engineering works duly certified by the Chartered Accountant for the immediate past THREE" years.
- **II)** Income Tax Return filed (clearly showing the total contract amount received) for the preceding THREE' years.

#### 8.CRITERIA VIII :

The tenderer should furnish **past experience certificate** (work completion certificate) for the **past Three financial years** clearly indicating department of work executed, period and value of work.

#### **EVIDENCE TO BE PRODUCED:-**

I) Certificate issued by the Engineer-in-Charge - (Not below than rank of Executive Engineer / Project Engineer) or Authorized Official of Corporate Entity of the project clearly showing the following details.

- a. Name of the Project
- b. Location of the Project (Village / Town / Taluk / District / State)
- c. Name / Designation of the Employer
- d. Value of work (As per Agreement)
- e. Agreement Number
- f. Period of contract as stipulated in the Agreement
- g. Date of commencement of the Project
- h. Date of actual completion of the Project
- i. Reasons for the delay in completion of the project, if any
- j. Actual value of work done as per Final Bill
- k. Quality of work executed.
- i. Quantities of individual items of work actually executed.

The tenderer should have completed **at least one building work** and the value should not be **less than 60 %** of the tender value for any one of the last 3 (Three) years.

9

#### **EVIDENCE TO BE PRODUCED:-**

I) Certificate issued by the Engineer-in-Charge - (Not below than rank of Executive Engineer / Project Engineer) or Authorized Official of Corporate Entity of the project clearly showing the following details.

- a. Name of the Project
- b. Location of the Project (Village / Town / Taluk / District / State)
- c. Name / Designation of the Employer
- d. Value of work (As per Agreement).
- e. Agreement Number
- f. Period of contract as stipulated in the Agreement
- g. Date of commencement of the Project
- h. Date of actual completion of the Project
- i. Reasons for the delay in completion of the project, if any
- j. Actual value of work done as per Final Bill
- k. Quality of work executed.
- I. Quantities of individual items of work actually executed.

#### 10.CRITERIA -X:

The tenderer should have access or as **available liquid asset** (working capital, cash on hand) and / OR credit facility of **not less than 10%** of the contract value. Cash flow may be taken as 10% of the estimated value of contract.

#### EVIDENCE TO BE PRODUCED:

I) Certificate issued by the Chartered Accountant, not earlier than Seven Days from the date fixed for submission of tender, clearly showing the Cash on Hand and Cash with Banks.

**II)** Certificates issued by the Bank / Banks, not earlier than Fifteen Days from the date fixed for submission of tender, clearly showing the Cash Credit / Overdraft Facilities extended to the Tenderer, the Cash Credit / Overdraft Facilities availed as on the date of certificate by the Tenderer and the balance Cash Credit / Overdraft Facilities remaining in the Accounts of the Tenderer as on the date of certificate.

#### 11.CRITERIA -XI:

The applicant shall have the following **minimum construction equipment's**, Tools and Plants exclusively available for this work - (Either own or under lease with the applicant)

| SI.No | Equipment                                    | Qty      |
|-------|----------------------------------------------|----------|
| 1     | Hydraulic Excavator (Pocklain/ JCB/ Hitachi) | 2 Nos    |
| 2     | Water Tank 4000 ltr. capacity                | 3 Nos    |
| 3     | Lorry / Tipper 8 to 10 ton Capacity          | 2 Nos    |
| 4     | Mixer Machine                                | 3 Nos    |
| 5     | Air Compressor                               | 2 Nos    |
| 6     | Concrete Vibrators                           | 3 Nos    |
| 7     | Centering Material                           | 3000 Sqm |

#### **EVIDENCE TO BE PRODUCED:**

I)Attested Xerox copy of the RC Books for the Machineries mounted on Trucks, Lorries, Tippers, etc.

**II)** Certificate issued by the Chartered Accountant clearly stating the details of Machineries, Tools and Plants owned by the Tenderer with year of purchase, capacity, present working condition, etc.

**III)** If the Tools and Plants or Machineries are proposed to be taken on leasehold or already on leasehold with the Tenderer, the source from which the same have been taken on lease / proposed to be taken on lease along with attested true copy of the Lease Agreement, entered into, lease period, etc. should be furnished.

#### 12.CRITERIA -XII:

The Tenderer should have executed **at least the following Quantities of items** of work mentioned below in single work for anyone of the last three years.

| SI.No | Description of Work         | Qty                 |
|-------|-----------------------------|---------------------|
| 1.    | Brick work                  | 750 m <sup>3</sup>  |
| 2.    | Steel centering             | 7000 m <sup>2</sup> |
| 3.    | Reinforced Cement Concrete  | 1550 m <sup>3</sup> |
| 4.    | Reinforcement grills        | 155000 Kg           |
| 5.    | Plastering                  | 7000 m <sup>2</sup> |
| 6.    | Granite works               | 1500 m <sup>2</sup> |
| 7.    | MS rolled or hollow section | 4000 Kg             |
| 8.    | Plain cement concrete       | 400 m <sup>3</sup>  |

#### EVIDENCE TO BE PRODUCED:

I) Certificate issued by the Engineer-in-Charge (not below rank of

Executive Engineer or Project Engineer) or Authorized official of corporate entity clearly showing the quantities of various items of work as detailed below:

a. Name of the Project

b. Value of the Project

c. Agreement Number

d. Period of execution from...... to ......

e.Quantities of work executed year wise.

#### NOTE:

Support of their Technical Qualifications should be produced. Even though the applicants meet the above criteria, they are subject to disqualified, if they have :-

**A.**Made misleading or false representation in the form, statements and attachment submitted. and/or

**B.**Records of poor performance such as abandoning the work, rescinding of contract for which the reasons are attributed to the non performance of the contractor, consistent history of litigation awarded against the applicant or financial failure due to bankruptcy.

# <u>General:-</u>

- 1. Copies of the documentary evidence in support qualification requirements should be submitted with due attestation by the competent authority.
- 2. The tenderers should furnish the original documents if called for at the time of tender evaluation to verify the copies of documentary evidence furnished along with the prequalification documents.
- **3.** The audited balance sheet/profit and loss account etc., to be furnished by the tenderers should be properly endorsed by the auditors as "verified with reference to the particulars furnished by the individual and found to be correct".

#### 2. INSTRUCTIONS TO THE TENDERERS

# FORM OF CONTRACT: LUMPSUM AGREEMENT (ITEM RATE LUMPSUM AGREEMENT)

**2.1.**INVITATION: Sealed Tenders under Two Cover System are invited from eligible contractors on behalf of the Managing Director, TCMPF Limited, Chennai - 600 035.

This TWO PART TENDER document consists of:

Part - A - Pre - Qualifying Technical bid

Part-B - Commercial bid with price-quote schedules.

- 2.2 Read all the terms and conditions of the TWO PART TENDER before you start filling up.
- 2.3. PURPOSE OF PRE QUALIFICATION: The purpose of Pre Qualification of tenderers for this work, is to ensure that the tenderer eventually selected for participating in the price bid, possess requisite organizational, financial and technical capability to carry out this large magnitude project in a duration of 18 Months (Including Monsoon Period).
- 2.4. Tenderers are to submit the original set of the TWO PART TENDER (both Part A Technical Bid and Part B Commercial Bid) duly filled in, attached with necessary documents.
- 2.5 Two cover system shall be adopted. The first cover shall contain the "Technical Bid" and the Bid Security/EMD. The second cover shall contain the Price Bid. Both technical as well as price bids shall be filled in with relevant details and duly signed. The completed bid documents in separate sealed covers shall be submitted in a common sealed cover. The name and address of the tenderers should be indicated legibly on the front page. All the covers shall be sealed and super-scribed properly and the common cover containing the Technical Bid and Price Bid shall be addressed to The Managing Director,TCMPF Ltd., Chennai-35. The Cover-1 containing the Technical Bid will be opened on the date and time stipulated above.
- 2.6 The Cover-II containing the Price Bid of the contractors/Firms whose credentials are decided as having satisfied the qualification/eligibility criteria as per bid documents will be followed strictly and will be opened in another day. The date and time scheduled for opening of price bid will be intimated to the Bidders at later date, for those who qualify in Technical Bid. The tender will be opened by the Committee on the date and time stipulated above. If the last date of receipt of tender happens to be a Public Holiday,

#### Signature of the Tenderer

12

the tenders will be received and opened at the above said time on the next working day.

- **2.7** The tenderers who are desirous of making field visits may do so at their own cost. Price variation clause is not applicable for this work.
- 2.8 TCMPF reserves the right to reject any or all the Bids without assigning any reason there for.

#### 2.9 METHODS OF TENDERING:

- (a) If the tender is made by an individual, it should be signed by the individual, with his full name and current address.
- (b) If the tender is made by a Sole-Proprietary "FIRM", it shall be signed by the Proprietor along with his full name and full name of the "FIRM" with it's current address. Documents with regard to Registration of the Firm by the Registrar of Firms should be produced, without fail.
- (C) If the tender is made by a "Firm" in partnership, it shall be signed by all the Partners of the Firm with their full name and current address or by a Partner authorized by the Firm (Either as per articles of the Deed of Partnership or by Registered Power of Attorney) for signing in Tenders, Agreements, etc., in which case, certified True Copy of the Deed of partnership along with the current address of all the Partners and the certified photocopy of the Registered Power of Attorney issued in favour of the Signatory should be produced.
- (d) If the tender is made by a Public | Private Limited Company or Corporation, it shall be signed by a duly authorised person holding the Power of Attorney for signing in tender, in which case, the certified copy of the Power of Attorney should accompany the Technical Bid. Such Public Private Limited Company / Corporation, should also furnish satisfactory evidence of its existence along with the Pre-Qualification Tender (Technical Bid).
- (e) Tenders from "JOINT VENTURES" are not acceptable.
- **2.10.** Go through the check slip given and ensure compliance of the terms and conditions
- 2.11. Tenderer is specifically informed that all the pages in both Part -A Technical Bid and Part-B Commercial Bid should be signed at the bottom of each page without any omission by the authorized signatory with name and seal of the firm.

#### 2.12 PRE-BID MEETING:-

- a. The tenderers or their authorised representative may attend the Pre-Bid Meeting, which will take place at 21.04.2022 at 3.00 pm in the Office of the Managing Director, TCMPF Ltd, Aavin Illam, Chennai-600035.
- b. The purpose of the Pre-Bid Meeting is to clarify issues and answer queries on any matter in connection with the conditions, specifications, etc., furnished in the Technical / Price Bid Documents that may be raised on or before the date of Pre-Bid Meeting.
- c. Minutes of the Pre-Bid Meeting including the text of the questions / queries raised (without identifying the source of the question / query) and the response thereon will be transmitted to all the intending tenderers who have purchased the tender documents. Any modification of the contents in the bid documents, consequent on the decision taken during the Pre-Bid Meeting shall be made by the Tender Inviting Authority, exclusively through the issue of an ADDENDUM and not through the Minutes of the Pre-Bid Meeting.
- d. Only the intending tenderers or their authorized representatives, who and with have purchased and with the tender documents, will be permitted to attend the Pre-Bid Meeting.
- 2.13 Filled tenders received by post will not be accepted.
- 2.14. Requisition by POST will not be considered at any cost.
- 2.15. Bank Guarantee will not be accepted towards Earnest Money Deposit.
- **2.16.** Even though the tenderer offered their tender through on line the tenderer are necessary to submit the original set of documents.
- 2.17. LANGUAGE OF TENDER: The Technical Bid (Pre-Qualification Tender) and all Supporting Documents, Certificates, Evidences and the Price Bid should be submitted in "ENGLISH" only. The Supporting Documents if attached in any other language should be translated in English with the certificate of the "Notary Public" duly certifying that the English translation of the documents is true and accurate translation of the original documents.
- 2.18. Bid document will be sold to the Experienced Bidders or their authorized representatives on payment of cost of Schedule + GST and on the submission of a written application along with relevant documents, return for filing Latest I.T.Certificate and, GST registered number and on production of proof of having similar experience, including date of

completion of work, actual value of work done etc., during office working hours either in person or his authorized agents. Necessary authorization should be produced if the request made by the agents of the bidder. If the tender schedules are downloaded from website, **the tenderer should attach the above details duly attested by Notary Public.** 

#### **3.SPECIAL INSTRUCTION TO THE TENDERERS**

As per G.O (MS) No.555/Public Works(G2) Department dated 17.11.1999 on evaluation of tender if it is found that if the overall quoted amount of the tender is less than 5 to 15 % of the value put to tender, the contractor shall pay an additional security at 2% of the Estimated value. If the tender discount exceeds 15% to 20%, the contractor shall pay an additional security deposit of 50% of the difference between the quoted amount and estimated amount. Failure to furnish the additional security deposit within 15 days from the date of receipt of acceptance order and execute the agreement shall entail cancellation of award of contract and forfeiture of EMD furnished.

The Additional security deposit collected for the minus tender referred to above will be refunded along with security deposit as per agreement condition.

# 4. GENERAL TERMS & CONDITIONS

- **4.1.** PART A Technical bid, wherein the pre-qualification, based on various factors such as suitability and eligibility of the tenderer will be evaluated, considered and decided prior to opening and consideration of Commercial Bids under PART B of the tender.
- **4.2** PART A Technical bid shall be opened on **11.05.2022** at **3.30 PM** in the presence of the tenderers or their authorized representative who opt to be present during the opening.
- **4.3** PART B Commercial Bid of the tenderers who do not satisfy any / all the terms and conditions specifically so mentioned under PART A Technical bid, shall not be considered eligible and shall not be opened.
- 4.4 PART B Commercial Bid, wherein the rates tendered by those who qualify themselves for and are selected as per the terms and conditions prescribed in PART A Technical Bid only will be considered and decided for the award of the contract.
- **4.5** Part B Commercial bids shall be opened after scrutiny of Part-A Pre-qualification / Technical bids in respect of those who are found and declared as qualified, eligible and short listed as per technical parameters and terms and conditions of prequalification bid with prior individual intimation in the presence of tenderers or their authorized representative who opt to be present. The date of such opening of part-B Commercial bid will be informed separately to those who qualify in the PART - A Technical bid confirm to the Technical parameters prescribed thereon.
- 4.6 The tender forms are not transferable or assignable.
- **4.7** The signatory of the tender should indicate his / their status in which he / they have signed and submit necessary documentary proof admissible in law in respect of such authority assigned to him / them by the firm. If the tender opening day is declared as a holiday, the tenders shall be received and opened immediately on the next working day at the same time and place.
- 4.8 EARNEST MONEY DEPOSIT:
- **4.8.1** All tenders must be accompanied with the prescribed amount of EMD along with tender.
- 4.8.2 EMD amount of Rs.12,80,000/- (Rupees Twelve Lakhs eighty thousand only) to be drawn by means of Bank Demand Draft from any nationalized or scheduled Bank drawn in favour of "The Managing Director, TCMPF Limited," Payable at Chennai-35 in the name of tenderer/firm only. IT SHALL BE ENCLOSED WITH THE PART-A, <u>TECHNICAL BID ONLY</u>. No other form of remittance shall be accepted.No Exemption.
- **4.8.3** Tenders not accompanied with demand draft towards the prescribed EMD shall be summarily rejected.
- **4.8.4** If tenderer withdraw his offer before finalization of the tender, the EMD remitted by the tenderer shall be forfeited in full.

- **4.8.5** The tenderer should be submit a covering letter giving full details as called for in the tender notice together along with the copy of letter registering them in the appropriate class.
- **4.8.6** The tenderer should furnish their Income Tax Permanent Account Number [PAN] in the tender document itself.
- **4.8.7** List of various machineries and other equipment's of the tenderer disposal for use in the execution of work should be furnished.
- **4.8.8** Details of previous work done / under execution by the tenderer covering the cost of work, Agreement No. & date, the department in which the work was carried out etc., should be furnished so as to assess the previous experience of the tenderer. Year wise details should be furnished so as to see that these tenderers have minimum experience of major works.
- **4.8.9** The rate quoted in the tender shall be kept valid for 120 days from the date of opening of part-A Technical bids and the tenderer at his own cost shall attend and sign the contract as soon as the acceptance of tender is communicated. Failure to attend in the manner above said shall entail forfeiture of EMD furnished by the tenderer. Besides, the tenderer shall be held responsible for any loss to the Federation on account of his failure to attend the manner aforesaid.
- **4.8.10** The EMD of the successful tenderer shall be retained as security deposit, which will not bear any interest, and the same will be released after 6 months from the date of completion of work. The EMD of the unsuccessful tenderer shall be returned after execution of the agreement of the contract.
- **4.8.11** The tenderer's particular attention is drawn to the sections and clauses in the General Conditions of the Contract dealing with
  - a) Test, Inspection and rejection of defective materials and work
  - b) Carriage
  - c) Accidents
  - d) Delays
  - e) Sanction on particulars of payments
  - f) Construction plant
  - g) Water and lighting and
  - h) Cleaning up during progress and for delivery.
- 4.8.12 The tenderer who are downloading the document from the website are instructed to check the website for corrigendum after the date of pre-bid meeting, for any amendments (pre-bid minutes) (if any issued) They are instructed to down load the above amendments and enclose it along with the technical bid document duly authenticating while submitting without fail. Failure to submit the pre-bid minutes will lead to rejection of the tender offer.

Signature of the Tenderer

17

#### 4.9 SECURITY DEPOSIT

- 4.9.1 After evaluation and finalization of Part-A pre-qualification / technical bids and Part-B commercial bids, selected tenderers would be required to sign an agreement and furnish a Security Deposit such that the total value of Security Deposit including EMD already paid shall be 2 % of the order value as specified by the tender accepting authority, drawn by means of Bank Demand Draft only from any Nationalized Bank drawn in favour of "THE MANAGING DIRECTOR, TCMPF LIMITED" payable at Chennai-35. The EMD already paid along with tender shall be adjusted in the Security Deposit to be paid by the successful tenderer. The above Security Deposit amount will be released after 6 months from the date of completion of the work in all respects.
- **4.9.2** No exemption will be given for payment of security deposit under any circumstances as per TNTT Act and the same should be remitted by Demand Draft.
- **4.9.3** No interest shall be paid on Earnest Money Deposit / Security Deposit.
- **4.9.4** If the tenderer withdraws his bid after the acceptance of Price bid or fails to pay the requisite security deposit amount within the time specified in the bid acceptance order, the earnest money deposit produced with the technical bid will be forfeited.
- **4.10.** No increase of the rate will be allowed during the period of contract under any circumstances.

#### 4.11 AGREEMENT:

- 4.11.1 The successful tenderer has to execute an agreement on Rs.100/- stamp paper incorporating the terms & conditions of the contract within 15 days from the date of work order.
- **4.11.2** If the contractor fails to execute the work satisfactorily at the tendered rate, the Federation will forfeit the security deposit.
- **4.11.3** If for any reason the Federation incurs any loss / additional expenditure in connection with the work during the period of contract, the same shall be recovered together with all charges and expenses from the contractor.
- **4.11.4** Notwithstanding anything contained in the tender schedule, no obligation is cast on the Federation to accept the lowest tender and the Federation shall also have the right to accept or reject any or all the tenders without assigning any reasons.
- **4.12.5** For violation of any of the terms and conditions of the contract, the Federation reserves the right to terminate the contract, with or without notice as applicable.
- **4.12.6** On termination of contract, the security deposit is liable to be forfeited and any of the resultant loss beyond that recoverable from pending bills if any.

#### 4.13 PENALTY:

If the contractor fails in its due performance of the contract within the time fixed or extension of time granted, the contractor is liable to pay liquidated damage of 1 % per month subject to the maximum of 5 % on actual expenditure of contract / final bill value.

#### 4.14 DISPUTES & ARBITRATION:

- 4.14.1 The Arbitrator for fulfilling the duties set forth in the Arbitration clause of General Conditions of Contract shall be in case of value of claim up to Rs.50,000/- [Rupees fifty thousand only] the Arbitrator who will be appointed by the Managing Director, TCMPF Limited and if the value of claim exceeds Rs.50,000/- it shall be settled through the competent civil court of Chennai jurisdiction.
- **4.14.2** In case of discrepancy between the prices quoted in words and in figures, the lower of the two shall be considered.

# 4.15 WITHHELD AMOUNT:

5 % of bill value shall be retained in each bill as withheld amount and at the time of payment of the final bill  $2\frac{1}{2}$  % of the withheld amount shall be released to the contractor as first installment and the remaining  $2\frac{1}{2}$  % withheld amount will be retained as security deposit for a period of 1 year reckoned from the date of successful completion of work in order to enable the Federation Officers to watch the effect of all seasons on the works. Further, an indemnity bond should also be given by the contractor for a further period of 4 years when the  $2\frac{1}{2}$  % balance withheld amount is released to the contractor after completion of 1 year, the defects should be rectified by the contractor at his own cost as directed by the Federation Officers and no extra payment will be made for the rectification of such work. If the contractor fails to carry out the rectification works, the Federation shall carryout the work at the risk and cost of the contractor & recovery from the pending dues.

# 4.16 Goods and Service tax :

The tenderer should furnish a self attested copy of the GST registration certificate along with Tender document.

The contractor shall claim GST only in case of a registered supplier and should raise tax invoice, without fail.

All duties, taxes and other levies payable by the contractor under the contract, or for any other cause, as applicable on the date of submission of Bid, shall be included in the rates and prices and the total bid price submitted by the bidder.

# 5. CHECK SLIP

Kindly ensure compliance of the under-mentioned requirements, as per Tender Terms and Conditions.

| 1 | Whether the EMD amount remitted.                                             | Yes/No |
|---|------------------------------------------------------------------------------|--------|
| 2 | If yes, whether DD attached with the Tender offer – Part A / Technical bid.  | Yes/No |
| 3 | If yes, details of DD No., date, Bank on which drawn etc., may be furnished. | Yes/No |

| Demand Draft No       | dated  | for a value of ` |  |
|-----------------------|--------|------------------|--|
| (Rupees               |        |                  |  |
| only) drawn on (Bank) | Branch | in               |  |
|                       |        |                  |  |

favour of The Managing Director, TCMPF Ltd. payable at Chennai.

| 4  | Whether registered class of the tenderer with monetary limit and department in which registered. [Certified copy of the registration should be attached] .                                                                                        | Yes/No |
|----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|
| 5  | If so, whether necessary supportive documents such as copies of completion certificates, Live certificate, Audit balance sheet etc.,                                                                                                              | Yes/No |
| 6  | Income Tax Permanent Account Number(PAN) attached.                                                                                                                                                                                                | Yes/No |
| 7. | GST registration certificate attached.                                                                                                                                                                                                            | Yes/No |
| 8  | ESI Registration Certificate attached                                                                                                                                                                                                             | Yes/No |
| 9  | PF Registration Certificate attached                                                                                                                                                                                                              | Yes/No |
| 10 | Credit facility or liquid asset certificate attached.                                                                                                                                                                                             | Yes/No |
| 11 | Whether details of past experience for past three years/ Under execution enclosed.                                                                                                                                                                | Yes/No |
| 12 | Minimum Construction equipment;s proof attached.                                                                                                                                                                                                  | Yes/No |
| 13 | Whether all the pages in the tender formats, Part – A (Technical Bid) and<br>Part - B (Commercial Bid) have been duly signed by authorized signatory                                                                                              | Yes/No |
| 14 | Whether two covers have been wax sealed duly superscribed as "tender<br>for the work OF <b>CONSTRUCTION OF 10 TLPD ICE CREAM PLANT BUILDING AT</b><br><b>TRICHY</b> Part-A Technical bid" or "Part-B Commercial bid" (whichever is<br>applicable) | Yes/No |
| 15 | Whether these two sealed covers for Part – A, Technical Bid and Part – B,<br>Commercial Bid, put in a larger cover duly superscribed addressed and<br>wax sealed at appropriate places.                                                           | Yes/No |

#### **SCHEDULE**

#### **SPECIAL CONDITIONS**

- The work shall be carried out strictly in accordance with the specification and provision stipulated in the (TNDSS) Tamil Nadu Detailed Standard Specifications and (NBC) National Building Code unless otherwise specified.
- The contractor shall abide to the conditions set-forth in the preliminary specification to T.N.D.S.S. 1952 reprint. Wherever the words "Executive Engineer and Superintending Engineer" occurring shall be read as Managing Director respective of the TCMPF Limited.
- 3. The contractor shall not enter the private land without written understanding of the owner.
- 4. The work shall be carried out in the best workmanship manner. Pure water and best materials available in the market shall be used on the work.
- 5. The work site shall be kept clean always and all unused materials shall be removed from the site within one month from the date of physical completion of work.
- 6. The work should be completed as specified herein:

#### PERIOD OF COMPLETION OF WORK 18 Months

 $1^{st}$  month from the date of handing over the site – 5%  $2^{nd}$  month from the date of handing over the site – 10%  $3^{rd}$  month from the date of handing over the site – 15%  $4^{\text{th}}$  month from the date of handing over the site – 20%  $5^{\text{th}}$  month from the date of handing over the site – 25%  $6^{\text{th}}$  month from the date of handing over the site – 30%  $7^{\text{th}}$  month from the date of handing over the site – 35%  $8^{\text{th}}$  month from the date of handing over the site – 40% $9^{\text{th}}$  month from the date of handing over the site – 45%10<sup>th</sup> month from the date of handing over the site –50%  $11^{\text{th}}$  month from the date of handing over the site -55% $12^{\text{th}}$  month from the date of handing over the site -60% $13^{\text{th}}$  month from the date of handing over the site -65% $14^{\text{th}}$  month from the date of handing over the site -70%15<sup>th</sup> month from the date of handing over the site –75% 16<sup>th</sup> month from the date of handing over the site -80% 17<sup>th</sup> month from the date of handing over the site –90% 18<sup>th</sup> month from the date of handing over the site –100%

7. If night work is involved, the contractor shall make his own arrangements at his cost. The work shall be carried out with least hindrance to the adjacent buildings and the

contractor will be held responsible for the damages caused to the existing structure, fittings etc.

- 8. a). The arrangement of MS & RTS Rods for reinforcement for R.C.C. works shall be in accordance with the working drawing.
  - b). The planks for forms and centering for R.C.C works shall be of well seasoned timber approved by the officer-in-charge of work according to the para 10 clause 30 of T.N.D.S.S.
  - c). Holes and recesses for electric wiring, water supply and drainage etc. shall be Provided as directed during progress of work without any claim for extra.
  - d). The broken stones for Reinforced Cement Concrete and Plain Cement Concrete works shall be of granite blasted and broken to the requiring size as specified.
  - e). All the cement concrete will be machine mixed and vibrators shall be used while placing the concrete for RCC works.
- 9. a]. The required quantity of steel and cement will be own arrangement by the tenderer.
  - b]. The quality of cement and steel used to the work by the tenderer to be tested as per ISI specification in the PWD quality control lab / Government Engineering college lab / Government recognized lab at his own cost and the test result shall be produced to the site Engineer-in-charge and the same shall be confirmed by the site in-charge.
  - c]. The balance quantity of steel and cement will be taken by the tenderer after completion of the work.
- 10. The tenderers who are themselves not professionally qualified shall undertake to employ qualified staff at their cost to look after the work. The tenderers should state that in clear terms, whether they are professionally qualified or whether they undertake to employ technical staff required by the department, specified in the schedule below for the work. In case the selected tenderer is professionally qualified or has undertake to employ technical staff under him, he should see that one of the technically qualified staff is always at the site of the work during working hours, personally checking all items of works and paying extra attention to such works as may deemed special attention (e.g.) Reinforced Cement Concrete works etc. If the tenderer fails to employ Technical Assistant the recovery will be as follows:

(In the format below enter or incorporate the latest norms fixed by Federation for the employment of Technical Assistant from time to time and penalty for non employment of such Technical Assistant etc.)

| SI.<br>No | Value of contract                          | Qualification and No. of Technical Assistance to be employed                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |  |
|-----------|--------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|
| 1         | Upto Rs. 1.00 lakhs                        | No Technical Assistant need be employed, if situation and nature of<br>work warrants.<br>i. A Diploma holder in Civil Engineering (or)<br>ii. A retired Junior Engineer may be employed.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |  |
| 2         | From Rs. 1.00 lakhs<br>to Rs. 5.00 lakhs   | i. One Diploma holder in Civil Engineering (or)<br>ii. Not less than one retired Junior Engineer                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |  |
| 4         | From Rs. 10.00 lakhs<br>to Rs. 25.00 lakhs | <ul> <li>i. One B.E. (Civil) with 3 years experience plus one diploma holder in<br/>Civil Engineering (or)</li> <li>ii. Equivalent Degree holder with 3 years experience plus one<br/>diploma holder in Civil Engineering (or)</li> <li>iii. Not less than one retired Assistant Executive Engineer / Assistant<br/>Divisional Engineer plus one diploma holder in Civil Engineering (or)</li> <li>iv. Two Diploma Holders in Civil Engineering with 3 and 5 years<br/>experience respectively.</li> </ul>                                                                                                                                                                                                                               |  |
| 5         | From Rs. 25.00 lakhs<br>to Rs. 50.00 lakhs | <ul> <li>i. One B.E. (Civil) with 3 years experience plus two diploma holders i<br/>Civil Engineering (or)</li> <li>ii. One B.E (Civil) with 3 years experience plus two retired Junior<br/>Engineers (or)</li> <li>iii. Equivalent Degree holder with 3 years experience plus two<br/>diploma holder in Civil Engineering / two retired Junior Engineers (or<br/>iv. One retired Assistant Executive Engineer / Assistant Divisional<br/>Engineer plus two diploma holders in Civil Engineering (or)</li> <li>v. One retired Assistant Executive Engineer / Assistant Divisional<br/>Engineer plus two retired Junior Engineers.</li> </ul>                                                                                             |  |
| 6         | From Rs. 50.0 lakhs<br>to Rs. 1.00 Crore   | <ul> <li>i. One B.E. (Civil) with 3 years experience plus two diploma holders in Civil Engineering (or)</li> <li>ii. One B.E (Civil) with 3 years experience plus two retired Junior Engineers (or)</li> <li>iii. Equivalent Degree holder with 3 years experience plus two diploma holder in Civil Engineering / two retired Junior Engineers (or)</li> <li>iv. One retired Assistant Executive Engineer / Assistant Divisional Engineer plus two diploma holders in Civil Engineer / Assistant Divisional Engineer plus two retired Assistant Executive Engineer / Assistant Divisional Engineer plus two retired Junior Engineers.</li> </ul>                                                                                         |  |
| 7         | From Rs.1.00 Crore<br>to Rs.3.00 Crore     | <ul> <li>i. One B.E. (Civil) with 3 years experience plus three diploma holders in Civil Engineering (or)</li> <li>ii. One B.E (Civil) with 3 years experience plus three retired Junior Engineers (or)</li> <li>iii. Equivalent Degree holder with 3 years experience plus three diploma holder in Civil Engineering / three retired Junior Engineers (or)</li> <li>iv. One retired Assistant Executive Engineer / Assistant Divisional Engineer plus three diploma holders in Civil Engineer / Assistant Divisional Engineer plus three diploma holders in Civil Engineering (or)</li> <li>v. One retired Assistant Executive Engineer / Assistant Divisional Engineer plus three diploma holders in Civil Engineering (or)</li> </ul> |  |
| 8         | Above Rs. 3.00<br>Crore                    | i. Two B.E. (Civil) with 3 years experience plus three diploma holders<br>in Civil Engineering (or)<br>ii. Two B.E (Civil) with 3 years experience plus three retired Junior<br>Engineers (or)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |  |

| SI.<br>No | Value of contract | Qualification and No. of Technical Assistance to be employed                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|-----------|-------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|           |                   | <ul> <li>iii. Equivalent Degree holder with 3 years experience plus three diploma holder in Civil Engineering / three retired Junior Engineers (or)</li> <li>iv. Two retired Assistant Executive Engineer / Assistant Divisional Engineer plus three diploma holders in Civil Engineering (or)</li> <li>v. Two retired Assistant Executive Engineer / Assistant Divisional Engineer plus three diploma holders in Civil Engineering (or)</li> <li>v. Two retired Assistant Executive Engineer / Assistant Divisional Engineer plus three retired Junior Engineers.</li> </ul> |

Note:

- 1) Item (1), (2), (3), (4) (5) and (6) should be scored No. 1 out in case where not applicable to the particular work.
- 2) A penalty of **Rs. 10,000/-** per month for Diploma holder
- 3) **Rs. 15,000/-** per month for degree holder will be levied in case of default on the part of contractors in following the norms laid down above.
- 4) The employment of Technical Assistants should be based only on the value of contract. Engineers with Mechanical Engineering qualification and retired from Civil Engineering departments are also suitable to supervise the Civil Engineering works because of their experience in Civil Engineering field.
- 5) In case of contract who is professionally qualified is not in position to remain always at the site of the work and pay extra attention to such work, as many demand special attention (e.g. RCC work etc.) he should employ technically qualified man as prescribed above.
- 11. a) The quantities provided in the schedule are approximate subject to variation up to 25% either way of requirement indicated in the tender schedule. The payment for the work done shall be restricted to the recorded measurement of finished item in sites.

b) The rate for additional items not contemplated in the agreements shall be decided at the discretion of Managing Director as per the principle in vogue in PWD circles and rules applicable to the PWD special buildings circles.

12. a). The tenderer shall inspect the site and satisfy himself about the site condition and soil condition, availability of water etc. and other materials as shown in the lead statement. The rate quoted by the tenderer is final and for finished item of work in site and any claims for enhancement of rate shall not be entertained.

b). Sheds for storing construction materials like cement and steel shall be provided at tenderer's cost, which shall be removed within one month from the date of completion.

c). All tools & plants, and other building materials required for the work shall be arranged by the tenderer himself.

13. The tenderer's special attention is invited to clause 37 and 38 of the Preliminary Specifications of TNDSS and he is requested to provide at his own expense sheds, latrines, and urinals for his workmen.

- 14. If night work is required to fulfill the agreed rate of progress, all arrangements shall be made by the tenderers inclusive of lighting without any claim for extra.
- 15. The tenderer shall not employ the labour below the age of 12 years and shall also note that he must offer employment to ex-servicemen, ex-toditappers, and unemployed agricultural labourers as far as possible.
- 16. Any of the items in the schedule may be omitted or radically altered. No variation in rate shall become payable to tenderer an account of such omission or variation in quantities.
- 17. Reference to TNDSS in the schedule of quantities referred to reprint 1952 and addenda corrigenda issued thereafter.
- 18. The construction of the building will be deemed to be completed only if all the items of works including finishing items contemplated herein are executed.
- 19. The tenderer shall abide by the tenderer's labour regulation of the PW frames by the Tamilnadu Government.
- 20. The tenderer shall be responsible for the safe custody and storage of the materials under dry conditions at the places of the work spot approved by the Engineer.
- 21. No royalty shall be charged where due for materials quarried from the corporation or other Government quarries. Necessary assistance will be given to the tenderer by the corporation to obtain access to quarries approved by the Federation Engineer. No plot rent shall be charged so far materials stacked on the Government land during the course of construction provided all such materials are removed within the month after the work is completed.
- 22. The tenderer shall pay royalty or charges due for use of private quarries and private land.
- 23. The tenderer shall form his own approach road to the work site for which no extra will be due to him. On completion of work, the tenderer shall not be permitted to remove the materials laid for formation of road. If the tenderer is allowed to use the existing roads, he shall maintain them in good condition at his own cost throughout the period of the contract.
- 24. Any surplus materials remaining at the site, will not generally taken over by the Federation, whether before or after the completion or termination of contract. Such materials either which were originally procured by the tenderer or were issued to them by the Department and charged to their accounts, are the property of the tenderers and can however be taken over by Department if required, for use on other works which are in progress only by special arrangements and at the prevailing market rates. Viz. the rates at which the articles of a similar description can be procured at a given time at the stores, go-down from public market suitable to the Federation office for obtaining the supply there-of.

If the Federation originally used the materials, the price allowed to the tenderer on re-acquisition shall not exceed the amount charged to the tenderer excluding the elements of storage charge if any.

The surplus materials, which were originally issued to the tenderer by the Department for use on the work, shall not be removed from the site of work without getting the written permission of the Federation Engineer.

- 25. The tenderer shall at his own expense provide arrangements for the provision of footwear for any labour doing cement mixing work and all other similar type of work involving the use of tar, mortar etc. to the satisfaction of the Engineer-in-charge and on his failure to do so, Federation shall be entitled to provide same and recover the cost from the tenderer.
- 26. When there are complaints of no-payment of wages to the labour, bills of the tenderer may be withheld pending a clearance certificate from the Labour Department.
- 27. Rules for the provision of health and sanitary arrangements for workers employed by the Federation and its tenderers.

The tenderer's special attention is invited to clause 37, 38, 39, and 51 of the preliminary specification to the Tamil Nadu Detailed Standard Specification and he is requested to provide at his own expenses, the following amenities to the satisfaction of the Federation Engineer.

#### 1. FIRST AID:

At the work site, there shall be maintained in a readily accessible place, first aid appliances and medicines including an adequate supply of sterilized dressing and sterilized cotton roll. The appliances shall be kept in a good order. They shall be placed under the charge of a responsible person who shall be readily available during working hours.

#### 2. DRINKING WATER:

- a) Water of good quality fit for drinking purpose shall be provided for the work people on a scale of not less than three gallons per head per day.
- b) Where drinking water is obtained from an intermittent public water supply each work place shall be provide with storage tank where such drinking water shall be stored.
- c) Every water supply and storage shall be at a distance of not less than 15 m from any latrine, drain or other existing well which is within such proximity of latrine, drain or any other source of pollution, the well shall be properly closed if water is drawn from it for drinking. All such wells shall be entirely closed and be provided with a trap door, which shall be dust and waterproof.
- d) A reliable pump shall be fitted to each covered well. The trap door shall be kept locked and opened only for cleaning or inspection, which shall be done at least once in a month.

#### 3. WASHING AND BATHING PLACES:

Adequate washing and bathing places shall be provided separately for men and women. Such places shall be kept in clear and drained condition. Bathing or washing should not be allowed in or near the drinking water well.

#### 4. LATRINES AND URINALS:

There shall be provided within premises of every work place latrines and urinals in an accessible place and the accommodations separately for each of them shall be on the following scale or on the scale so directly by Executive Engineer in any particulars case.

| i.   | Where the number of persons employed does not exceed 50                | 2 Seats |
|------|------------------------------------------------------------------------|---------|
| ii.  | Where the number of persons employed exceed 50 but does not exceed 100 | 3 Seats |
| iii. | For every additional 100 persons                                       | 3 Seats |

If women are employed, separate latrines and urinals screened from those for men shall be provided on the same scale. Except in work places provided with water flushed latrines connected with a water borne sewage system all latrines shall be provided with acceptable dry earth system which will be cleared at least four times daily and at least twice during working hours and kept in strictly sanitary condition. The latrines and urinals shall be tarred inside and outside at least once a year.

Excrete from the latrines shall be disposed off at the tenderer's expenses, in outside pits approved by the local Public Health Authority. The tenderer shall also employ adequate number of scavengers, conservancy staff to keep the latrines and urinals in clean condition.

#### 5. SHELTERS DURING REST:

At the work site, there shall be provided at free of cost, two suitable sheds one for meals and another for rest for the use of labour.

#### 6. <u>CRÈCHE</u>:

At every work place at which 25 or more women working ordinary employed there shall be provided two huts of suitable size for the use of children under the age of 6 years belonging to such women. One hut shall be used for infants, games and play and the other as their bedroom. The huts shall not be constructed on lower standard than the following.

- $\checkmark$  Thatched Roofs.
- $\checkmark$  Mud floors and walls.
- ✓ Planks spread over the mud floor and covered with matting.

The size of the crèche or crèches should vary according to the number of women workers. The crèches should properly maintain and necessary equipment like toys etc. should be provided and huts shall be provided with suitable and sufficient sweepers to keep the place clean. There shall be two ayahs in attendance. Sanitary utensils shall be provided to the satisfaction of the Health Officer of the area concerned.

The number of the huts shall be restricted to children, their attendants, and others of the children.

#### 7. <u>CANTEEN</u>:

A cooked good canteen on moderate scale shall be provided for the benefits of the workers if it is considered expedient.

#### 8. SHEDS FOR WORKMEN:

The tenderer should provide at their own expense sheds for housing the workmen. The sheds shall be on a standard not less than the cheep shelter type to live in which the works pertaining to locality are accustomed to. A floor area of about 1.80 m -1.50 m for two persons shall be provided. The sheds are to be in row with 1.50 m clear spaces between the sheds and 24 m clear space between rows if conditions permit. The work people's camp shall be laid out in units of 400 persons each. Each unit should have clear space of 14.4 m.

28

**9.** Safety provision in the building industry conditions in addition to clause 36 of preliminary specification of TNDSS.

#### <u> PART</u> - <u>I</u>

#### <u>ARTICLE – 1</u>

- 1. Suitable scaffolds shall be provided for workmen for all work cannot be safely done from a ladder or by other means.
- 2. A scaffold shall not be constructed, taken down, or subsequently altered except.
  - a) Under the supervision of a competent and responsible person and;
  - b) By competent workers possessing adequate experience in this kind of work.
- 3. Scaffolds shall be so constructed that no part thereof can be displaced in consequence of normal use.
- 4. Scaffolds shall not be overloaded and so far as practicable and shall be evenly distributed.
- 5. Before installing lifting gear on scaffolds special precautions shall be taken to ensure the strength and stability of the scaffolds.
- 6. A competent person shall periodically inspect scaffolds.
- 7. Before allowing a scaffold to be used by his workmen every employee shall, satisfy as to whether the scaffold has been executed by his workmen or not he should take steps to ensure that it functions fully with the requirement of this articles.

#### ARTICLE - 2

- 1. Working Platforms, gangway and staircase shall be so constructed that no part thereof can sag unduly or unequally.
- a) Be so constructed and maintained to obviate from risks of persons tripping or slipping
- b) Be kept free from any unnecessary obstructions.
- c) Every working platform, gangway, working place, and staircase shall be suitably forced.

#### <u>ARTICLE - 3</u>

- 1. Every opening in the floor of a building or in a working platform shall except for the time and to the extent required to allow the excess of persons or the transport or shifting of materials be provided with suitable means to prevent the fall of persons or materials.
- 2. When persons are employed on a roof where there is danger of falling from height exceeding that to be prescribed by national laws or regulations, suitable precautions shall be taken to prevent the fall of persons or material.
- 3. Suitable precautions shall be taken to prevent persons being struck by articles, which might fall from scaffolds or other working places.

# ARTICLE - 4

- 1. Safe means of access shall be provided to all working platform and other working places.
- 2. Every ladder shall be securely fixed and of such length as to provide secure handhold and foothold at every position at which it is used.
- 3. Every place where work is carried on the mean of approach there to shall be adequately lighted.
- 4. Adequate precautions shall be taken to prevent danger from electrical equipment.
- 5. No material on the site shall be so attached or placed as to cause danger to any persons.

# <u> PART – II</u>

# GENERAL RULES AS TO HOISTING APPLIANCES:

# ARTICLE - 5

- 1. Hoisting machines and tackle including their attachments enhotages and supports shall.
  - a) be of good mechanical construction sound materials and adequate strength and free from patent defects and
  - b) be kept in good repair and in good working order.

Every rope used in hoisting or lowering materials or as a means of suspension shall be suitable quality and adequate strength and free from patent defects.

# ARTICLE - 6

- Hoisting machines and tackle shall be examined and adequately tested after erection on the site and before use and be re-examined in positional intervals to be prescribed by national law or regulations.
- 2. Every chain ring, hook shackle, swivels, and pulley block used in hoisting or lowering materials or as a means of suspension shall be periodically examined.

# ARTICLE - 7

- 1. Every Crane driver or hoisting appliances operator shall be properly qualified.
- 2. No persons under an age to be prescribed by national laws, regulations shall be in control of any hoisting machinery including any scaffold which, or give signals to the operator.

# ARTICLE - 8

- In the case of every hoisting machine and every chain ring, hook shackle, swivel and pulley block used in hoisting or lowering or as a means of suspension, the safe working load shall be ascertained by adequate means.
- 2. In the case of hoisting machine having a variable safe working load, each safe working load and the conditions under which it is applicable shall be clearly indicated.
- 3. Every hoisting machine and all gear referred to in the proceeding paragraphs shall be plainly marked with the safe working load.
- 4. No part of any hoisting machine or of any gear referred to in paragraph 1 of this article shall be loaded beyond the safe working load except for the purpose of testing.
- 5.

# ARTICLE - 9

- 1. Motors gearing, transmission, electric wiring and other dangerous parts of hoisting appliances, shall be provided with sufficient safe guards.
- 2. Hoisting appliances shall be provided with such means as will reduce the risk of the accidental descent of the load.
- 3. Adequate precautions shall be taken to reduce the risk of any part of a suspended load becoming accidentally displaced.

# <u> PART</u> – <u>III</u>

# GENERAL RULES TO SAFETY EQUIPMENT AND FIRST AID

# ARTICLE - 10

- 1. All necessary personal safety equipment shall be kept available for the use of the persons employed on the site and be maintained in a condition suitable for immediate use.
- 2. The workers shall be required to use the equipment thus provided and the employer shall take adequate steps to ensure proper use of the equipment by those concerned.

# ARTICLE - 11

When work is carried on in proximity to any place where there is a risk of drawing, all necessary equipment shall be provided and kept ready for use and all necessary steps shall be taken for the prompt rescue of any person in danger.

# ARTICLE - 12

Adequate provision shall be made for prompt first-aid treatment of all injuries likely to be sustained during the course of the work.

# ARTICLE - 13

Where large work places are situated in cities, towns or in their suburban and no beds are considered necessary owing to the proximity of city or town hospital, suitable transport shall be provided to facilitate removal of urgent cases to the hospitals, at their work places, some conveyance facilities such as car shall be kept readily available to the injured person or persons suddenly taken seriously ill to the nearest hospital.

#### GENERAL QUALITY OF TILES

 Unless otherwise required the wearing face of the terrace tiles shall be mechanically sound and flat. The wearing face of the tiles shall be plane, free from projections, depressions and cracks, (Hair-cracks not included) and shall be reasonably parallel to the back face of tiles. All corners shall be right angles and all edges shall be sharp and true.

| Size of tile     | Span  | Breaking wet test | Land based dry test |
|------------------|-------|-------------------|---------------------|
| 19.85 x 19.85 cm | 15 cm | 71 kg             | 106 kg              |
| 24.85 x 24.85 cm | 20 cm | 90 kg             | 120 kg              |
| 29.85 x 29.85 cm | 25 cm | 99 kg             | 149 kg              |

2. Breaking transverse strength of tiles shall be given as below:

The average wear of not less than 12 specimens shall not exceed 2 mm and the wear on any individual specimen shall not exceed 2.5 cm when tested in an absorption machine.

- 3. The average percentage of water absorption shall not be less than six full tiles shall not exceed ten in the case of water absorption test.
- 4. The density of the tiles shall be in the order of about 2.4 gms. The tiles shall be laid with the minimum possible width of joints and not exceeding 1/32 inch. The joints shall be filled with gray cement to match the finish of the tiles and shall be made almost invisible when the floor is given the final polish. The polishing shall be done by means of electric polisher wherever possible and hand polish to other places like vertical faces, walls, coves and other areas where the machines can have no access and to a high degree so as to present a perfectly smooth and glossy surface as even as possible.

All angles at junctions of vertical faces shall be rounded off to 1½" radius with same quality of materials and colour of the tiles of the floor. But lay in site and these coves shall be measured as part of flooring and laid for at the same rates and the flat floors. The colours of the tiles shall generally match other coloured face adjacent as may be directed by the Federation Officers.

The dadoing and skirting have to be finished by giving necessary recess in the brick wall itself so that the projections does not exceed <sup>3</sup>/<sub>4</sub>" from the face of the wall i.e. the finish plastered surface

Based on the modulus or rapture of 30 kg./m<sup>2</sup> for dry test and 2/3 of the value of wet test.

- 5. The rates quoted by the tenderer should include all de-watering charges.
- 6. The works shall be proceeded with expeditiously from the date of the site is handed over and completed within the prescribed schedule.
- 7. In the event of the work being transferred to any other Department like PWD to execute all the powers and privileges reserve in favour of the Federation.
- The materials used for work should be of best quality and to be got approved by the Federation Engineers / Officers and approved samples are to be kept at site of work till the completion of the work.
- 9. The tenderer will be paid only for finished items of works.
- 10. All fittings of furniture for doors and windows shall be best quality steel machine made and wall japanned. The iron hold fasts shall be built up in the wall in cement mortar 1:3 at the time of construction of walls. No extra claim shall be made for the same.
- 11. In the case if 'T' beams and 'L' Beams, the quantity of rib portion only. The top flange portion will be always measured with the general slab portion and paid for at the slab rate only. For all RCC work the rate shall include the treatment of bearing as per plate W.No.2 of 1946 as per MDSS (Page 52 of 1952 Edition).
- 12. The tenderer should cooperate with the tenderer for erection of machinery and provide him with necessary holes in the masonry and subsequently refill, without extra cost. There should be cooperation with the tenderers for the civil works and machinery.
- 13. In the case of earthwork excavation in hard rock requiring blasting the tenderer should observe the following condition.

i). The blasting rock shall be compactly stacked for measurement. The net quantity of blasted rock shall be arrived by allowing a deduction of 40% of voids and compared with pre-measured quantity and only the lesser of the two shall be paid.

ii). When the rock other than hard rock and hard rock mixed upon ground the two kinds of rocks shall be stacked separately for measurement. The net measurement of the two kinds of rock shall be arrived by allowing 40% deductions for voids. The total of the net measurements of two kinds of rocks shall be compared with the premeasured quantity and only lesser of the two kinds of rock shall be paid for. If the total of net measurements if the two kinds of rocks exceeds or falls short of measurement of mixture the volume of mixture proposed to be paid shall be apportioned in the proportion of the actual measurements of stacks of the two kinds of rock. <u>NOTE</u>:

- a) 40% deduction for voids shall be adopted for compact and proper stacking but such deduction shall be increased for loose or improper stacks.
- b) The blasted rock materials stacked, measured, and paid for shall become property of the Department.
- c) IS Code No. 1200 (Part I) 1969 method of measurement of building and Civil Engineering works Pare-I earthwork may be referred to.

EXTRACT OF:

#### NATIONAL BUILDING CODE OF INDIA 1970

#### PART – VI, SECTION 5-A: PLAIN AND REINFORCED CONCRETE

#### 4.2. <u>GRADE OF CONCRETE</u>.

**4.2.1**. Plain and Reinforced Cement Concrete shall be in seven grades as designed M100, M150, M200, M250, M300, M350, and M400.

**NOTE**: In the designation of a concrete mix, letter "M" refers to the mix and the number of the specified 28 days of works cube compressive strength of that mix expressed in Kg./cm<sup>2</sup>.

**4.2.2.1**. Where ordinary port-land cement or port-land blast furnace slag cement conforming to accepted standard VI.5 (2) IS 269/1967 specification for ordinary rapid hardening and low heat port-land cement.

IS 455/1967 specifications for port-land and blast furnace slag cement is used. The compressive strength requirements for various grades of concrete shall be as given in Table-1. Where rapid hardening port-land cement is used, the 28 days compressive strength requirements specified in Table-1 shall be met at 7 days where other cement are used, the Engineer-in-charge shall specify the corresponding requirements preferably on the basis of preliminary test.

**4.2.2.2.** The strength requirements specified in Table-1 shall apply to both controlled concrete and ordinary concrete (see 4.3.1) preliminary tests need not however be made in the case of ordinary concrete.

1. In order to get a relatively quicker idea of the quality of concrete optional works tests on beams for modulus of rupture at 72 + 2 hours or at 7 days or compressive strength tests at 7 days may be carried out in addition to 28 days compressive strength test. In all cases, the 28 days compressive strength specified in Table-1 shall alone be the criteria for acceptance or rejection of the concrete. If however from tests carried out in a particular job over a reasonably long period, it has been established to the satisfaction of the Engineer-in-charge that a suitable ratio between the 28 days compressive strength and the modulus of rupture at 72 + 2 hours or at 7 days or compressive strength at 7 days may be accepted. The Engineer-in-charge may suitably relax the frequency of 28 days compressive strength test specified in Table 5 provided the expected strength values given at the specified early age are consistently met. For this purpose the values given in

table 2 may be taken for general guidance in the case of concrete made with ordinary cement.

- 2. Whether the strength of a concrete mix as indicated by test lies between the strength for any two grades, specified in Table-1, such concrete shall be classified for all purposes as a concrete belonging to the lower of the two grades between which its strength lies.
- 4.3 <u>PROPORTIONING AND WORKS CONTROL.</u>
- 4.3.1. METHODS OF PROPORTIONING:

The determination of the proportion of cement aggregate and water to attain the required strength shall be made by one of the following:

- a. With preliminary tests by designing the concrete mix. Such concrete shall be called controlled concrete.
- b. Without preliminary tests by adopting nominal concrete mixes. Such concrete shall be called ordinary concrete.

#### 4.3.2. <u>CONTROLLED CONCRETE:</u>

**4.3.2.1**. As far as practicable, controlled concrete should be used on all concrete works. Controlled concrete for use in plain and reinforced concrete structures shall be in grade M 100, M 150, M 200, M 250, M 300, M 350, and M 400.

**4.3.2.2**. The concrete mix shall be designed to have a average strength corresponding to the values specified for preliminary test in Table-1. The proportions chosen should be such that the concrete is of adequate workability for the conditions prevailing on the work in question and may be properly compacted with the means available.

The maximum total quantity of aggregate by weight per 50 Kg. of cement shall not exceed 450 Kg. except where otherwise specifically permitted by the Engineer-in-Charge.

**4.3.2.3.** Except where it can be shown to the satisfaction of the Engineer-in-charge that supply of properly graded aggregate of uniform quality may be maintained over the period of work, the grading of aggregate should be controlled by obtaining the coarse aggregate in different sizes and blending them in the right proportion when required the different sizes being stocked in separate stock piles. The materials should be stock piled for several hours preferably a day before use. The grading of course and fine aggregate should be checked as frequently as possible, the frequency for a given job being determined by the Engineer-in-charge to ensure that the suppliers are maintaining the grading uniform with that on the samples used in the preliminary tests.

**4.3.2.4**. In proportioning concrete the quantity of both cement and aggregate should be determined by weight. Where the weight of cement is determined by accepting the manufacturer's weight per bag, a reasonable number of bags should be weighed separately to check the net weight. Where the cement is weighed on the site and not in bags it should be weighed separately from the aggregates. Water should be either measured by volumes in calibrated tanks or weighed. All measuring conditions and their accuracy may be periodically checked.

**4.3.2.5**. It is most important to maintain the water cement ratio constant at its correct value. To this end, determination of moisture contents in both fine and coarse aggregates should be made as frequency as possible the frequency for given job being determined by the Engineer-in-charge according to weather conditions. The amount of the added water should be adjusted to compensate for any observed variations in the moisture contents. Their determination of moisture content in the aggregate shall be carried out in accordance with good practice (VI-5-9) IS 2386 Part III-1963. To allow for the variation in weight of aggregates due to variation in their moisture content suitable adjustment in the weight of aggregate should also be made.

**4.3.2.6.** On substitution in materials used on the work or alteration in the established proportions except as permitted in 4.3.2.5 shall be made without additional tests to show that the quality and strength of concrete are satisfactory.

**4.3.2.7**. Workability of the concrete should be checked at frequent intervals. To slump test or where facilities, exist the compacting factor test conducted in accordance with good practice [VI-5 (10)] may adopted for this purpose.

**4.3.2.8.** A competent person should be employed whose first duty will be to supervise all stages in the preparation and placing of the concrete. All works test specimens should be made and site tests carried out under his direct supervision.

#### 4.3.3. ORDINARY CONCRETE:

**4.3.3.1**. Where, it is considered not practicable to use controlled concrete and ordinary concrete may be used for concrete of grades M 100, M 150, M 200, M 250. The proportions of materials for nominal concrete mixes for ordinary concrete shall be in accordance with Table-3.

**4.3.3.2.** In proportioning concrete, the quantity of cement should be determined by weight. The quantity of fine and course aggregates may be determined by volume but these should also preferably be determined by weight. In the latter case, the weight should be determined from the volume specified in Table-3 and the weight per litre of dry aggregate. If fine aggregate is moist and volume batching is adopted, allowances to be made for bulking in accordance with good practice [VI-5 (9)].

4.3.3.3. The water cement ratio shall not be more than those specified in Table-3.

The cement content of the mix specified in Table-3 for any nominal mix may be increased if the quantity of water in a mix has to be increased to overcome the difficulties of placement and compaction, so that the water cement ratio specified in Table-3 is not exceeded.

**NOTE 1**: In the case of vibrated concrete, the limit specified may be suitably reduced to avoid segregation.

**NOTE 2**: The quantity of water used in the concrete mix for reinforced concrete work should be sufficient, but should not be more that what is sufficient to produce a dense concrete of adequate, workability for the purpose, which will surround and properly grip, all the reinforcement, workability of the concrete should be controlled by maintaining a water cement ratio that is found to give a concrete which is just sufficient wet to be placed and compacted without difficulty with the means available.

**4.3.3.4**. Workability of the concrete should be controlled direct measurement of water content, making allowance for any surface water in the fine and course aggregates. The slump test may be conducted in accordance with good practice [VI-5(10)].

**4.3.3.5.** Allowance should be made for surface water present in the aggregate when computing the water content. Surface water shall be determined by field methods in accordance with good practice [VI-5 (9)]\*. In the absence of exact date the amount of surface water may be estimated from the values given in Table-4.

**4.3.3.6**. If ordinary concrete made in accordance with the proportions given for a particular grade does not yield the specified strength due to proper qualities of materials not being available, such concrete shall be classified as belonging to the appropriate lower grade.

Ordinary concrete proportioned for a grade given in accordance with Table-3 shall not however, be placed in a higher grade on the ground that the test strengths are higher than the minimum specified. No interpolation shall be permissible.

4.4. SAMPLE SIZE OF ACCEPTANCE CRITERIA.

4.4.1. All tests shall be carried out in accordance with good practice [VI-5 (4)]. +

**4.4.2**. The number of test specimens required, the frequency of the sampling and the criteria for acceptance of a concrete as conforming to the specified grade shall be in accordance with Table-5 for both ordinary concrete and controlled concrete. No preliminary tests are however necessary in the case of ordinary concrete.

IS 199-1959 methods of sampling and analysis of concrete?

\* IS 2386 (Part III) 1963 specific gravity, density, and voids absorption and bulking methods of tests for aggregate of concrete?

Specified density, gravity, voids absorption, and bulking.

• IS 516-1959 methods of tests for strength of concrete.

# TABLE - 1.STRENGTH REQUIREMENTS OF CONCRETE

# (CLAUSE 4.2.2.1 and 4.2.2.2) (All Values in kg/cm<sup>2</sup>)

Compressive strength of 15 cm cubes at 28 days after mixing conducted in accordance with good practice [VI 5(4)]~.

36

| Grade of Concrete | Preliminary tests Minimum | Works test Minimum |
|-------------------|---------------------------|--------------------|
| M 100             | 135                       | 100                |
| M 150             | 200                       | 150                |
| M 200             | 250                       | 200                |
| M 250             | 320                       | 250                |
| M 300             | 380                       | 300                |
| M 350             | 440                       | 350                |
| M 400             | 500                       | 400                |

#### NOTE 1: PRELIMINARY TEST:

A test conducted in a laboratory on the mix\* of the concrete produced in the laboratory with the object of

a. Designing a concrete mix, before the actual concreting operation starts.

- b. Determining the adjustments required in the designed mix when there is a change in the mater also used during the execution of work, or
- c. Verifying the strength of concrete mix.

#### NOTE 2: WORK TEST:

A test conducted either in the field or in laboratory on the specimens made out of the concrete being used on the works.

#### NOTE 3: SIZE OF CUBES:

In the working test, with the approval of the Engineer-in-charge, 10 cm cubes may be used in place of 15 cm cubes provided the maximum nominal size of aggregate does not exceed 20 mm. Even the use of 15 cm cubes should normally be restricted to concrete having a maximum nominal size of aggregate not exceeding 40 mm. Where concrete with aggregates larger than 40 mm size is required to be tested, the size of cubes should be specified by the Engineer-in-charge, keeping in view that generally the length of size of the cube should be about four times the maximum nominal size of aggregate in the concrete constituting the cubes specimen.

#### NOTE 4: STRENGTH IN RELATION TO SIZE OF THE CUBE:

Where 10 cm cubes are used, the values obtained from tests on 10 cm cubes shall be reduced to the extent established by comparative preliminary tests with 10 and 15 cm cubes, or in the absence of such comparative tests, by 10 % of the value determined from the tests, in order to give the equivalent strength for 15 cm cubes, when cubes larger than 15 cm are adopted, generally no modification is necessary unless otherwise specified by the Engineer-in-charge.

~IS 516-1959 methods of test for strength of concrete

<u>NOTE 5:</u> Cylinder strength - compressive strength test may, with the approval of the Engineerin-charge, be conducted on 15 cm diameter and 30 cm high cylinders in accordance with good practice [VI-5 (4)\*] instead of one cube, where cylinder strength figures adopted the compressive strength figures given above shall be modified according to the formula. Minimum cylinder compressive strength requires, 0.8, compressive strength specified for 15 cm cubes.

\*THE CENTRAL BOARD RESEARCH INSTITUTE, New Delhi has carried out tests with a view to establishing a relation between water cement ratio and the compressive strength of concrete using ordinary port-land cements manufactured in the country confirming to accepted standards [VI-5 (2)].\*\*

As a result of these, it has been considered advisable to give graphs showing the relationship between the compressive strength of concrete mixes with different water cement ratios and the 7 days compressive strength of cement tested in accordance with good practices [VI-5 (2)]\*\*. These graphs have been given in Appendix-A as they would be some assistance in obtaining the water cement ratio for trail mixes of concrete.

#### TABLE - 2: OPTIONAL WORKS TEST REQUIREMENTS OF CONCRETE

#### CLAUSE 4.2.2.2.(a) (All Values in kg/cm<sup>2</sup>.)

| Grade of |        | Compressive strength of 15 | Modulus of rupture by Beams Test |            |  |  |
|----------|--------|----------------------------|----------------------------------|------------|--|--|
| Cor      | ncrete | cm cubes minimum at 7 days | At 72+2 hours                    | At 7 hours |  |  |
| М        | 100    | 70                         | 12                               | 17         |  |  |
| М        | 150    | 100                        | 15                               | 21         |  |  |
| М        | 200    | 135                        | 17                               | 24         |  |  |
| М        | 250    | 170                        | 19                               | 27         |  |  |
| М        | 300    | 200                        | 21                               | 30         |  |  |
| М        | 350    | 235                        | 23                               | 32         |  |  |
| М        | 400    | 270                        | 25                               | 34         |  |  |

All tests shall be conducted in accordance with good practice [VI-5(4)\*].

#### <u>NOTE:</u>

Notes 3 to 5 under Table -1 are also applicable to this Table.

- \* IS 516-1959 Methods of test for strength of concrete.
- IS 269-1967 Specification for ordinary, rapid, hardening, and low heat port-land cement.

#### CONCRETE MIX PROPORTIONS

#### (CLAUSE 4.3.3.) ORDINARY CONCRETE

| Grade of<br>Concrete | Total quantity of dry<br>aggregates by volume per 50<br>Kg. of cement to be taken as<br>the sum of the individual<br>volumes of fine and coarse<br>aggregates Max | Proportion of fine<br>aggregate to coarse<br>aggregate | Quantity<br>of water<br>per 50 kg<br>of cement |
|----------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------|------------------------------------------------|
| M 100                | 300 litres                                                                                                                                                        | Generally 1:2 for fine                                 | 34 litres                                      |
| M 150                | 220 litres                                                                                                                                                        | aggregate by volume<br>but subject to an upper         | 32 litres                                      |
| M 200                | 160 litres                                                                                                                                                        | limit of 1: 1½ and a lower                             | 30 litres                                      |
| M 250                | 100 litres                                                                                                                                                        | limit of 1:3 *                                         | 27 litres                                      |

**NOTE:** It may be noted for general guidance that M 100, M 150, M 200 and M 250 of ordinary concrete correspond approximately to 1:3:6, 1:2:4, 1:1½:3 and 1:1:2 nominal mixes of ordinary concrete currently used in the country.

\* The proportions of the aggregate should be adjusted from upper limit to lower limit progressively as the grading of fine aggregate becomes finer and the maximum size of coarse aggregate becomes larger. Example, for an average grading of fine aggregate that is, Zone II in accordance with good practice [VI-5 (1)] # the proportion shall be 1:1½, 1:2 and 1:3 for maximum size of aggregate 10 mm, 20 mm and 40 mm respectively.

#### <u>TABLE - 4</u>.

#### SURFACE WATER CARRIED BY AVERAGE AGGREGATE

| Aggregate                     | Approximate quantity of surface water lit/m <sup>3</sup> |
|-------------------------------|----------------------------------------------------------|
| Very wet sand                 | 120                                                      |
| Modulate wet sand             | 80                                                       |
| Moist sand                    | 40                                                       |
| *Moist gravel or crushed work | 20 to 40                                                 |

\*Coarser the aggregate, less the water it will carry.

# IS 383-1963 Specification for coarse and fine aggregates for natural sources for concrete.

IS 516-1959 Specification for natural and manufactured aggregates for use in mass concrete

|                                                                    | Ρ                                 | RELIMINARY                                        | TEST                                                                                                                                                                                                                                                                                                                                             | WORKS TEST |                            |                                                                    |                                   |                                               |                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                                                                                                          |                    |                            |
|--------------------------------------------------------------------|-----------------------------------|---------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|----------------------------|--------------------------------------------------------------------|-----------------------------------|-----------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|----------------------------|
| Minimum No. of<br>specimen from                                    | each batch<br>[cubes]             |                                                   |                                                                                                                                                                                                                                                                                                                                                  | sp         | ecir<br>om                 | num N<br>men to<br>the sa<br>ys wor                                | ıken<br>me                        | Minimu                                        | m frequency                                                                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                          |                    |                            |
| 7 days compressive strength test<br>as an optional test if desired | 28 days compressive strength test |                                                   | Minimum<br>frequency                                                                                                                                                                                                                                                                                                                             |            | Criteria for<br>acceptance | 7 days compressive strength test<br>as an optional test if desired | 28 days compressive strength test | 72+2 hrs. test as an optional test if desired | 7 days test as an optional test if desired                                                                                                                         | In terms of the quantity of concrete                                                                                                                                                                                                                                                                                                                                                     | In terms of period | Criteria for<br>acceptance |
| 5                                                                  | 5                                 | batch<br>with a<br>minimum<br>of three<br>batches | Accept if<br>average<br>compressive<br>strength of the<br>specimens<br>tested is not<br>less than the<br>compressive<br>strength<br>specified in<br>Table 1 [for<br>optional test<br>see Table 2]<br>subject to the<br>conditions<br>that only one<br>out of five<br>consecutive<br>tests may give<br>a value less<br>than specified<br>strength |            | 3                          | 3                                                                  | 3                                 | concrete<br>or part<br>thereof                | intervals as<br>the Engineer-<br>in-charge<br>may decide.<br>However, in<br>the case of<br>controlled<br>concrete,<br>samples shall<br>be drawn on<br>each day for | Accept if<br>average<br>strength of the<br>specimens<br>tested is not less<br>than the strength<br>specified in<br>Table 1 [for<br>optional tests<br>see table 2]<br>subject to the<br>conditions that<br>only one out of<br>three<br>consecutive tests<br>may give a<br>value less than<br>specified<br>strength but this<br>shall not be less<br>than 90 % of<br>specified<br>strength |                    |                            |

| PRELIMINARY TEST                                                   |                                   |                                                   |                                                                                                                                                                                                                                                                                                                                                                                                               |     |                |                              | WOR | KS TEST                        |                                                                                                                                                                                        |                                                                                                                                                                                                                                                                                                            |                                                  |                                            |                                                  |                       |                            |
|--------------------------------------------------------------------|-----------------------------------|---------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|----------------|------------------------------|-----|--------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------|--------------------------------------------|--------------------------------------------------|-----------------------|----------------------------|
| Minin<br>No.<br>spec<br>n fro<br>eao<br>bat<br>[cub                | of<br>ime<br>om<br>ch<br>ch       |                                                   |                                                                                                                                                                                                                                                                                                                                                                                                               | spe | ecime<br>the s | m No<br>en tak<br>ame<br>ork | en  | Minimum frequency              |                                                                                                                                                                                        |                                                                                                                                                                                                                                                                                                            |                                                  |                                            |                                                  |                       |                            |
| 7 days compressive strength test as<br>an optional test if desired | 28 days compressive strength test | Minimum<br>frequency                              | Minimum<br>frequency                                                                                                                                                                                                                                                                                                                                                                                          |     |                |                              |     | Criteria for<br>acceptance     | 7 days compressive strength test as<br>an optional test if desired                                                                                                                     | 28 days compressive strength test                                                                                                                                                                                                                                                                          | 72+2 hrs. test as an optional test if<br>desired | 7 days test as an optional test if desired | In terms<br>of the<br>quantity<br>of<br>concrete | In terms of<br>period | Criteria for<br>acceptance |
|                                                                    | 10                                | batch<br>with a<br>minimum<br>of three<br>batches | Accept if<br>average<br>compressive<br>strength of the<br>specimens<br>tested is not<br>less than the<br>compressive<br>strength<br>specified in<br>Table 1<br>subject to the<br>condition that<br>the average<br>compressive<br>strength shall<br>be more than<br>the specified<br>compressive<br>strength in<br>Table 1 by<br>atleast the<br>value of<br>standard<br>deviation* of<br>the series of<br>test | 5   | 5              | 5                            | 5   | concrete<br>or part<br>thereof | intervals as<br>the Engineer-<br>in-charge<br>may decide.<br>However, in<br>the case of<br>controlled<br>concrete,<br>samples shall<br>be drawn on<br>each day for<br>the first 4 days | Accept if<br>average<br>strength of the<br>specimens<br>tested is not less<br>than the<br>strength<br>specified in<br>Table 1 [for<br>optional tests<br>see Table 2]<br>subject to the<br>condition that<br>one out of five<br>consecutive<br>tests may give a<br>value less than<br>specified<br>strength |                                                  |                                            |                                                  |                       |                            |

\* Standard deviation: Where d = Individual deviation from the average and n = Number of specimens tested.

#### FOR TENDERER'S SPECIAL ATTENTION

- 1. "M" or "P" sand shall be used in all cases as per PWD norms.
- 2. Only clean fresh water shall be used on the work. The tenderer shall make their own arrangements for water and shall meet all charges therefore. The special attention of the tenderer is drawn to clause 39 of preliminary specification of the TNDSS regarding water and lighting.
- 3. The broken stone for concrete and RCC works should be of granite and passed by the Federation Engineer / Officer.
- 4. All iron work or steel work of every kind such as to be embedded in concrete shall immediately on arrival at the site be properly scrapped and wire brushed and given priming coat of approved lead painting without claim for extra.
- 5. The iron hold fasts shall be built up in walls in cement mortar 1:3 at the time of construction of walls. No extra claim shall be due for the same wherever hold fasts are to be provided to 9" thick walls. Those should be fixed with cement concrete 1:3:6 using 20 mm gauge broken granite stone jelly for proper anchorage and proper binding. No separate rate for such pockets of concrete filling at hold fast points will be allowed and this will be measured as masonry along with adjacent masonry.
- 6. Holes for electric wiring, water supply and drainage etc., shall be provided as directed during progress of work without any claim for extra.
- 7. The work will be carried with the least hindrance to the adjoining building and the tenderer will be responsible for any damages, caused to the existing fixtures, electric fittings, etc. in the course of execution and the tenderer shall make good any damages without any claim for extra.
- 8. In the case of `T' beams and `L' beams, the quantity shown in the schedule is the quantity of rib portion only. The top flange portion will be always measured with the general slab portion and paid for at the slab rate only. For all RCC works the rate shall include the treatment of bearing as per plate No. 2 of 1946 as per TNDSS (Page 3 of 1964 Edition).
- 9. <u>CONCRETE WORK</u>: All exposed concrete surfaces will be required to be finished by cement plaster as detailed in schedule `A'.
- 10. <u>PLASTERING</u>: All external corners, edges of beams, edges of doors and window openings etc., shall be finished sharp using richer mortar and also finished truly vertical or horizontal as the case may be. The rate for plastering shall include the cost of finishing as above and no separate extra for the corners, edges, and beams etc., shall be paid.
- 11. If rates are not separately called for, for similar items of works in different floors, the tenderer should note that one rate is applicable for all floors indicated in the detailed

plans. Any claims for extra for such items in different floors will not be entertained under any circumstances.

- 12. The Managing Director reserves the right, to split up the work and entrust the main work, internal water supply and sanitary arrangements to different tenderers without assigning any reason therefore.
- 13. The projection if any to the masonry will be measured under the relevant items and no extra will be paid for finishing the same.
- 14. a). The work in the Federation executed by the tenderer, under the contract shall be maintained by the tenderers until the work is taken over by the Federation Engineer. The tenderer shall accordingly arrange his own insurance against fire, flood, volcanic eruption, earthquake, other convention of nature and all other natural calamities risks arising out of acts of God during such period and that the Federation shall not be liable for any loss or damage occasioned by or arising out of any such acts of God.

b). Provided however that the tenderer shall not be liable for all or any loss or damages occasioned by or arising out of acts of foreign enemies, invasion hostilities or war like operations (before or after declaration of war) rebellion, Ministry or usurped power.

#### **REVENUE RECOVERY ACT**

c). Whenever any amount has to be paid by the tenderer in view of termination of the contract by virtue of clause 87 (4) any amount that may be due or may become due from the tenderer under their presents and the tenderer is not responding to the demands for the payment of said amount, then the Federation shall be entitled to recover the said amount under the provision of the Revenue Recovery Act.

#### **RISK INSURANCE**

d). The work executed by the tenderer or under these contract shall be maintained by the tenderer's risk until the work is taken over the Federation Engineer. The Federation should not be liable to pay for any loss or damages occasioned by (or) arising out of fire, flood, volcanic, eruption, earth-slake other conclusion of nature and all other natural calamities risks arising out of acts of God during such period and that the option whether to take insurance coverage (or) not to care such risks is lift to the tenderer.

The tenderer shall not be liable for all or any loss of damages occasioned by or out of acts of foreign enemies' invasions, hostilities or war like operation (before or after declaration of war) rebellion, military or usurped power.

#### **ADDITIONAL SPECIFICATIONS**

- 1. The arrangements of M.S. & RTS rods for all RCC works shall be in accordance with the working drawing supplied.
- 2. i). The planks for forms and centering for RCC works shall be of well seasoned timber approved by the Federation Engineer according to clause 10 of TNDSS No. 30. They must be made smooth and perfectly level at top so as to give smooth and even finish to the RCC ceilings. Alternatively, the tenderer may use steel sheets over wooden forms provided the required finish to the outside of the slab is obtained. Mango planks shall not be used under any circumstances. Centering and form work shall be provided to the extent and area ordered by the Federation Engineer during execution.

ii). Payments for centering works for all RCC items shall be made only after the concrete is laid, even though separate items for centering works are included in the schedule. The centering and form shall be provided to the extent and area ordered by the Federation Engineer during execution.

- iii). All cement concrete for RC works shall be machine mixed and vibrated.
- iv). All lime mortar shall be ground in mortar well as per TNDSS.

#### **ADDITIONAL CONDITION**

#### SPECIFICATION FOR SANITARY, DRAINAGE AND WATER SUPPLY ARRANGEMENTS

- 1. Water closets, basins, urinals, sinks and other sanitary-ware shall be approved make as required in the relevant items. The fixing of these shall be in accordance with the specification attached.
- 2. The rates shall include all dismantling, making holes in walls or slabs, and restoring the structure to the original conditions after the completion of the work.
- 3. The work should be carried out with least hindrance to the adjoining buildings and the tenderer shall be responsible for any damage caused to the existing fixtures, electrical fittings etc. in the course of execution and the tenderer shall make good any such damage without claim for extra.
- 4. The rate for laying stoneware pipes shall include necessary earthwork excavation for trenches (irrespective of nature of soil and depth) and all incidental charges such as shoring, strutting and balling out water, refilling trenches after the completion of work and consolidating, removing the surplus earth to places shown within the compound and making good the damages to roads and other structure.
- 5. The rate for laying GI Pipes and CI Pipes (or PVC Pipes) shall include earthwork for trenching and refilling them and fixing with wooden plugs, GI /CI clamps and brass screws where the pipes are fixed to walls. The rates for the pipes shall also include wrapping them with tarred tape where they are buried in earth tarring the portions

#### 44

embedded in masonry and painting with white lead two coats for portions above ground level.

- 6. The clamps for GI Pipes, fittings should not be spaced more than 150 mm apart. The wooden plugs for pipe and bracket fittings should be properly fixed in CM 1:3 in holes made in masonry with the wide and wedge shaped plugs inside and not hammered with them and into walls. The size of plugs should not be less than 1 square inch at one end and 1½ square inch at other end with a depth not less than 9 inch.
- Paint with two coats of best white glazed paint or any other colour approved by the Federation Engineer over a priming coat of red lead to all flushing tanks, brackets, clamps used for fixing pipes and all lead connections.
- 8. The tenderer should employ sufficient number of qualified licensed plumber with necessary experience and skill in the trade to the satisfaction of the Federation Engineer concerned for execution of water supply and sanitary fittings of work.
- 9. The Indian Type Water Closet shall be with `P' or `S' trap and glazed earthenware footrests it shall be fixed in position of floor level in a bed concrete brick jelly in lime mortar 1:2 so as to completely embed the closet, trap and footrests. The existing masonry structure after dismantling the floor making the holes etc. shall be restored to its original conditions after completing the work. The flooring round the closet shall be finished off in cement mortar with adequate slope all round for drainage into as per the sanitary Engineer's type design. The footrests should be fixed at an angle as per standards.
- 10. The PVC flushing tanks shall be of three gallons capacity of Indian make (confirming to ISI specification) supported on CI brackets with necessary GI chain and handle for pull float bell valve ½" PVC connections to the water main and closet including prior to the white glazed paint two coats over a priming coat of red lead.
- 11. The fixing of water closet shall include the dismantling of existing floor wherever indicated making holes in masonry walls etc. and restoring structure to original condition after completion of the work. The flushing tank and accessories will be fixed to the walls with necessary clamps and brackets in cement mortar 1:4.

#### ADDITIONAL CONDITION FOR TENDERER'S SPECIFIC CONDITION

If at any time the Federation Engineer shall be of the opinion that the tenderer is delaying commencement of the work or violating any of the progress of work is defined by the tabular statement rate of progress in the article of agreement the Federation Engineers shall also advise the tenderer in writing and at the same time demand compiled. If the tenderer neglects to comply with such demand within 7 days after the receipt of the notice it shall those or at any time thereafter be lawful for the Managing Director to determine the contract. Which determination shall carry with the forfeiture of the security deposit and total sum of the amount withheld from the final bill together with value of such work as may have been executed and not paid for such proportion of such total sums as shall be assessed by the Federation Engineer.

The water for the works shall be as far as practicable free from earth vegetable or organic matter and from salts or other substance likely to interfere with the setting of mortar or otherwise prove harmful to the work.

All terms of works shall be done in accordance with relevant classes of TNDSS and addenda volume to the TNDSS or addenda from time to time.

The tenderer shall be responsible for the safe custody of all the departmental materials once they are handed over to the tenderer at the departmental stores. The cost of any materials in the custody of the tenderer stolen, destroyed or damaged or if rendered unfit for the work will be recovered from the tenderer at the issue rate.

For testing the concrete and aggregate the tenderer must procure the following equipment and make them available at site.

- a) Steel mould for 45 cm cubes of concrete (the mould will be in two halves for easy removal).
- b) Slump cone for testing consistency (slump test) the cone will be 30 cm height truss castled cone with top and bottom diameters of 20 cm and 30 cm respectively. In addition a steel rod 25 cm dia and 50 cm in length and with tamping and rounded is to be procured.
- c) For finishing fineness moulds, and coarse aggregate expand operated over apparatus may be procured along with weighing machine for weighing the aggregate and sand.
- d) In the case of any breach of the terms of the contract the contract will be closed at the risk of cost of the tenderer in addition to the forfeiture of the EMD and security deposit.
- e) The testing is to be done at the tenderer's cost for all building materials and also for concrete cubes.
- f) The work shall be executed and measured as per metric dimension given in the schedule of quantities, drawings etc. (F.P. Units where indicated are for guidance only).
- g) Unless otherwise specified all the rates quoted by the tenderers shall be for works at all levels of the buildings.
- h) Rates for every item of works to be done under this contract shall be for all lifts and leads, heights, depths, lengths and widths except when specifically mentioned in the item, otherwise nothing extra will be paid on this account.
- i) The rate for all item in which use of cement is involved is inclusive of charges for curing.

46

#### ADDITIONAL CONDITIONS

#### WATER SUPPLY FOR CONSTRUCTION AND OTHER USE

Unless otherwise specified the tenderer shall make their own arrangement for water for the work and nothing extra shall be paid for the same.

The water used by the tenderer shall be fit for drinking as well as construction purposes to the satisfaction of the Federation Engineer.

The tenderer may be allowed to construct temporary tube well / open well in the project site for getting water after he has got written consent of the Federation Engineer. The tenderer shall be required to provide necessary arrangements to avoid any accident or damage to the buildings, roads and service lines adjacent to the tube well / open well sunk. The tenderer shall dismantle the tube well / open well after completion of work and restore the ground to its original condition at their cost.

In case the Federation supplies water, it shall be on the following conditions:

- 1. Water charges at 0.50 % shall be recovered from the total value of contract from each interim bill.
- The water shall be provided at one point in the site at the discretion of the Engineer. The tenderer shall make their arrangement for water connection and distribution pipelines in the construction area.
- 3. The Federation shall not guarantee the maintenance of uninterrupted water supply. It will be the responsibility of the tenderer to make alternative arrangements for water supply at their own cost in the event of any breakdown so that the progress of work is not affected for want of water. No claim or damage or refund of water charges shall be entertained on account of such breakdown.

#### POWER (ELECTRICITY) SUPPLY

Successful contractor shall make own arrangement to obtain temporary EB connection from TNEB for the construction work at his own cost and EB bill amount should be settled as per claims. All the works shall be done as per IEA rules. The temporary lines shall be removed by the tenderer at his cost after the completion of the work or if there is any hindrance, to the other works due to the alignment of these lines, during the contract period.

In case the Federation provides the power supply, it shall be on the following conditions:

1. The supply shall be made at one point in the site at the discretion of the Engineer. The tenderer shall make their own arrangement to carry and distribute the power wherever it is required within the site as per IEA rules. An Energy Meter shall be installed at the site by the tenderer for recording the power consumed by the tenderer and the same shall be recovered at the prevailing rate of supply of electricity by the local electricity board or other local authorities as the case may be.

(or)

- 2. If the Energy meter is not fixed for taking readings/faulty the electricity charges shall be recovered from the interim bills at the rate of 0.50 % of the value of work done during that particular period.
- 3. Power required for commissioning and trial runs of the plant shall be supplied free of cost.
- 4. The Temporary supply lines shall be removed and the tenderer shall be clear the site after the completion of work at their own cost .

#### SCHEDULE `A'

#### SCHEDULE OF RATES AND APPROXIMATE QUANTITIES

The quantities given here and those upon which the lump-sum tender most of the work is based but they are subject to alteration, omissions, deductions and additions as provided for in the condition of their contract and do not necessary to show the actual quantities of work to be done. The unit rates noted below is this governing payment for extras or deductions or omissions according to the conditions of contract as set for in the preliminary specifications of the Tamil Nadu Detailed Standard Specification and other condition of specification of the contract.

It is to be expressly understood that the measured works is to be taken net (not standing any custom or practice to the tenderer) according to the drawing or as may be ordered from time to time by the Federation Engineer and the cost calculated by measurement or weight.

#### ADDITIONAL CONDITION FOR ROOFING WORK

# Providing, fabricating and erecting MS structural steel work for trusses, purlins, girders, columns, rafters, runners, struts, wind ties, bracings, sag rods, etc.

All structural steel materials such as angles, RS joists, flats, tees, plates, channels, etc. shall conform to the latest edition of IS 226. All structural steel shall be free from twists/bents before fabrication and such lengths should be discarded. Cutting of members shall be done by shearing, cropping, sawing or gas cutting. Contact surfaces of plates and butt joints shall be accurately machined over the whole area so that the parts connected shall butt over the entire surface of contact. Welding of pieces shall be done with the approval of the Engineer.

The components parts shall be assembled in such a manner that they are not damaged in any way and specific cambers as shown in the drawing or as directed by the engineer, shall be provided.

For bolted connection, where ever necessary washers shall be tapered or otherwise suitably shaped to give satisfactory bearing. The threaded portion of the bolt shall project beyond the nut by at least 1.5 threads.

Welding shall be done in accordance with the latest edition of IS 813 and 814, Code of Practice for use of Electric Arc welding for general construction in mild steel. In welding it must be ensured that the base metal is in fused state when filled metal makes contact with it, filler metal does not overflow upon and unused base metal, base metal is not cut along the weld edges, flowing metal floats the slag, oxide and gas bubbles at the surface behind advance pole.

For this purpose current shall be adjusted or the electrode size is changed. Welding shall be free from cracks, discontinuity, under or over size welding thickness.

Surface to be welded shall be free from loose mill scale, rut, grease, paint and any other foreign material. As far as possible avoid the welding at heights and at difficult positions. Generally fillet welding is preferred. The parts to be welded are brought in as close contact as practicable and rigidly clamped together.

Before erection steel work shall be thoroughly cleaned of rust, loose scale, dust, welding slag and shall be given one coat of red oxide primer of approved make and one coat of first quality synthetic enamel paint of approved make as specified in the item before erection and final coat of painting after the erection as directed.

Steel members shall be hoisted and put in position carefully without any damage to the member and to the building and labour. The trusses shall be lifted at such points that they do not buckle or deform or be unduly stressed. The end of the truss which faces the prevailing wind shall be fixed and the other end may be kept free to move. The steel work shall be securely fastened wherever necessary, temporarily braced, to provide for all loads to be carried by the member during erection including the load due to the erection equipment and its operation. No permanent bolting or welding is done until proper alignment has been obtained. The holes for the rivets shall be determined with the help of templates and drilled. Erection clearance of the cleared ends shall not be more than 1.5mm and without clearing end clearance shall not be more than 3mm. Grouting or embedding of structural steel members done after the approval of the alignment, level and position of the members by the engineer. In case, bolts receiving the base plate of the truss is not grouted using template and pockets left, in such case the bolts shall be grouted with non shrink ready mix grout.

#### Important points:

Before the actual execution of the job, the contractor shall prepare fabrication drawings for all structural steel work from the structural drawings supplied to him and determine the exact cutting lengths of the members, sizes of gusset plates, welding lengths by marking out on a level platform to full scale.

Welding plant, electrodes and other equipment, scaffolding, labour shall be arranged by the contractor at his cost. Erection equipment of required capacity, sufficient number of spare parts and staff should be maintained by the contractor at site at his cost. **Mode of Measurement**: All structural steel members shall be measured in length, area of MS plates shall be measured in Sq.m and converted into weights as per IS tables for steel and paid for in Kg. All rivets, bolts shall be measured in Kg and paid for in same rate as structural steel. No deduction shall be made for rivet holes and bolts. Nothing extra shall be paid for wastages and rolling margin in case of over weight. However in case of underweight actual shall be paid for.

# Providing, fabricating and erecting MS structural steel work for trusses, purlins, girders, columns, rafters, struts, wind ties, bracings, etc. with MS B class pipes/ Tubular section

The general specifications are same as given in item 8.01 but with MS B class pipes, medium duty square or rectangular sections of approved make as per item description given in the schedule of quantities. Part of work involving standard rolled sections shall be measured .

**Mode of Measurement**: All structural steel members shall be measured in length, area of MS plates shall be measured in Sq.m and converted into weights as per IS tables for steel and paid for in Kg. All rivets, bolts shall be measured in Kg and paid for in same rate as structural steel. No deduction shall be made for rivet holes and bolts. Nothing extra shall be paid for wastages and rolling margin in case of over weight. However in case of underweight actual shall be paid for.

PART – B

COMMERCIAL BID

SHOULD BE SEPARATED



# **TCMPF LIMITED** "AAVIN ILLAM" 3A - Muthuramalinganar Road, NANDANAM: CHENNAI - 35.

TWO PART TENDER

PART - B



# CONSTRUCTION OF 10 TLPD ICE CREAM PLANT BUILDING AT TRICHY

THE TAMILNADU COOPERATIVE MILK PRODUCERS' FEDERATION LIMITED, AAVIN ILLAM, 3A - MUTHURAMALINGANAR ROAD, NANDANAM, CHENNAI – 600 035.



# TCMPF LIMITED "AAVIN ILLAM" NANDANAM: CHENNAI - 35.

TWO PART TENDER

PART - B



# CONSTRUCTION OF 10 TLPD ICE CREAM PLANT BUILDING AT TRICHY

INDEX OF CONTENTS

| S. No. | Details                          |
|--------|----------------------------------|
| 1.     | ISSUE LETTER FOR TENDER DOCUMENT |
| 2.     | QUALIFICATION                    |
| 3.     | PRICE SCHEDULE                   |

#### **ISSUE LETTER FOR TENDER DOCUMENT**

# <u>PART-B,</u>

#### COMMERCIAL BID

This Two Part tender document set containing of Part – B Commercial bid.

Issued to:

For and on behalf of

The Tamilnadu Coop Milk Producers' Federation Limited, 'Aavin Illam', 3A - Muthuramalinganar Road, Nandanam Chennai - 35.

ISSUED BY;

Deputy General Manager (Civil), T C M P F Limited Aavin Illam,Nandanam CHENNAI – 600 035

#### QUALIFICATION:

The Part-B commercial offers of such of those tenderer who qualify themselves for being considered for the work of **"Construction of 10 TLPD ICE CREAM PLANT BUILDING AT TRICHY "** by fulfilling the entire terms and conditions as laid in Part - B "Commercial Bid" of this tender, will be considered for opening of Part-B commercial bid.

Other commercial offers not qualifying as above will be rejected outright.

#### Goods and Service Tax:

The tenderer should furnish a self attested copy of the GST registration certificate along with Tender document.

The contractor shall claim GST only in case of a registered supplier and should raise tax invoice, without fail.

All duties, taxes and other levies payable by the contractor under the contract, or for any other cause, as applicable on the date of submission of Bid, shall be included in the rates and prices and the total bid price submitted by the bidder.

## **PRICE SCHEDULE**

# CONSTRUCTION OF 10 TLPD ICE CREAM PLANT BUILDING AT TRICHY

| S.<br>No. | Quant   | ity            | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Rate in figures and<br>in words | Unit                  | Amount in<br>Rs. |  |  |  |  |
|-----------|---------|----------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-----------------------|------------------|--|--|--|--|
| 1         |         |                | Earth work excavation for foundation<br>in all soils and sub-soils and to full<br>depth as may be directed except in<br>rock requiring blasting inclusive of<br>back filling ,shoring shuttering, bailing<br>out water wherever necessary and<br>depositing the surplus earth within the<br>compound in places shown by the<br>departmental officers with an initial<br>lead of 10 mts and initial lift of 2 mts.<br>and clearing and levelling the site,<br>etc., complete complying with<br>standard specification. |                                 |                       |                  |  |  |  |  |
| a         | 3406.00 | m <sup>3</sup> | 0 to 2m Depth                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                 | One<br>Cubic<br>meter |                  |  |  |  |  |
| 2         | 25.00   | m <sup>3</sup> | Refilling with excavated earth other<br>than sand with an initial head load of<br>100 mts. and depositing the earth as<br>shown by the departmental officers<br>in layers of not more than 15 cm thick<br>well rammed, watered and<br>consolidated etc. complete<br>complying with standard specification                                                                                                                                                                                                             |                                 | One<br>Cubic<br>meter |                  |  |  |  |  |
| 3         | 540.00  | m <sup>3</sup> | Supplying and filling in foundation and<br>basement with filling Crushed stone<br>sand in layers of not more than 15 cm<br>thick well rammed watered and<br>consolidated complying with std spec.                                                                                                                                                                                                                                                                                                                     |                                 | One<br>Cubic<br>meter |                  |  |  |  |  |
| 4         | 2925.00 | m <sup>3</sup> | Supplying and filling conveyed gravel<br>other than sand with an initial head<br>load of 100 mts. and depositing the<br>earth as shown by the departmental<br>officers in layers of not more than 15<br>cm thick well rammed, watered and<br>consolidated etc. complete<br>complying with standard specification                                                                                                                                                                                                      |                                 | One<br>Cubic<br>meter |                  |  |  |  |  |

| S.<br>No. | Quant  | ity            | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Rate in figures and<br>in words | Unit                  | Amount in<br>Rs. |
|-----------|--------|----------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-----------------------|------------------|
| 5         | 138.00 | m <sup>3</sup> | Providing, laying, spreading and<br>compacting stone aggregate of<br>specified sizes to WBM 100 mm thick in<br>2 layers specifications in uniform,<br>hand picking, rolling with 3 wheeled<br>road/ vibratory roller 8-10 tonne<br>capacity in stages to proper grade<br>and camber, applying and brooming<br>requisite type of screening / binding<br>material to fill up interstices of coarse<br>aggregate, watering and compacting<br>to the required density. |                                 | One<br>Cubic<br>meter |                  |
| 6         | 675.00 | m <sup>3</sup> | Cement Concrete 1:5:10 (One<br>Cement, Five Crushed stone sand and<br>Ten hard broken stone jelly) using 40<br>mm gauge hard broken granite stone<br>jelly for foundation including<br>dewatering wherever necessary and<br>laid in layers of not more than 15 cm<br>thick well rammed, consolidated and<br>curing etc. complete (The crushed<br>stone sand to be used on concrete<br>work shall confirm to gradation as per<br>IS 383-1970)                       |                                 | One<br>Cubic<br>meter |                  |
| 7         | 95.00  | m <sup>3</sup> | Cement Concrete 1:4:8 (One Cement,<br>Four Crushed stone sand and Eight<br>hard broken stone jelly) using 40 mm<br>gauge hard broken granite stone jelly<br>for foundation including dewatering<br>wherever necessary and laid in layers<br>of not more than 15 cm thick well<br>rammed, consolidated and curing<br>etc. complete (The crushed stone<br>sand to be used on concrete work<br>shall confirm to gradation as per IS<br>383-1970)                      |                                 | One<br>Cubic<br>meter |                  |
| 8         |        |                | Brick work in following Cement Mortar<br>using best quality II class table<br>moulded chamber burnt bricks of size<br>9" x 4-1/2" x 3" for foundation and<br>basement including curing, etc.,<br>complete complying with standard<br>specifiction. In Cement Mortar 1:5                                                                                                                                                                                            |                                 |                       |                  |
| a         | 285.00 | m <sup>3</sup> | For Foundation and Basement.                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                 | One<br>Cubic<br>meter |                  |

No of Corrections:

| S.<br>No. |         |                | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|---------|----------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------------------------|------------------|
| b         | 875.00  | m <sup>3</sup> | For Superstructure in 0.0m to 4.50m                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                                 | One<br>Cubic<br>meter  |                  |
| C         | 304.00  | m <sup>3</sup> | For Superstructure in 4.50m to 9.0m                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                                 | One<br>Cubic<br>meter  |                  |
| d         | 11.00   | m <sup>3</sup> | For Superstructure upto 10.80m Height                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                 | One<br>Cubic<br>meter  |                  |
| 9         |         |                | Supplying and erecting steel centering<br>including necessary supports for plane<br>surfaces for Reinforced Cement<br>Concrete works such as column<br>footings, column pedestals, plinth<br>beams, grade beams, staircase steps,<br>etc. which require only nominal<br>strutting using mild steel sheets of size<br>90cm x 60cm and 10 BG stiffened with<br>welded mild steel angles of size 25mm<br>x 25mm x 3 mm for boarding, laid over<br>silver oak joists of size 10cm x 6.5cm<br>spaced at about 75cm centre to<br>centre or at suitable intervals etc.<br>complete. |                                 |                        |                  |
| i         |         |                | below basement                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                                 |                        |                  |
| a         | 2880.00 | m <sup>2</sup> | plain surface                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                 | One<br>Square<br>meter |                  |
| b         | 905.00  | m <sup>2</sup> | vertical surface                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                 | One<br>Square<br>meter |                  |

No of Corrections:

| S.<br>No. | Quant  | ity            | Description                                | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|--------|----------------|--------------------------------------------|---------------------------------|------------------------|------------------|
| ii        |        |                | above basement - for 0 to 3.30 m<br>height |                                 |                        |                  |
| a         | 905.00 | m <sup>2</sup> | plain surface                              |                                 | One<br>Square<br>meter |                  |
| b         | 750.00 | m <sup>2</sup> | vertical surface                           |                                 | One<br>Square<br>meter |                  |
| iii       |        |                | for 3.30 m to 4.30 m height                |                                 |                        |                  |
| a         | 881.00 | m <sup>2</sup> | plain surface                              |                                 | One<br>Square<br>meter |                  |
| b         | 260.00 | m <sup>2</sup> | vertical surface                           |                                 | One<br>Square<br>meter |                  |
| iv        |        |                | for 4.30 m to 5.30 m height                |                                 |                        |                  |
| a         | 50.00  | m <sup>2</sup> | plain surface                              |                                 | One<br>Square<br>meter |                  |
| b         | 195.00 | m <sup>2</sup> | vertical surface                           |                                 | One<br>Square<br>meter |                  |

Signature of the Tenderer

No of Corrections:

| S.<br>No. | Quant   | ity            | Description                 | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|---------|----------------|-----------------------------|---------------------------------|------------------------|------------------|
| V         |         |                | for 5.30 m to 6.30 m height |                                 |                        |                  |
| a         | 5345.00 | m <sup>2</sup> | plain surface               |                                 | One<br>Square<br>meter |                  |
| b         | 80.00   | m <sup>2</sup> | vertical surface            |                                 | One<br>Square<br>meter |                  |
| vi        |         |                | for 6.30 m to 7.30 m height |                                 |                        |                  |
| a         | 585.00  | m <sup>2</sup> | plain surface               |                                 | One<br>Square<br>meter |                  |
| b         | 45.00   | m <sup>2</sup> | vertical surface            |                                 | One<br>Square<br>meter |                  |
| vii       |         |                | for 7.30 m to 8.30 m height |                                 |                        |                  |
| a         | 110.00  | m <sup>2</sup> | Column surface              |                                 | One<br>Square<br>meter |                  |
| viii      |         |                | for 8.30 m to 9.30 m height |                                 |                        |                  |
| a         | 17.00   | m <sup>2</sup> | Column surface              |                                 | One<br>Square<br>meter |                  |

No of Corrections:

| S.<br>No. | Quantity |                | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|----------|----------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------------------------|------------------|
| ix        |          |                | for 9.30 m to 10.30 m height                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                 |                        |                  |
| а         | 17.00    | m <sup>2</sup> | Column surface                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                 | One<br>Square<br>meter |                  |
| ×         |          |                | For 10.30 m to 11.30 m height                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                                 |                        |                  |
| a         | 62.00    | m <sup>2</sup> | Plain surface                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                                 | One<br>Square<br>meter |                  |
| b         | 9.00     | m <sup>2</sup> | Column surface                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                 | One<br>Square<br>meter |                  |
| С         | 48.00    | m <sup>2</sup> | Wall surface                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                 | One<br>Square<br>meter |                  |
| 10        |          |                | Cement Concrete 1:2:4 (One Cement,<br>Two sand and Four hard broken stone<br>jelly) using 20 mm gauge hard broken<br>granite stone jelly for all RCC items of<br>works excluding cost of reinforcement<br>grill and fabricating charges,<br>centering and shuttering but including<br>laying, vibrating with mechanical<br>vibrators, finishing, curing, etc. and<br>providing fixtures like fan clamps in the<br>RCC floor / roof slabs wherever<br>necessary and bearing surfaces of<br>walls, beams etc. shall be finished<br>smooth with Cement Mortar 1:3 (One<br>Cement and Three M Sand) and kraft<br>paper laid over it without claiming<br>extra, etc., complete complying with<br>standard specification and as<br>directed by the departmental officers |                                 |                        |                  |

Signature of the Tenderer

| S.<br>No. | Quantity  |                | Description                                                                                                                                                                                                                                                                                                                                                                                                          | Rate in figures and<br>in words | Unit                  | Amount in<br>Rs. |
|-----------|-----------|----------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-----------------------|------------------|
| a         | 8.00      | m <sup>3</sup> | For Superstructure in First floor -<br>Parapet column                                                                                                                                                                                                                                                                                                                                                                |                                 | One<br>Cubic<br>meter |                  |
| 11        | 309697.00 | Kg             | Supplying, fabricating and placing in<br>position Mild Steel / Ribbed Tor Steel<br>grills for all RCC works as per design<br>given including cost of steel and G.I.<br>binding wire in all floors etc. complete<br>complying with standard specification                                                                                                                                                             |                                 | One<br>Kilo<br>gram   |                  |
| 12        |           |                | Brick partition walls of 11.50cm<br>thickness using best quality II class<br>table moulded chamber burnt bricks<br>of size 9" x 4-1/2" x 3" in Cement Mortar<br>1:3 (One Cement and Three M Sand)<br>using hoop iron reinforcement if found<br>necessary including curing etc.<br>complete and as directed by the<br>departmental officers. (Hoop iron<br>reinforcement will be measured and<br>paid for separately) |                                 |                       |                  |
| a         | 4.00      | m <sup>3</sup> | In Ground Floor                                                                                                                                                                                                                                                                                                                                                                                                      |                                 | One<br>Cubic<br>meter |                  |
|           |           |                | ICE CREAM PLANT                                                                                                                                                                                                                                                                                                                                                                                                      |                                 |                       |                  |
| 13        | 2281.00   | Kg             | Supplying and fixing mild steel grills for<br>windows, ventilators, etc., including<br>priming coat etc., complete.                                                                                                                                                                                                                                                                                                  |                                 | One<br>Kilo<br>gram   |                  |

No of Corrections:

| S.<br>No. | Quantity |    | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|----------|----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------------------------|------------------|
| 14        | 92.00    | m² | Fabricating Supplying and fixing in<br>position Aluminium anodised Natural<br>color matt finish door of size<br>1.00mx2.10m with 12mm thick<br>bothside prelaminated particle board<br>at bottom w& 2/3 glazed using<br>5.50mm thick Plain glass at top with<br>aluminium grill 10mm thick double<br>leaves door. The outer frame shall be<br>with aluminium box section<br>101.60x44.45x3.18m at 2.319kg/m and<br>Shutter frame made of section with<br>Vertical & Top rail:<br>50x44.45x2.50mm@1.292 kg/m, Bottom<br>rail: 100x44.45x2.50mm@ 1.974<br>kg/m,Lock rail : 50x44.45x2.5mm @<br>1.292 kg/m,Alu. Clips:<br>17.15x17.27x1.50mm @ 0.176 kg/m,Alu.<br>Handle: 100x30mm @ 0.988 kg/m and<br>Fixed ventilator Inner frame of section<br>@ 63.50x38x3mm @ 1.72kg/m and<br>necessary accessories such as rubber<br>beading PVC felt, handle for a length<br>of shutter (both sides), locking<br>arrangements, furniture fittings such as<br>aluminium tower bolts-250x12mm -<br>2Nos, aluminium tower bolt 200x12mm<br>- 1No, aluminium door stopper with<br>rubber bush - 2Nos ., lock-<br>1No.,Hydraulic Door closer as per BIS<br>standards including cost of all<br>materials, labour charges and power<br>consumption charges required for<br>fabrication including chipping<br>dismantling and making holes to the<br>required extent in RCC in<br>column/beam/masonry with power<br>drill wherever neccessary and redoing<br>the damaged portion to the original<br>condition after fixing etc. complete<br>All Aluminium section shall be used in<br>electrically controlled condition in<br>accordance with IS 1868/1962 for an<br>average anodic film thickness of 15<br>microns etc., complete.<br>. a) Single leaf |                                 | One<br>Square<br>meter |                  |

| S.<br>No. | Quantity |                | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|----------|----------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------------------------|------------------|
| 15        | 79.00    | m <sup>2</sup> | Fabricting Supplying and fixing in<br>position Aluminium anodised Natural<br>color matt finish door of size 2.00 m x<br>2.10m and 1.50m x 2.10m having fixed<br>ventilator at top of size 1.50x0.30m with<br>1/3 panelled with 12mm thick bothside<br>prelaminated particle board at<br>bottom w& 2/3 glazed using 5.50mm<br>thick Plain glass at top with<br>aluminium grill 10mm thick double<br>leaves door. The outer frame shall be<br>with aluminium box section<br>101.60x44.45x3.18m at 2.319kg/m and<br>Shutter frame made of section with<br>Vertical & Top rail:<br>50x44.45x2.50mm@1.292 kg/m, Bottom<br>rail: 100x44.45x2.50mm@ 1.974<br>kg/m,Lock rail : 50x44.45x2.5mm @<br>1.292 kg/m,Alu. Clips:<br>17.15x17.27x1.50mm @ 0.176 kg/m,Alu.<br>Handle: 100x30mm @ 0.988 kg/m and<br>Fixed ventilator Inner frame of section<br>@ 63.50x38x3mm @ 1.72kg/m and<br>necessary accessories such as rubber<br>beading PVC felt, handle for a length<br>of shutter (both sides), locking<br>arrangements, furniture fittings such as<br>aluminium tower bolts-250x12mm -<br>2Nos, aluminium door stopper with<br>rubber bush - 2Nos ., lock-<br>1No., Aluminium door stopper with<br>rubber bush - 2Nos ., lock-<br>1No.,Hydraulic Door closer as per BIS<br>standards including cost of all<br>materials, labour charges and power<br>consumption charges required for<br>fabrication including cost of all<br>materials, labour charges and power<br>consumption charges required for<br>fabrication including cost of all<br>materials, labour charges and power<br>consumption charges required for<br>fabrication including cost of all<br>materials, labour charges and power<br>consumption charges required for<br>fabrication including cost of all<br>materials, labour charges and power<br>consumption charges required for<br>fabrication including condition in<br>accordance with IS 1868/1962 for an<br>average anodic film thickness of 15<br>microns etc., complete Double<br>leaves |                                 | One<br>Square<br>meter |                  |

| S.<br>No. | Quant  | ity            | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|--------|----------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------------------------|------------------|
| 16        | 234.00 | m <sup>2</sup> | Supplying , fabricating and fixing in position Aluminium powder coated brown shade finish Four track sliding window in all floors with Aluminium sections of outer frame Bottom Track 92.34x46.00x1.50@1.637 kg/m,Top & vertical 92.34x29.70x1.50 at 1.066 kg/m,and Shutter Vertical 39x20x1.50 at 0.493 kg/m, Top & Bottom 18x36.6x1.50at0.439 kg/m, Vertical locking arrangement 28.94x39x1.50at0.632 kg/m with necessary accessories such as rubber beadings, special hinges, lock, handle including supplying and fixing 4mm thick plain glass including cost of all materials , labours, power consumption required for fabrication , drilling holes in RCC colunm, slab, masonry walls wherever necessary with power drills to the required extent and make good to the original condition after fixing and also as directed.The aluminium sections are to be anodised with matt finish under electrically controlled in accordance with IS 1868 / 1962 for an average anodic film thickness 15 microns etc., complete. |                                 | One<br>Square<br>meter |                  |
| 17        | 13.00  | m <sup>2</sup> | Providing and fixing in position<br>interlocking rolling shutters of<br>approved make of 18 gauge, 75 mm<br>wide cold rolled, MS Lathe interlocked<br>through entire length and jointed<br>together at the end by end locks<br>mounted on specially designed pipe<br>shaft with bracket including top<br>cover, spring, axles, guide rails, tees,<br>iron pulleys, bearings, handles,<br>arrangements for inside and outside<br>locking, holding-down bolts / MS lugs<br>embedded in CC 1:2:4 including 2 or<br>more coats of first quality synthetic<br>enamel paint of approved make, over<br>a coat of primer etc. complete as<br>directed. (Measurements to be<br>considered for payment shall be the<br>clear size of opening plus guide<br>channels on both sides for width and<br>450mm on top for drum height) for<br>providing and fixing in position<br>interlocking rolling shutter partly grilled<br>and mechanically operated with                                                                               |                                 | One<br>Square<br>meter |                  |

Signature of the Tenderer

No of Corrections:

| S.<br>No. | Quant   | ity            | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|---------|----------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
|           |         |                | mechanical device chain and crank<br>operated with pair of handles etc<br>complete as directed                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                 |                         |                  |
| 18        | 65.00   | Rm             | Manufacturing, Supplying and Fixing of<br>Stainless Steel Hand rails for staircase<br>near wet riser using 50mm dia 304L<br>Grade Stainless Steel pipe of 1.60mm<br>thick will be provided with tubular<br>supports made of 304L Grade Stainless<br>Steel pipe of 25mm dia of 1.60mm<br>thick welded to the railing. The<br>supports will be grouted into the wall<br>and provided with 93.00mm thick<br>Stainless Steel circular base plate of<br>304 Grade. The rate shall included for<br>grouting into concrete with necessary<br>supporting arrangements the hand rail<br>in floor polishing buffing, bonding,<br>cutting, grinding, conveyance,<br>welding charges, electrical charges,<br>etc. complete |                                 | One<br>Running<br>meter |                  |
| 19        | 6150.00 | m <sup>2</sup> | Plastering with Cement Mortar 1:5<br>(One cement and M sand), 12mm<br>thick in all floors including curing etc.<br>complete complying with standard<br>specification and as directed by the<br>Engineer-incharge.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                                 | One<br>Square<br>meter  |                  |
| 20        | 5580.00 | m <sup>2</sup> | Special ceiling plastering and finishing<br>the exposed surface of all RCC items<br>of work such as slabs, beams,<br>sunshades, facia, canopy slab,<br>staircase waist slab, landing slab etc.,<br>with Cement Mortar 1:3 (One Cement<br>and Three M Sand) 10mm thick<br>including hacking the surfaces,<br>providing cement mortar nosing,<br>beading for sunshades, staircases,<br>steps, landing slabs and curing, etc., in<br>all floors complying with standard<br>specification and as directed by the<br>Engineer-in charge.                                                                                                                                                                            |                                 | One<br>Square<br>meter  |                  |
| 21        | 1700.00 | m <sup>2</sup> | Plastering with Cement Mortar 1:5<br>(One cement and M sand), 20 mm<br>thick in all floors including curing etc.<br>complete complying with standard<br>specification and as directed by the<br>Engineer-incharge.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                 | One<br>Square<br>meter  |                  |

No of Corrections:

| S.<br>No. | Quant   | ity            | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|---------|----------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
| 22        | 9004.00 | m <sup>2</sup> | Painting two coats of newly plastered<br>wall surface with ready mixed plastic<br>emulsion paint of first class quality and<br>of approved colour over a priming<br>coat including thorough scrapping,<br>clean removal of dirt, and including<br>necessary plaster of paris putty,<br>wherever required etc., complete<br>complying with standard specification.                                                                                                                                                                                                                                                                                                                                                                       |                                 | One<br>Square<br>meter  |                  |
| 23        | 1700.00 | m <sup>2</sup> | Painting two coats of newly plastered<br>wall surface with Weather Proof<br>Exterior emulsion paint of first class<br>quality and of approved colour over a<br>priming coat including thorough<br>scrapping, clean removal of dirt, and<br>including necessary plaster of paris<br>putty, wherever required etc.,<br>complete complying with standard<br>specification.                                                                                                                                                                                                                                                                                                                                                                 |                                 | One<br>Square<br>meter  |                  |
| 24        | 393.00  | m <sup>2</sup> | Painting new wood work with two<br>finishing coats of synthetic enamel<br>ready mixed paint of approved quality<br>and colour over one coat priming<br>coat in all floors including the cost of<br>primer etc., complete complying with<br>standard specification. (The make,<br>quality and colour of paint should be<br>got approved by the Executive<br>Engineer before use on works.)                                                                                                                                                                                                                                                                                                                                               |                                 | One<br>Square<br>meter  |                  |
| 25        |         |                | Supplying and fixing in position best<br>approved of BIS quality PVC rain water<br>down fall pipes having a pressure of 6<br>kg. / sq.cm including cost of necessry<br>PVC shoe, PVC bend, cast iron<br>gratings of required diameter and<br>special clamps, brass screws, nails,<br>etc., and fixing of cast iron gratings at<br>junction of parapet and the RCC roof<br>slab including finishing neatly etc.,<br>complete. The rate shall be inclusive of<br>cast of removable cast iron grating.<br>The PVC pipe shall be fixed in wall with<br>special type of "U" clamp at the centre<br>of the pipe line in addition to those for<br>more than 3.0 metre pipe length, etc.,<br>complete complying with standard<br>specification. |                                 |                         |                  |
| a         | 140.00  | Rm             | 160mm dia PVC Rain water Pipe                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                 | One<br>Running<br>meter |                  |

No of Corrections:

| S.<br>No. | Quant   | ity            | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|---------|----------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------------------------|------------------|
| 26        | 180.00  | m <sup>2</sup> | Supplying and fixing colour galvanum<br>sheet roof of 0.47mm thick in position<br>with all necessary accessories<br>complete complying with standard<br>specification and as directed by the<br>departmental officers.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                 | One<br>Square<br>meter |                  |
| 27        | 7800.00 | Кg             | Providing, fabricating and fixing in<br>position M.S. Structure made out of<br>M.S.rolled/hollow (rounds/rectangular/<br>square etc.) sections as per architect's<br>details including shearing /cutting,<br>riveting, welding, grinding to smooth<br>surface of all works, MS fixing holdfasts<br>/ anchor bolts to be grouted in<br>concrete 1:2:4, providing and fixing<br>nuts bots fasteners as required as per<br>architect's details, including painting<br>with two or more coats of first quality<br>synthetic enamel paint of approved<br>quality and make over a coat of<br>primer etc. complete as directed. (MS<br>standard section shall be measured<br>and paid under relevant Item. Nuts,<br>bolts, washers shall be deemed to<br>have been included in the unit rates<br>and nothing extra shall be paid for) |                                 | One<br>Kilo<br>gram    |                  |
| 28        | 4000.00 | m <sup>2</sup> | Providing Anti-termite treatment to soil<br>adjecent and under building<br>foundation, plinth periphery of the<br>building by application of chemicals<br>of IS 63613 part I to IV in stages to suit<br>the progress of work consist as per the<br>detailed specification as below.<br>Including breaking of termite mounds,<br>making holes with crow bar, closing<br>the holes after the treatment and<br>including cost of chemicals, labour<br>charges, transport and storing etc.,<br>complete and as directed by the<br>departmental officers.                                                                                                                                                                                                                                                                           |                                 | One<br>Square<br>meter |                  |
|           |         | -              | ICE CREAM PLANT                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                 |                        |                  |
| 29        | 9.00    | m <sup>2</sup> | Supplying and fixing pre polished Ruby<br>red or equivalent colour Granite slab<br>20 mm thick for Pantry and wash basin<br>counter with bullnose edges are set in<br>CM 1:3 10mm thick for base and<br>pointed with the same colour cement<br>etc complete. The rate inclusive of<br>labour charges for laying & pointing<br>curing etc. complete                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                 | One<br>Square<br>meter |                  |

| S.<br>No. | Quantity |                | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|----------|----------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------------------------|------------------|
| 30        | 75.00 r  | m <sup>2</sup> | Providing and laying polished machine<br>cut single piece green Kota stone of<br>uniform shade in required size as per<br>drawing 20 to 25 mm thick for treads,<br>risers, sides of staircase over 20 mm<br>thick cement mortar bed of CM 1:4 (1<br>part cement :4 part of coarse sand)<br>with thick cement slurry including<br>making 3 to 5 mm V shaped grooves if<br>required, curing machine / hand,<br>curing, grinding, polishing, wax<br>polishing etc complete as directed.                                                                                                                                                                                                                                                                                                                                                                   |                                 | One<br>Square<br>meter |                  |
| 31        | 270.00 r | m <sup>2</sup> | Providing the floor with 20 mm thick<br>Granite slabs of approved colour and<br>size in all floors over a base layer of<br>20 mm thick CM 1:3, the granite slab<br>be laid over the cement mortor by<br>applying white cement slurry in<br>between base mortor and granite<br>slab. The granite slabs are to be so<br>laid that there should not be any<br>gap inbetween the adjacent slabs<br>and the joints shall be in line with<br>another joint and uniform by using<br>cutting machine without any damage<br>to the sides of corners of the granite<br>slab. The entire area of the flooring so<br>laid shall be neatly pointed with<br>coloured cement of 1.80 kg/m2. The<br>granite slabs proposed for the work<br>shall be shown to the departmental<br>officers and got approved by them<br>before use in the work etc., complete.           |                                 | One<br>Square<br>meter |                  |
| 32        | 420.00 r | m <sup>2</sup> | Providing the floor with 50 mm thick<br>Unpolished Granite slabs of approved<br>colour and size in all floors over a base<br>layer of 20mm thick CM 1:3, the granite<br>slab be laid over the cement mortor by<br>applying white cement slurry in between<br>base mortor and granite slab. The<br>granite slabs are to be so laid that<br>there should not be any gap<br>inbetween the adjacent slabs and the<br>joints shall be in line with another joint<br>and uniform by using cutting machine<br>without any damage to the sides of<br>corners of the granite slab. The entire<br>area of the flooring so laid shall be<br>neatly pointed with coloured cement of<br>1.80 kg/m2. The granite slabs proposed<br>for the work shall be shown to the<br>departmental officers and got approved<br>by them before use in the work etc.,<br>complete. |                                 | One<br>Square<br>meter |                  |

Signature of the Tenderer

No of Corrections:

| S.<br>No. | Quant   | ity            | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|---------|----------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------------------------|------------------|
| 33        | 1363.00 | m <sup>2</sup> | Dadoing walls with following best<br>approved quality, white / colour<br>Glazed tiles of approved sizes set in<br>Cement Mortar 1:2 (One Cement and<br>Two M sand) 10mm thick and pointing<br>the joints with white cement mixed<br>with colouring pigments at the rate of<br>0.40 Kg. / sq.m. neatly in all floors,<br>curing, etc., complying with standard<br>specification and as directed by the<br>departmental officers.                                                                                                                                                                                                                                                                                                                                                                                                                        |                                 | One<br>Square<br>meter |                  |
| 34        | 637.00  | m <sup>2</sup> | Paving the floor with best quality<br>Virtified Tiles of size 600 x 600 x 8mm<br>of approved colour, shade and quality<br>laid in cement mortar 1:3 (one cement<br>and three M sand) 20mm thick in all<br>floors and the top pointed with the<br>white cement mixed same colour<br>pigments etc., complete complying<br>with standard specification. (The<br>make and brand of the tiles should be<br>got approved by Executive Engineer<br>before use on works)                                                                                                                                                                                                                                                                                                                                                                                       |                                 | One<br>Square<br>meter |                  |
| 35        | 2182.00 | m²             | Providing the floor with 30 mm thick<br>Unpolished Granite slabs of approved<br>colour and size in all floors over a<br>base layer of 20mm thick CM 1:3, the<br>granite slab be laid over the cement<br>mortor by applying white cement slurry<br>in between base mortor and granite<br>slab. The granite slabs are to be so<br>laid that there should not be any<br>gap inbetween the adjacent slabs<br>and the joints shall be in line with<br>another joint and uniform by using<br>cutting machine without any damage<br>to the sides of corners of the granite<br>slab. The entire area of the flooring so<br>laid shall be neatly pointed with<br>coloured cement of 1.80 kg/m2. The<br>granite slabs proposed for the work<br>shall be shown to the departmental<br>officers and got approved by them<br>before use in the work etc., complete. |                                 | One<br>Square<br>meter |                  |

| S.<br>No. | Quant   | ity            | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|---------|----------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
| 36        | 390.00  | Rm             | Providing expansion joint in RCC floor<br>slab for 12.5mm width using<br>polysulphide as sealent on the top and<br>bottom for a depth of 7.5mm each<br>and packing the inner space using<br>compressible non-absorbent filler<br>materials including cost of labour for<br>cutting and fixing filler materials and<br>laying polysulphide sealent with<br>necessary spatula etc., complete<br>complying with standard<br>specifications and as directed                                                                               |                                 | One<br>Running<br>meter |                  |
| 37        | 120.00  | m <sup>2</sup> | Providing expansion joint of 12.5mm<br>wide in between RCC twin columns<br>from top of pedastal to full height<br>including filling the inner space with<br>suitable non-absorbent, flexible and<br>well compressible filler materials of<br>approved quality and brand; finishing<br>the sides of RCC columns with<br>polysulphide sealents for a depth of<br>7.5mm on either side covering the<br>inner space filled with filler materials as<br>above etc., complete complying with<br>standard specifications and as<br>directed. |                                 | One<br>Square<br>meter  |                  |
| 38        | 800.00  | Кg             | Providing fabricating and installing in<br>position Stainless Steel 304 sheets for<br>cladding and anchored to corners of<br>columns L shape 50 x 50 size through<br>shaped custom fabricated etc as per<br>the drawings including all fixing<br>accessories, all cutting, bending,<br>welding, grinding, and all other<br>incidentals and approved buffing to<br>stainless steel members etc. complete<br>as directed.                                                                                                               |                                 | One<br>Kilo<br>gram     |                  |
| 39        | 3550.00 | m <sup>2</sup> | Indian patent stone flooring (I.P.S) in<br>cement concrete 10mm chips for<br>40mm tk and the top finish thick neatly<br>etc,completed                                                                                                                                                                                                                                                                                                                                                                                                 |                                 | One<br>Square<br>meter  |                  |
| 40        |         |                | Providing of placing RMC Cement<br>Content 360 Kg/Cum Reinforced<br>Cement concrete of the following<br>grades using OPC 53 grade cement,<br>machine crushed coarse agrregates<br>20 mm and 12.5 mm, M sand, Water                                                                                                                                                                                                                                                                                                                    |                                 |                         |                  |

Signature of the Tenderer

No of Corrections:

| S.<br>No. | Quant   | ity            | Description                                                                                                  | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|---------|----------------|--------------------------------------------------------------------------------------------------------------|---------------------------------|------------------------|------------------|
|           |         |                | and admixture etc complete all for<br>casting concrete elements of all<br>shape and size and at all heights. |                                 |                        |                  |
| a         | 1284.00 | m <sup>2</sup> | For Foundation and Basement.                                                                                 |                                 | One<br>Square<br>meter |                  |
| d         | 890.00  | m <sup>2</sup> | Above Basement 0.0m to 4.5m Height                                                                           |                                 | One<br>Square<br>meter |                  |
| С         | 895.00  | m <sup>2</sup> | Above 4.5m to 9.0m Height                                                                                    |                                 | One<br>Square<br>meter |                  |
| d         | 22.00   | m <sup>2</sup> | Above 9.0m Height                                                                                            |                                 | One<br>Square<br>meter |                  |

| S.<br>No. | Quantity              | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|-----------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------------------------|------------------|
| 41        | 150.00 m <sup>2</sup> | Surface Preparation:- Providing and<br>grinding all sharp edges to make it<br>flush with the surface, cleaning all<br>floor, walls areas to make it free from<br>debris, dirt, dust and other<br>contaminants, etc and complete as<br>per manufacturer's<br>specification.Construction joints<br>treatment - Providing and supplying E<br>135, SBR based admixture and<br>polymer bonding agent, for filling CM<br>1:4 (fine sand) admixed with E 135 at<br>dosage of 2.5 Ltr per 50 Kg bag of<br>cement, including cut opening the<br>joints in the form of "V" shape of<br>required size, cleaning the grooves,<br>applying neat coat of E 135, filling the<br>groove with mixed mortar and<br>finishing, curing, etc and complete as<br>per manufacturer's<br>specification.Horizontal bore packing -<br>Providing and supplying E 135, SBR<br>based admixture and polymer<br>bonding agent, for filling the gap<br>between the wall and pipe using CM<br>of required mix ratio admixed with E<br>135 at dosage of 2.5 Ltr per 50 Kg bag<br>of cement, over the neat coat of E<br>135, including cleaning, filling -<br>compacting in the horizontal bore<br>holes, finishing the mortar flush with the<br>surface, curing, etc and complete as<br>per manufacturer's<br>specification.Waterproofing<br>Membrane: Providing and applying<br>two coats of Ardex WPM 004, two<br>components, two components,<br>breathable, acrylic elastomeric<br>waterproofing coating in two coats<br>with dft 0.8 - 1.0 mm thick using<br>brush/roller leaving each coat to dry<br>completely, applying first coat of WPM<br>004, sandwiching WPM Deck Web at<br>all corners and pipe penetration on<br>the wet first coat of WPM 004,<br>applying second coat of WPM 004,<br>applying second coat of WPM 004,<br>applying second coat of WPM 004<br>and allowing it to dry, etc and<br>complete as per manufacturer's<br>specification. [The properties are:- Pot<br>life : 60 min; Appearance : Grey colour<br>fluid liquid; Mixed material density : 1-<br>65 - 1.7 Gms / CC; Bond strength : 0.90<br>N/Sqmm; Depth of water penetration : |                                 | One<br>Square<br>meter |                  |

No of Corrections:

| S.<br>No. | Quantity | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Rate in figures and<br>in words | Unit | Amount in<br>Rs. |
|-----------|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------|------------------|
|           |          | >21mm, crack bridging upto 1 mm,<br>flexible]. Screed for Floor - Providing<br>and supplying of E 135, SBR based<br>admixture and polymer bonding<br>agent, for installing screed with<br>required thickness using CM of<br>required mix ratio admixed with E 135<br>at dosage of 2.5 Ltr per 50 Kg bag of<br>cement, over the tacky bonding slurry<br>of E 135, water and cement mixed in<br>ratio of 1:1:3, including cleaning the<br>surface, installing level buttons,<br>applying the mixed mortar,<br>compacting, leveling, curing, etc and<br>complete as per manufacturer's<br>specification. Plastering - Providing<br>and supplying of E 135, SBR based<br>admixture and polymer bonding<br>agent, for installing plastering using<br>CM of required mix ratio admixed with<br>E 135 at dosage of 2.5 Ltr per 50 Kg<br>bag of cement, over the tacky<br>bonding slurry of E 135, water and<br>cement mixed in ratio of 1:1:3,<br>including cleaning the surface,<br>installing level buttons, applying the<br>mixed mortar, compacting, leveling,<br>curing, etc and complete as per<br>manufacturer's specification. |                                 |      |                  |
| 42        |          | Supply and installation of Restroom<br>cubicle system that includes<br>intermediate panel, pilaster & door<br>made of BWR .PLY and laminates of<br>single colour . The solid<br>BWR .PLYpact laminate is based on<br>thermosetting resins, homogeneously<br>reinforced with cellulose fibres and is<br>manufactured as per relevant quality<br>standards. Top surface on both sides is<br>melamine coated which is scratch &<br>impact resistant . Intermediate panel is<br>one continuous panel without any<br>joints , All intermediate panels , pilaster<br>& doors shall be 12mm thick with<br>edges chamfered. (Door width:<br>600mm)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                                 |      |                  |
|           |          | Accessories 304 Grade                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                 |      |                  |

| S.<br>No. | Quantity |                | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|----------|----------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------------------------|------------------|
|           |          |                | a) SS Coated Top Rail<br>b) 304 SS Hinges – Gravity to close<br>c) 304 SS Privacy Thumb turn c/w<br>Occupancy Indicator<br>d)304 SS Coat Hook<br>e) 304 SS Door Knob<br>f) 316 SS Adjustable Pedestal<br>g) 304 SS "U" channel<br>h)SS Coated Door Stopper channel<br>i) Rubber Door Stopper Lining<br>j) Screws & Wall Plugs                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                 |                        |                  |
|           | 40.00    | m <sup>2</sup> | Average Cubicles -1200 W X 2000mm<br>Ht                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                                 | One<br>Square<br>meter |                  |
| 43        | 1038.00  | m <sup>2</sup> | Providing and laying 125mm thick<br>Vacuum De-watered of M25 grade<br>concrete (Seprate design mix for VDF<br>flooring) with minimum cement<br>content of 360kg/cum, surface<br>vibrated and finished with machine for<br>flooring over prepared sub-base in<br>strips of width up to 3.5 M in line and<br>level maintaining required slope ,<br>compacting with needle / surface<br>vibrator, leveling with surface vibrator,<br>Vacuum De-watering with vacuum<br>pump, floating and further<br>compaction with skin floater equipped<br>with floating disc, providing and<br>spreading Rockite or equivalent floor<br>hardener @ 3.5 Kg/Sq.M, curing,<br>formation of joints @ 4 M c/c<br>(maximum) by cutting up to 25mm<br>thickness of concrete slab with<br>mechanized saw and filling the same<br>with semi-rigid epoxy based Rockite or<br>equivalent sealant including<br>preparation of base, curing finishing<br>etc. with required 12mm MS dia bar<br>on all edges 300mm on both pannel @<br>300mm c/c, curing etc complete as<br>per the drawing / as directed by<br>Engineer. |                                 | One<br>Square<br>meter |                  |

| S.<br>No. | Quantity |                | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|----------|----------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------------------------|------------------|
| 44        | 473.00   | m <sup>2</sup> | PU FLOORING - 10 MM : Surface<br>Preparation:- Providing and<br>roughening the smooth surface to<br>provide the mechanical key for<br>subsequent application, grinding all<br>sharp edges to make them flush with<br>the surface, making groove of 8mm X<br>8mm in size at approximately 100mm<br>away parallel from wall and adjacent<br>to doorways, covering not more than<br>20 Smtr, cleaning the all floor area to<br>make it free from all dirt, dust and<br>other contaminants, etc and<br>complete as per manufacturer's<br>specifications. Scratch Coat:-<br>Providing and installing R 90C P at<br>1mm thick as scratch coat using flat<br>trowel by mixing all 3 components and<br>colour pigment in mixing vessel using<br>heavy duty slow speed drilling<br>machine fixed with mixing paddle, etc<br>and complete as per manufacturer's<br>specification. Final Floor Finishing:-<br>Providing and installing R 90C P at<br>required 9mm thickness using flat<br>trowel, notch trowel and spike roller by<br>mixing all 3 components and colour<br>pigment in mixing vessel using heavy<br>duty slow speed drilling machine fixed<br>with mixing paddle, etc and complete<br>as per manufacturer's<br>specification.[The floor finish may<br>confirm to:-Full chemical cure : 7 days;<br>Bond strength : > 1.5 N/mm <sup>2</sup> ;<br>Compressive strength : 48 N/mm <sup>2</sup> ;<br>Flexural strength : 20 N/mm <sup>2</sup> ; Tensile<br>strength : 7 N/mm <sup>2</sup> ; Abrasion<br>resistance : Classified 'Special Duty'<br>under BS 8204:Part 2:2002(9); Slip<br>resistance : Classified 'Special Duty'<br>under BS 8204:Part 2:2002(9), wet and<br>dry; Impact resistance : Classified<br>'High Impact Resistance' under BS<br>8204: Part 1: 1999] |                                 | One<br>Square<br>meter |                  |

| S.<br>No. |        |     | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Rate in figures and<br>in words | Unit                   | Amount in<br>Rs. |
|-----------|--------|-----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------------------------|------------------|
| 45        | 371.00 | m²  | "Providing and applying Ardex<br>Endura "R 3 E"/ "R 2 CE", 2 component<br>solvent free epoxy primer, mixing 2<br>components by mechanical means,<br>applying mixed "R 3 E / R 2 CE" in one<br>or more coat using brush / roller,<br>allowing it to dry completely,<br>including, grinding the sharp edges,<br>preparing the surface up to required<br>roughness, cleaning, etc and<br>complete as per manufacturer's<br>specification. Providing and installing<br>3 mm thick epoxy flooring underlay<br>using Ardex Endura "R 24 CE", 3<br>component with outstanding wearing<br>properties self levelling epoxy screed,<br>mixing 3 components by mechanical<br>means, spreading and finishing the<br>mixed Ardex Endura R 24 CE over<br>completely dried one or more coats of<br>primer, etc and complete as per<br>manufacturer's specification. Providing<br>and installing 2 mm thick epoxy floor<br>toping using Ardex Endura "R 25 CE", 4<br>components high glossy self smoothing<br>chemical resistant epoxy resin floor<br>finish, mixing 4 components by<br>mechanical means, spreading and<br>finishing the mixed Ardex Endura R 25<br>CE over completely dried primer coat,<br>etc and complete as per<br>manufacturer's specification. |                                 | One<br>Square<br>meter |                  |
| 46        | 2.00   | Nos | Providing and fixing in position precast<br>R.C.C. manhole cover and<br>frame.Square shape 600mm internal<br>dimensions                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                                 | Each                   |                  |
| 47        | 10.00  | Nos | Providing and fixing PVC coated MS<br>rungs as per drawing and instruction of<br>Engineer in-charge complete.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                 | Each                   |                  |

| S.<br>No. | Quantity |     | Description                                                                                                                                                                                                                                                                                                                                             | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|----------|-----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
| 48        | 100.00   | Rm  | Providing, laying and making kerb<br>channel 30 cm wide and 50 mm thick<br>with cement concrete 1:3:6 (1<br>cement: 3 coarse sand:6 graded<br>stone aggregate 20 mm nominal size)<br>well rammed and consolidated and<br>grouted with fine sand, including<br>finishing the top smooth etc. complete<br>and as per direction of Engineer-in-<br>charge. |                                 | One<br>Running<br>meter |                  |
|           |          |     | SANITARY INSTALLATION & DRAINAGE WORKS                                                                                                                                                                                                                                                                                                                  |                                 |                         |                  |
| 49        | 2.00     | Nos | Supplying and fixing of Oval Shape<br>Hand Wash Basin of size 560 x 450mm<br>with all accessories such as 32mm dia<br>CP Waste Coupling, Rubber Plug and<br>Chain, 32mm dia 'B' Class GI Waste<br>Pipe, 15mm dia GM Wheel Valve,<br>15mm dia Nylon Connection, 15mm<br>dia Brass Nipples, 15mm CP Pillar Tap<br>etc                                     |                                 | Each                    |                  |
| 50        | 4.00     | Nos | Supplying and fixing Stainless Steel Sink<br>of size 600mm x 450mm x 200mm with<br>32mm dia 'B' Class GI Waste Water<br>Pipe and 32mm dia CP Waste<br>Coupling                                                                                                                                                                                          |                                 | Each                    |                  |
| 51        | 2.00     | Nos | Supplying and fixing of Granite Sink of<br>size 600 x 600 x 250mm with 32mm dia<br>'B' Class GI Waste Water Pipe and<br>32mm dia CP Waste Coupling                                                                                                                                                                                                      |                                 | Each                    |                  |
| 52        | 6.00     | Nos | Supplying and fixing SS Swan Neck Tap<br>for lab sink                                                                                                                                                                                                                                                                                                   |                                 | Each                    |                  |
| 53        | 5.00     | Nos | Providing and fixing liquid soap<br>dispenser of approved make fixed<br>with necessary fittings etc. complete<br>as directed.                                                                                                                                                                                                                           |                                 | Each                    |                  |

| S.<br>No. | Quant | ity | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Rate in figures and<br>in words | Unit | Amount in<br>Rs. |
|-----------|-------|-----|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------|------------------|
| 54        | 5.00  | No  | Supplying and fixing approved make<br>C.P. towel ring with necessary fixing<br>materials                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                 | Each |                  |
| 55        | 5.00  | Nos | Supplying and fixing approved make<br>C.P. towel rail 600mm long with<br>necessary fixing materials                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                                 | Each |                  |
| 56        |       |     | Supplying and fixing position CI Nahani<br>Trap / Floor Trap of the following sizes<br>with best stainless steel gratings of<br>approved brand and quality, fixed<br>over a bed of brick jelly lime concrete<br>1:2:5 (One part of lime, two part of<br>sand and five part of 40mm gauge<br>brick jelly) and finished with Cement<br>Mortar 1:3 (One Cement, Three sand)<br>including dismantling masonry works<br>wherever found necessary and<br>making good the dismantled portions<br>to the original condition and giving<br>connection to the CI / PVC pipes, etc.,<br>complete complying with standard<br>specification. (The Nahani Trap should<br>be got approved by the Executive<br>Engineer before use on works) |                                 |      |                  |
| a         | 10.00 | Nos | Nahani Trap of size 100 x 75mm with stainless steel gratings                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                 | Each |                  |
| 57        | 26.00 | Nos | Providing and fixing factory made<br>grade SS 304 deep seal ' P' trap / Amul<br>Trap 300x300mm in single piece<br>without side joints of self cleansing<br>design with or without vent arm with<br>provision for connecting inlet fitting<br>complete including cost of cutting<br>and making good the walls and floors<br>wherever required for 100mm inlet and<br>100mm outlet The trap shall be<br>connected to HDPE pipe etc<br>complete as directed.                                                                                                                                                                                                                                                                    |                                 | Each |                  |

No of Corrections:

| S.<br>No. | Quant  | ity | Description                                                                                                                       | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|--------|-----|-----------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
| 58        |        |     | Providing & Fixing HDPE pipe 4 kg<br>pressure 4984 PE 80 with welding, all<br>fitting such as bend, tee, reducer etc<br>complete. |                                 |                         |                  |
| а         | 30.00  | Rm  | HDPE pipe 110mm                                                                                                                   |                                 | One<br>Running<br>meter |                  |
| b         | 342.00 | Rm  | HDPE pipe 160mm                                                                                                                   |                                 | One<br>Running<br>meter |                  |
| С         | 50.00  | Rm  | HDPE pipe 200mm                                                                                                                   |                                 | One<br>Running<br>meter |                  |
| d         | 105.00 | Rm  | HDPE pipe 250mm                                                                                                                   |                                 | One<br>Running<br>meter |                  |
| e         | 120.00 | Rm  | HDPE pipe 315mm                                                                                                                   |                                 | One<br>Running<br>meter |                  |

| S.<br>No. | Quanti | ty  | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Rate in figures and<br>in words | Unit                | Amount in<br>Rs. |
|-----------|--------|-----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|---------------------|------------------|
| 59        | 300.00 | Kg  | Providing fabricating and installing at<br>all levels and in position (for dairy<br>effluent drainage) Stainless Steel (SS)<br>pipes Grade-304, 100mm to 200mm<br>dia and wall thickness from 2mm to<br>3mm including all types of necessary<br>fittings such as elbows, bends, reducer<br>bends, reducers, reducer tees, tees, TC<br>ends, SS flanges with nuts and bolts, SS<br>caps etc, piping work shall be carried<br>out in verticals and horizontals and<br>also fixed to stainless steel drain traps<br>including providing and fixing of<br>approved heavy duty SS 304 grade<br>pipe brackets (made from SS 304 flats<br>up to 50mm wide and up to 6mm<br>thick) and anchoring arrangement by<br>providing and fixing self-expansion<br>fasteners of 12mm dia X 100/120mm<br>long sized of approved make fixed<br>with RCC (concrete) elements, all<br>fixing accessories, all cutting, bending,<br>welding, grinding, drilling, tapping,<br>weep hole and all other incidentals,<br>and approved buffing to stainless steel<br>members, including all scaffolding and<br>staging etc. complete as directed. SS<br>Pipes and SS bracket supports actually<br>fixed in position as per the drawing<br>and as directed shall be measured<br>and paid in KG. Wastages shall not be<br>paid. (14kg/rm) |                                 | One<br>Kilo<br>gram |                  |
| 60        | 20.00  | Nos | Providing & Constructing 1.0 M x 1.0 M<br>(inside dimension) and 1.0 M to 1.5 M<br>depth Manholes. The rate includes<br>excavation, 150 mm thick BBCC 1:5:10<br>(1 part cement, 5 part coarse sand, 10<br>part of brick bat ) in foundation 230<br>mm thick brick masonry walls in CM<br>1:3(1 part cement, 3 part sand), 12<br>mm thick plastering in inside and top<br>300 on the external face of chamber<br>in CM 1:5(1 part cement, 5 part sand),<br>channels, IPS flooring, making drain<br>channel as per specification, CI/MS<br>rungs with paint, steps, CI cover 600<br>X600mm heavy duty, 150 mm thick<br>RCC 1:2:4(1 part cement, 2 part<br>coarse sand, 4 part of stone<br>aggregate) slabs with standard<br>reinforcement etc. complete as<br>directed                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                                 | Each                |                  |

| S.<br>No. | Quant | ity | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Rate in figures and<br>in words | Unit | Amount in<br>Rs. |
|-----------|-------|-----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------|------------------|
| 61        | 5.00  | Nos | Providing & Constructing 1.2 M x 1.2 M<br>(inside dimension) and 1.5 M to 2.0 M<br>depth Manholes. The rate includes<br>excavation, 150 mm thick BBCC 1:5:10<br>(1 part cement, 5 part coarse sand, 10<br>part of brick bat ) in foundation 230<br>mm thick brick masonry walls in CM<br>1:3(1 part cement, 3 part sand), 12<br>mm thick plastering in inside and top<br>300 on the external face of chamber<br>in CM 1:5(1 part cement, 5 part sand),<br>channels, IPS flooring, making drain<br>channel as per specification, CI/MS<br>rungs with paint, steps, CI cover 600<br>X600mm heavy duty, 150 mm thick<br>RCC 1:2:4(1 part cement, 2 part<br>coarse sand, 4 part of stone<br>aggregate) slabs with standard<br>reinforcement etc. complete as<br>directed                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                 | Each |                  |
| 62        | 4.00  | Nos | Providing and constructing Inspection<br>Chambers/ Manhole Chamber/ any<br>other<br>Chamber size 600 x600 mm x450mm to<br>1000mm deep including necessary<br>excavation in soil/murrum/rock as per<br>required invert level and working<br>space all around, 150mm thick bed of<br>cement concrete in proportion of CC<br>1:5:10 (1 part cement, 5 parts coarse<br>sand and 10 parts of stone<br>aggregates) with 150mm offsets at all<br>around the outer faces of walls,<br>providing and constructing of<br>minimum 230mm thick brick/cement<br>concrete block masonry walls in CM<br>1:4 (1part cement and 4 parts of<br>coarse sand), providing and applying<br>15mm thick water proof plaster in CM<br>1:3 (1 part cement and 3 parts of<br>coarse sand) added with integral<br>waterproofing compound as per<br>manufacturers specifications and<br>finished with a floating coat of neat<br>cement @ 2.2 Kg/SqM at the internal &<br>external faces all around the masonry<br>walls, necessary floor benching and<br>channels in cement concrete 1:1.5:3<br>(1 part cement, 1.5 part coarse sand,<br>3 parts of stone aggregates) of<br>minimum 150mm thick rendered<br>smooth with waterproof plaster<br>followed by neat cement, providing CI |                                 | Each |                  |

No of Corrections:

| S.<br>No. | Quantity |     | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|----------|-----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
|           |          |     | circular/square Manhole cover with<br>frame of minimum 600mmX600mm<br>weighing minimum 40 kg (double seal)<br>of approved make and confirming to<br>IS and fixing with reinforced cement<br>concrete 1:1.5:3 of minimum 150mm<br>thick slab including shuttering, finishing<br>the concrete surface and faces with<br>waterproof plaster/IPS in mild slopes<br>with float of neat cement etc<br>complete as directed.                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                 |                         |                  |
| 63        | 4.00     | Nos | Providing and fixing square mouth 'P'<br>type S.W gully trap grade 'A' of size<br>300x300mm complete with C.I grating,<br>brick masonry chamber and water<br>tight C.I cover with frame of 450 x 450<br>mm size. The weight of cover to be not<br>less than 4.50 Kg and and frame to be<br>not less than 4.70 Kg as per standard<br>design and detail.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                                 | Each                    |                  |
| 64        |          |     | Supplying and fixing in position best<br>quality UPVC soil / waste pipes of<br>various dia having 6 kg / sq.cm.<br>pressure BIS mark and providing leak<br>proof joints using UPVC adhesives<br>including fixing to the wall with special<br>UPVC / MS clamp, teak wood plugs,<br>brass screws, etc., and making<br>connection to all sanitary fittings,<br>dismantling masonry / RCC works<br>wherever found necessary and<br>making the good dismantled portion<br>to the original condition, including<br>testing for any leakages, etc.,<br>complete complying with standard<br>specifications. (The UPVC pipes<br>should be got approved by the<br>Executive Engineer before use on<br>works). The rate for earth work<br>excavation will be measured and paid<br>separately in the cases where the pipe<br>lines are proposed to laid below<br>ground level |                                 |                         |                  |
| а         | 10.00    | Rm  | 80mm dia                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                                 | One<br>Running<br>meter |                  |

| S.<br>No. | Quant | ity | Description                                                                                                                                                                                                                                                                                                                                                                                                                      | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|-------|-----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
| b         | 15.00 | Rm  | 100mm dia                                                                                                                                                                                                                                                                                                                                                                                                                        |                                 | One<br>Running<br>meter |                  |
| C         | 10.00 | Rm  | 150mm dia                                                                                                                                                                                                                                                                                                                                                                                                                        |                                 | One<br>Running<br>meter |                  |
| 65        |       |     | Providing and laying non-pressure<br>class NP2 RCC Hume pipes with collars<br>including excavation of trenches in<br>soil/murum/rock, laying the pipes as<br>per layout and drawing, filling the<br>joints with stiff mixture of cement<br>mortar (1 part cement :1part fine<br>sand) and jute, curing, testing the pipe<br>and refilling the trenches in layers with<br>due compaction & watering etc.<br>complete as directedl |                                 |                         |                  |
| a         | 15.00 | Rm  | 150mm dia                                                                                                                                                                                                                                                                                                                                                                                                                        |                                 | One<br>Running<br>meter |                  |
| b         | 30.00 | Rm  | 250mm dia                                                                                                                                                                                                                                                                                                                                                                                                                        |                                 | One<br>Running<br>meter |                  |
| C         | 25.00 | Rm  | 300mm dia                                                                                                                                                                                                                                                                                                                                                                                                                        |                                 | One<br>Running<br>meter |                  |

| S.<br>No. | Quantity |    | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|----------|----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
|           |          |    | WATER SUPPLY WORKS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                 |                         |                  |
| 66        |          |    | Supplying, laying and jointing CPVC<br>pipes (having working pressure 10 kg. /<br>sq.cm) of approved quality and best<br>variety conforming to BIS of the<br>following dia including cutting,<br>threading and fixing CPVC specials<br>using CPVC adhesives (but excluding<br>cost of such specials) and fixing into<br>wall with teak wood plugs, CPVC<br>clamps and screws making holes on<br>the wall (or) drilling holes in the roof<br>and making good the dismantled<br>portion to original condition with<br>necessary brick work / cement<br>concrete and plastering neatly<br>wherever necessary with necessary<br>scaffolding charges upto 4 metre<br>height above ground level, etc.,<br>complete complying with standard<br>specifications. The CPVC pipes shall<br>be got approved by Executive |                                 |                         |                  |
| a         | 30.00    | Rm | Engineer before use on works.<br>50mm dia CPVC Pipe Above Ground<br>level                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                 | One<br>Running<br>meter |                  |
| b         | 20.00    | Rm | 40mm dia CPVC Pipe Above Ground<br>level                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                 | One<br>Running<br>meter |                  |
| С         | 15.00    | Rm | 32mm dia CPVC Pipe Above Ground<br>level                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                 | One<br>Running<br>meter |                  |

| S.<br>No. | Quantity |    | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|----------|----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
| d         | 40.00    | Rm | 25mm dia CPVC Pipe Above Ground<br>level                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                                 | One<br>Running<br>meter |                  |
| e         | 40.00    | Rm | 20mm dia CPVC Pipe Above Ground<br>level                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                                 | One<br>Running<br>meter |                  |
| f         | 20.00    | Rm | 15mm dia CPVC Pipe Above Ground<br>level                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                                 | One<br>Running<br>meter |                  |
| 67        |          |    | Supplying, laying and jointing CPVC<br>pipes (having working pressure 10 kg. /<br>sq.cm) of approved quality and best<br>variety conforming to BIS of the<br>following dia including cutting,<br>threading and fixing CPVC specials<br>using CPVC adhesives (but excluding<br>cost of such specials) and fixing into<br>wall with teak wood plugs, CPVC<br>clamps and screws making holes on<br>the wall (or) drilling holes in the roof<br>and making good the dismantled<br>portion to original condition with<br>necessary brick work / cement<br>concrete and plastering neatly<br>wherever necessary with necessary<br>scaffolding charges upto 4 metre<br>height above ground level, etc.,<br>complete complying with standard<br>specifications. The CPVC pipes shall<br>be got approved by Executive<br>Engineer before use on works. |                                 |                         |                  |
| a         | 90.00    | Rm | 65mm dia upvc pipe                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                                 | One<br>Running<br>meter |                  |

No of Corrections:

| S.<br>No. | Quan | lity | Description                                                                                       | Rate in figures and<br>in words | Unit | Amount in<br>Rs. |
|-----------|------|------|---------------------------------------------------------------------------------------------------|---------------------------------|------|------------------|
| 68        |      |      | Providing and fixing gun metal gate<br>valve with C.I. wheel of approved<br>quality (screwed end) |                                 |      |                  |
| a         | 2.00 | Nos  | 65mm dia                                                                                          |                                 | Each |                  |
| b         | 3.00 | Nos  | 50mm dia                                                                                          |                                 | Each |                  |
| С         | 2.00 | Nos  | 40mm dia                                                                                          |                                 | Each |                  |
| d         | 1.00 | Nos  | 32mm dia                                                                                          |                                 | Each |                  |
| e         | 3.00 | Nos  | 25mm dia                                                                                          |                                 | Each |                  |
| f         | 5.00 | Nos  | 20mm dia                                                                                          |                                 | Each |                  |

No of Corrections:

| S.<br>No. | Quant | ity            | Description                                                                                                                                                                             | Rate in figures and<br>in words | Unit                  | Amount in<br>Rs. |
|-----------|-------|----------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-----------------------|------------------|
| 69        |       |                | Providing and fixing gun metal non-<br>return valve of approved quality<br>(screwed end)                                                                                                |                                 |                       |                  |
| a         | 2.00  | Nos            | 65mm dia                                                                                                                                                                                |                                 | Each                  |                  |
| b         | 2.00  | Nos            | 50mm dia                                                                                                                                                                                |                                 | Each                  |                  |
| 70        | 5.00  | m <sup>3</sup> | Providing and laying in position PCC<br>pedestal on terrace for water supply<br>pipes "1:2:4 (1 cement : 2 coarse sand<br>(zone-III) : 4 graded stone aggregate<br>20 mm nominal size). |                                 | One<br>Cubic<br>meter |                  |
| 71        | 1.00  | Nos            | Supplying and fixing of PVC water tank<br>2,000ltsIncluding cost and<br>conveyence of all charges<br>etc,completed (for Hand wash)                                                      |                                 | Each                  |                  |
| 72        | 1.00  | Nos            | Supplying and fixing of PVC water tank<br>5,000lts. Including cost and<br>conveyence of all charges<br>etc,completed (for Lab)                                                          |                                 | Each                  |                  |

No of Corrections:

| S.<br>No. | Quan | lity | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Rate in figures and<br>in words | Unit | Amount in<br>Rs. |
|-----------|------|------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------|------------------|
|           |      |      | ELECTRICAL WORKS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                                 |      |                  |
| 73        | 1.00 | Nos  | Supply, installation & commissioning of<br>fabricated / readymade MCCB type<br>electrical distribution board ( 6 WAYS 3<br>PHASE OUT GOING) flush type, indoor<br>enclosure, hinged front cover, dust &<br>vermin proof complete with<br>switchgear given below and<br>interconnection, as per detailed<br>specification enclosed, along with<br>powder coating painting. All MCCB<br>with min 25 KA and MCB/RCCB/ELCB<br>shall be of min 10 KA rupturing<br>capacity. RCCB /ELCB shall have<br>sensitivity of 300 mA. Detail of<br>incoming & outgoing switchgear &<br>component enclosed<br>Incoming : 100 A 4P MCCB - 1 no,                                              |                                 | Each |                  |
| 74        | 4.00 | Nos  | Outgoing : 63A TP MCB - 6 nos<br>Supply, installation & commissioning of<br>electrical distribution board (THREE<br>PHASE AND NEUTRAL, 6 WAYS 1 PHASE<br>OUTGOING) flush type, indoor enclosure,<br>hinged front cover, dust & vermin proof,<br>fabricated out of 16 G mild<br>steel sheets and complete with<br>switchgear given below and<br>interconnection, as per detailed<br>specification along with powder<br>coating. All MCB & RCCB/ELCB shall be<br>of minimum 10 KA rupturing capacity.<br>RCCB /ELCB shall have sensitivity of 30<br>MA. (7 Segment).<br>INCOMER : 63A, 4P, MCB - 1 NO.,<br>OUTGOING ; 63A , 2P, ELCB/ RCCB - 3<br>NOS ; 6/10A SP MCB - 18 NOS |                                 | Each |                  |
| 75        | 3.00 | Nos  | Supply, installation & commissioning of<br>electrical distribution board (THREE<br>PHASE AND NEUTRAL, 6 WAYS 1 PHASE<br>OUTGOING) flush type, indoor enclosure,<br>hinged front cover, dust & vermin proof,<br>fabricated out of 16 G mild<br>steel sheets and complete with<br>switchgear given below and<br>interconnection, as per detailed<br>specification along with powder<br>coating. All MCB & RCCB/ELCB shall be<br>of minimum 10 KA rupturing capacity.<br>RCCB /ELCB shall have sensitivity of 100<br>MA. (7 Segment).<br>INCOMER : 63A, 4P, MCB - 1 NO.,<br>OUTGOING ; 63A , 2P, ELCB/ RCCB - 3<br>NOS ; 6/10A SP MCB - 18 NOS                                 |                                 | Each |                  |

| S.<br>No. | Quantity |     | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|----------|-----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
| 76        | 1.00     | Nos | Supply, installation & commissioning of<br>fabricated / readymade MCB type<br>electrical distribution board (SPN 8<br>WAYS) flush type, indoor enclosure,<br>hinged front cover, dust & vermin<br>proof, complete with switchgear given<br>below and interconnection, as per<br>detailed specification enclosed, along<br>with powder coating painting. All MCB<br>& RCCB/ELCB shall be of minimum 10<br>KA rupturing capacity. RCCB /ELCB<br>shall have sensitivity of 300 mA. Detail<br>of incoming & outgoing switchgear &<br>component enclosed<br>Incoming: 32 A DP MCB+RCCB, 1 No.,<br>Outgoing: 10 - 20 A SP MCB- 6 nos. |                                 | Each                    |                  |
| 77        | 120.00   | Rm  | Supply and Laying XLPE insulated<br>outer and inner PVC sheath, 1100 V<br>grade, armoured Aluminium<br>conductor cable -size of cable 4X10 sq<br>mm.                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                                 | One<br>Running<br>meter |                  |
| 78        | 120.00   | Rm  | Supply and Laying XLPE insulated<br>outer and inner PVC sheath, 1100 V<br>grade, armoured Aluminium<br>conductor cable -size of cable 4X16 sq<br>mm.                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                                 | One<br>Running<br>meter |                  |
| 79        | 50.00    | Rm  | Supply and Laying XLPE insulated<br>outer and inner PVC sheath, 1100 V<br>grade, armoured Aluminium<br>conductor cable -size of cable 4X25 sq<br>mm.                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                                 | One<br>Running<br>meter |                  |
| 80        | 100.00   | Rm  | Supply and Laying XLPE insulated<br>outer and inner PVC sheath, 1100 V<br>grade, armoured Aluminium<br>conductor cable -size of cable 3.5 X 50<br>sq mm.                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                 | One<br>Running<br>meter |                  |

No of Corrections:

| S.<br>No. | Quantity |     | Description                                                                                                                                     | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|----------|-----|-------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
| 81        | 300.00   | Rm  | Supply and Laying XLPE insulated<br>outer and inner PVC sheath, 1100 V<br>grade, armoured Copper conductor<br>cable -size of cable 3 X 6 sq mm. |                                 | One<br>Running<br>meter |                  |
| 82        |          |     | TERMINATION                                                                                                                                     |                                 |                         |                  |
| a         | 10.00    | Nos | 4C X 10 SQ.MM AL.AR.CABLE                                                                                                                       |                                 | Each                    |                  |
| d         | 10.00    | Nos | 4C X 16 SQ.MM AL.AR.CABLE                                                                                                                       |                                 | Each                    |                  |
| С         | 4.00     | Nos | 4C X 25 SQ.MM AL.AR.CABLE                                                                                                                       |                                 | Each                    |                  |
| d         | 8.00     | Nos | 4C X 50 SQ.MM AL.AR.CABLE                                                                                                                       |                                 | Each                    |                  |

| S.<br>No. | Quantity |     | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Rate in figures and<br>in words | Unit | Amount in<br>Rs. |
|-----------|----------|-----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------|------------------|
| e         | 8.00     | Nos | 3C X 6 SQ.MM AL.AR.CABLE                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                                 | Each |                  |
| 83        | 50.00    | Nos | Providing and fixing/ laying of conduit<br>and wires for Light point wiring with 1.5<br>sq. mm PVC insulated, FRLS, copper<br>conductor (stranded) 1100V grade<br>wires alongwith earthing in 25mm dia.<br>medium duty PVC surface/ concealed<br>conduit system including providing<br>and fixing one no. 10 Amp single pole<br>modular switch grid plate mounted<br>with moulded cover plate in zinc<br>chromate passivated GI box suitable<br>for modular switch, complete in all<br>respect (wiring & conduiting up to<br>switchboard not included in item<br>cost), for one light point controlled by<br>one switch. Including making zaries in<br>the wall and finishing the same |                                 | Each |                  |
| 84        | 60.00    | Nos | Providing and fixing/ laying of conduit<br>and wires for Light point wiring with 1.5<br>sq. mm PVC insulated, FRLS, copper<br>conductor (stranded) 1100V grade<br>wires alongwith earthing in 25mm dia.<br>medium duty PVC surface/ concealed<br>conduit system including providing<br>and fixing one no. 10 Amp single pole<br>modular switch grid plate mounted<br>with moulded cover plate in zinc<br>chromate passivated GI box suitable<br>for modular switch, complete in all<br>respect (wiring & conduiting up to<br>switchboard not included in item<br>cost), for two light point controlled by<br>one switch. Including making zaries in<br>the wall and finishing the same |                                 | Each |                  |
| 85        | 100.00   | Nos | Providing and fixing/ laying of conduit<br>and wires for Light point wiring with 1.5<br>sq. mm PVC insulated, FRLS, copper<br>conductor (stranded) 1100V grade<br>wires alongwith earthing in 25mm dia.<br>medium duty PVC surface/ concealed<br>conduit system including providing<br>and fixing one no. 10 Amp single pole<br>modular switch grid plate mounted<br>with moulded cover plate in zinc                                                                                                                                                                                                                                                                                  |                                 | Each |                  |

No of Corrections:

| S.<br>No. | Quantity |     | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Rate in figures and<br>in words | Unit | Amount in<br>Rs. |
|-----------|----------|-----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------|------------------|
|           |          |     | chromate passivated GI box suitable<br>for modular switch, complete in all<br>respect (wiring & conduiting up to<br>switchboard not included in item<br>cost), for three light point controlled by<br>one switch. Including making zaries in<br>the wall and finishing the same                                                                                                                                                                                                                                                                                                                                                                                                         |                                 |      |                  |
| 86        | 70.00    | Nos | Providing and fixing/ laying of conduit<br>and wires for Light point wiring with 1.5<br>sq. mm PVC insulated, FRLS, copper<br>conductor (stranded) 1100V grade<br>wires alongwith earthing in 25mm dia.<br>medium duty PVC surface/ concealed<br>conduit system including providing<br>and fixing one no. 10 Amp single pole<br>modular switch grid plate mounted<br>with moulded cover plate in zinc<br>chromate passivated GI box suitable<br>for modular switch, complete in all<br>respect (wiring & conduiting up to<br>switchboard not included in item<br>cost), for four light point controlled by<br>one switch. Including making zaries in<br>the wall and finishing the same |                                 | Each |                  |
| 87        | 4.00     | Nos | Providing and fixing/ laying of conduit<br>and wires for Light point wiring with 1.5<br>sq. mm PVC insulated, FRLS, copper<br>conductor (stranded) 1100V grade<br>wires alongwith earthing in 25mm dia.<br>medium duty PVC surface/ concealed<br>conduit system including providing<br>and fixing one no. 10 Amp single pole<br>modular switch grid plate mounted<br>with moulded cover plate in zinc<br>chromate passivated GI box suitable<br>for modular switch, complete in all<br>respect (wiring & conduiting up to<br>switchboard not included in item<br>cost), for controlled by 2 nos. 2 way<br>switch. Including making zaries in the<br>wall and finishing the same         |                                 | Each |                  |
| 88        | 20.00    | Nos | Providing and fixing/ laying of conduit<br>and wires for Ceiling fan point wiring<br>with 1.5 sq. mm PVC insulated, FRLS,<br>Cu. conductor (stranded) 1100V<br>grade wires<br>alongwith earthing in 25 mm dia.<br>Medium duty PVC surface/ concealed<br>conduit<br>system including providing and fixing<br>one no. modular 10A single way<br>switch, grid plate mounted with                                                                                                                                                                                                                                                                                                           |                                 | Each |                  |

No of Corrections:

| S.<br>No. | Quantity |     | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Rate in figures and<br>in words | Unit | Amount in<br>Rs. |
|-----------|----------|-----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------|------------------|
|           |          |     | moulded cover plate, two module<br>electronic stepped fan regulator in<br>zinc chromate passivated GI box<br>suitable for modular switches, with GI<br>box for fan suspension, complete in all<br>respect ( wiring & conduiting up to<br>switchboard not included in item<br>cost). Including making zaries in the<br>wall and finishing the same                                                                                                                                                                                                                                                                                                     |                                 |      |                  |
| 89        | 20.00    | Nos | Providing and fixing/ laying of conduit<br>and wires for Exhaust / Brackate fan<br>point wiring with 1.5 sq. mm PVC<br>insulated, FRLS, Cu. conductor<br>(stranded) 1100V grade wires<br>alongwith earthing in 25 mm dia.<br>Medium duty PVC surface/ concealed<br>conduit system including providing<br>and fixing one no. modular 10A single<br>way switch, grid plate mounted with<br>moulded cover plate in zinc chromate<br>passivated GI box suitable for modular<br>switches complete in all respect<br>(wiring & conduiting up to switchboard<br>not included in item cost).<br>Including making zaries in the wall and<br>finishing the same |                                 | Each |                  |
| 90        | 1.00     | Nos | Providing and fixing/ laying of conduit<br>& wires for Buzzer point wiring with 1.5<br>sq.mm. PVC insulated, FRLS, Cu.<br>conductor 1100V grade wires in 25<br>mm dia Medium duty PVC<br>concealed/ surface conduit system<br>including providing and fixing one no.<br>10 Amp modular buzzer push button,<br>grid plate mounted with moulded<br>cover in zinc chromate passivated GI<br>box suitable for modular switches<br>( wiring & conduiting up to<br>switchboard not included in item cost)<br>complete in all respect. Including<br>making zaries in the wall and finishing<br>the same                                                      |                                 | Each |                  |
| 91        | 30.00    | Nos | Providing and fixing zinc chromate<br>passivated GI box suitable for modular<br>switches with grid plate moulded<br>cover, in surface / concealed conduit<br>system and 1 no. 10 A 3 pin 250 V<br>modular socket outlet with safety<br>shutter and 10 A 250 V modular switch<br>for 10 A isolated power point (wiring &<br>conduiting up to power plug point not<br>included in item cost) complete in all<br>respect.                                                                                                                                                                                                                                |                                 | Each |                  |

No of Corrections:

| S.<br>No. | Quantity |     | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Rate in figures and<br>in words | Unit | Amount in<br>Rs. |
|-----------|----------|-----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------|------------------|
| 92        | 10.00    | Nos | Providing and fixing 10A 3 pin 250 V<br>modular socket outlet and 10 A 250 V<br>modular switch in existing lighting<br>switch board, including connections<br>within the box with 1.5 sq. mm PVC<br>insulated, FRLS copper conductor 1100<br>V grade wires. (wiring & conduiting up<br>to power plug point not included in<br>item cost)                                                                                                                                                                                                                                                                                                                                                                                                                    |                                 | Each |                  |
| 93        | 20.00    | Nos | Providing and fixing zinc chromate<br>passivated GI box with moulded sheet<br>cover in surface/concealed conduit<br>system and 1 no. modular 20 A 3 pin<br>250 V universal socket outlet with<br>safety shutter and 20 A 250 V modular<br>type switch for 20 A isolated power<br>point (wiring & conduiting up to power<br>plug point not included in item cost)<br>complete in all respect.                                                                                                                                                                                                                                                                                                                                                                |                                 | Each |                  |
| 94        | 10.00    | Nos | Providing and fixing zinc chromate<br>passivated GI boxes with moulded<br>sheet cover in surfaces/concealed<br>conduit system for 20 A power point<br>(socket and switch are separated from<br>each other by a distance of 2 mtr.<br>Max). In one box 20 A universal 6 pin<br>250 V modular type socket outlet<br>having safety shutter to be fixed and in<br>other 1 no. 20 A 250 V modular type<br>switch to be fixed. Both the boxes to<br>be interconnected with surface/<br>concealed conduit system with 2.5 sq.<br>mm. PVC insulated FRLS, Cu<br>conductor (stranded), 1100 V grade<br>wires and 2.5 sq. mm. Green PVC<br>insulated earth wire. (Cost of wiring<br>and conduiting up to the first box from<br>DB is not included in this item cost). |                                 | Each |                  |
| 95        | 10.00    | Nos | Providing and fixing zinc chromate<br>passivated GI box suitable for modular<br>switches with grid plate moulded<br>cover, in surface / concealed conduit<br>system and 3 no. 10 A 3 pin 250 V<br>modular socket outlet with safety<br>shutter and 1 no. 10 A 250 V modular<br>switch (wiring & conduiting up to<br>power plug point not included in item<br>cost) complete in all respect                                                                                                                                                                                                                                                                                                                                                                  |                                 | Each |                  |

| S.<br>No. | Quantity |     | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|----------|-----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
| 96        | 2.00     | Nos | Supply and fixing 32 amps 240 V SPN<br>Industrial type socket outlet with 2 pole<br>and earth, plug top alongwith 32<br>amps C series SP MCB, in sheet steel<br>enclosure complete with all<br>accessories.                                                                                                                                                                                                                                                                                   |                                 | Each                    |                  |
| 97        | 2.00     | Nos | Providing and fixing 32 amps 440 V TPN<br>Industrial type socket outlet with 4 pole<br>and earth, plug top alongwith 32<br>amps C series 4P MCB, in sheet steel<br>enclosure complete with all<br>accessories.                                                                                                                                                                                                                                                                                |                                 | Each                    |                  |
| 98        | 2100.00  | Rm  | Circuit wiring with PVC insulated, FRLS,<br>1100V grade, Cu. conductor<br>(stranded) wires of red/blue/yellow<br>colour for phase, black colour for<br>neutral & green colour for earthing in<br>Medium duty PVC surface/concealed<br>conduit system, complete with wires<br>and conduit sizes of 2 x 2.5 Sq. mm for<br>power (phase & neutral) and 1 x 1.5sq<br>mm for earthing in 25 mm dia medium<br>duty PVC conduit. Including making<br>zaries in the wall and finishing the<br>same    |                                 | One<br>Running<br>meter |                  |
| 99        | 1100.00  | Rm  | Circuit wiring with PVC insulated, FRLS,<br>1100V grade, Cu. conductor<br>(stranded) wires of red/blue/yellow<br>colour for phase, black colour for<br>neutral & green colour for earthing in<br>Medium duty PVC surface/concealed<br>conduit system, complete with wires<br>and conduit sizes of 2 x 4.0 sq. mm. for<br>power (phase & neutral) and 1 x 2.5<br>sq. mm for earthing in 25 mm dia<br>Medium duty PVC conduit. Including<br>making zaries in the wall and finishing<br>the same |                                 | One<br>Running<br>meter |                  |
| 100       | 100.00   | Rm  | Circuit wiring with PVC insulated, FRLS,<br>1100V grade, Cu. conductor<br>(stranded) wires of red/blue/yellow<br>colour for phase, black colour for<br>neutral & green colour for earthing in<br>Medium duty PVC surface/concealed<br>conduit system, complete with wires<br>and conduit sizes of 4 x 4.0 sq. mm. for                                                                                                                                                                         |                                 | One<br>Running<br>meter |                  |

No of Corrections:

| S.<br>No. | Quantity |     | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|----------|-----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
|           |          |     | power (phases & neutral) and 2 x 2.5<br>sq. mm for earthing in 25 mm dia<br>Medium duty PVC conduit. Including<br>making zaries in the wall and finishing<br>the same                                                                                                                                                                                                                                                                                                                             |                                 |                         |                  |
| 101       | 50.00    | Rm  | Sub main wiring (3 PHASE) with PVC<br>insulated, FRLS, Cu. Conductor<br>(stranded) 1100V grade wires of<br>red/yellow/blue colour for phase,<br>black colour for neutral & green colour<br>for earthing in Medium duty PVC<br>surface/ concealed conduit system<br>complete with wires and conduit of<br>size 4x10 sq. mm for power (phases &<br>neutral) and 2x6 sq. mm for earth wire<br>in 38 mm dia Medium duty PVC<br>conduit. Including making zaries in the<br>wall and finishing the same |                                 | One<br>Running<br>meter |                  |
| 102       | 100.00   | Rm  | Providing & laying spare concealed or<br>surface 25 mm dia Medium duty PVC<br>conduit for wiring complete with<br>accessories and draw out boxes and<br>their covers.                                                                                                                                                                                                                                                                                                                             |                                 | One<br>Running<br>meter |                  |
| 103       | 100.00   | Rm  | Providing & laying spare concealed or<br>surface 32 mm dia Medium duty PVC<br>conduit for wiring complete with<br>accessories and draw out boxes and<br>their covers.                                                                                                                                                                                                                                                                                                                             |                                 | One<br>Running<br>meter |                  |
| 104       | 1.00     | Nos | Supply & Installation, testing and<br>commissioning of ceiling/ bracket fan,<br>with all standard accessories and<br>connecting with 1.5 sq mm Cu.<br>conductor PVC wires.                                                                                                                                                                                                                                                                                                                        |                                 | Each                    |                  |
| 105       | 1.00     | Nos | Supply &Installation, testing and<br>commissioning of ceiling/ bracket fan,<br>with all standard accessories and<br>connecting with 1.5 sq mm Cu.<br>conductor PVC wires. The standard<br>hanging rod of ceiling fan to be<br>replaced with new GI class `B' pipe up<br>to 700 mm long. (including painting of<br>new pipe)                                                                                                                                                                       |                                 | Each                    |                  |

98

| S.<br>No. | (JUGDTITV) |     | Description                                                                                                                                                                                                                                                                                                                                       | Rate in figures and<br>in words | Unit | Amount in<br>Rs. |
|-----------|------------|-----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------|------------------|
| 106       | 1.00       | Nos | Supply & Installation, testing and<br>commissioning of ceiling/ bracket fan,<br>with all standard accessories and<br>connecting with 1.5 sq mm Cu.<br>conductor PVC wires. The standard<br>hanging rod of ceiling fan to be<br>replaced with new GI class `B' pipe<br>above 700 mm and up to 1500 mm<br>long (including painting of new pipe)     |                                 | Each |                  |
| 107       | 1.00       | Nos | Supply & Fixing, testing and<br>commissioning of bell/ buzzer/ musical<br>bell/bell indicator on buzzer point.                                                                                                                                                                                                                                    |                                 | Each |                  |
| 108       | 10.00      | Nos | Supply & Installation, testing & commissioning of exhaust fan up to 450 mm size with all accessories inculding opening in wall and connecting with 2.5 sq mm Cu. Conductor PVC flexible cable with flexible conduit from exhaust fan point.                                                                                                       |                                 | Each |                  |
| 109       | 10.00      | Nos | Supply & Installation, testing & commissioning of exhaust fan up to 300 mm size with all accessories inculding opening in wall and connecting with 2.5 sq mm Cu. Conductor PVC flexible cable with flexible conduit from exhaust fan point.                                                                                                       |                                 | Each |                  |
| 110       | 20.00      | Nos | Supply & Installation, testing & commissioning of Recess/ Surface mounted LED lighting fixtures suitable for compact LED lamp up to 18w, directly on ceiling/false ceiling without any extra clamps or additional fixing device complete with all accessories including lamps and connecting with 1.5 sq mm Cu. Conductor wire from light points. |                                 | Each |                  |
| 111       | 58.00      | Nos | Supply & Installation, testing and<br>commissioning of 40 W LED lighting<br>fixture directly on ceiling/ beams/ walls<br>/ trusses etc. complete with all<br>accessories . The item include supply<br>of anchore fastners for fixing the<br>Lighting fixture & connecting with 1.5<br>sq.mm Cu. conductor wires from light<br>point.              |                                 | Each |                  |

| S.<br>No. | Quantity |     | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Rate in figures and<br>in words | Unit | Amount in<br>Rs. |
|-----------|----------|-----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------|------------------|
| 112       | 36.00    | Nos | Supply & Installation, testing and<br>commissioning of 36w LED 2x2 lighter<br>lighting fixture directly on ceiling.<br>complete with all accessories . The<br>item include supply of anchore<br>fastners for fixing the Lighting fixture &<br>connecting with 1.5 sq.mm Cu.<br>conductor wires from light point.                                                                                                                                                          |                                 | Each |                  |
| 113       | 6.00     | Nos | Supply & Installation, testing and<br>commissioning of 35w LED well glass<br>lighting fixture directly on ceiling/<br>beams/ walls / trusses etc. complete<br>with all accessories. The item include<br>supply of anchore fastners for fixing<br>the Lighting fixture & connecting with<br>1.5 sq.mm Cu. conductor wires from<br>light point.                                                                                                                             |                                 | Each |                  |
| 114       | 250.00   | Nos | Supply & Installation, testing and<br>commissioning of 75w LED LINEAR<br>HIGH BAY lighting fixture directly<br>SUSPENDED on ceiling/ beams/ walls<br>/ trusses etc. complete with all<br>accessories . The item include supply<br>of VERTICAL SUPPORTS , JUNCTION<br>BOXES anchore fastners for fixing the<br>Lighting fixture & connecting with 1.5<br>sq.mm Cu. conductor wires from light<br>point.WIPRO LH15-102-0-90-57-XX OR<br>EQVT                                |                                 | Each |                  |
| 115       | 16.00    | Nos | Supply & Installation, testing and<br>commissioning of 40W CLEAN ROOM<br>lighting fixture on ceiling. complete<br>with all accessories . & connecting<br>with 1.5 sq.mm Cu. conductor wires<br>from light point.CROMPTON LCTOR<br>40PCDL OR EQVT                                                                                                                                                                                                                          |                                 | Each |                  |
| 116       | 550.00   | Rm  | Supply & installation of heavy gauge<br>perforated Cable Tray made of GI<br>sheet<br>steel, min 2 mm thick, with sides not<br>less than 50 mm deep, fittings are to<br>be same material as tray, each<br>coupling should have GI earthing<br>connector, with suitable supports with<br>bends & couplings to avoid sagging of<br>the cable tray. The rate shall be<br>inclusive of all other accessories,<br>supports, rods & plates etc. Size 150<br>mm wide x 50mm depth |                                 | 1 Rm |                  |

100

| S.<br>No. | Quan   | lity | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|--------|------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
| 117       | 50.00  | Rm   | Supply & installation of heavy gauge<br>perforated Cable Tray made of GI<br>sheet<br>steel, min 2 mm thick, with sides not<br>less than 50 mm deep, fittings are to<br>be same material as tray, each<br>coupling should have GI earthing<br>connector, with suitable supports with<br>bends & couplings to avoid sagging of<br>the cable tray. The rate shall be<br>inclusive of all other accessories,<br>supports, rods & plates etc. Size 300<br>mm wide x 50mm depth |                                 | One<br>Running<br>meter |                  |
| 118       | 100.00 | Rm   | Providing & Laying of 50 mm dia HDPE<br>Pipe 6kg/cm <sup>2</sup> ISI 600mm underground<br>for laying of LAN cable including<br>excavation & refilling the trench                                                                                                                                                                                                                                                                                                          |                                 | One<br>Running<br>meter |                  |
| 119       | 2.00   | Nos  | Providing plate type earthing pit with<br>GI plate (600X600X6.0 mm)electrode<br>including all accessories, and civil work<br>complete as per IS 3043-1987 latest<br>revision, and as per sketch.                                                                                                                                                                                                                                                                          |                                 | Each                    |                  |
| 120       | 50.00  | Rm   | Providing and laying earth continuity<br>conductor in ground/ on surface of<br>building<br>with necessary clamps as required, of<br>size GI strip 25X6mm                                                                                                                                                                                                                                                                                                                  |                                 | One<br>Running<br>meter |                  |
| 121       | 50.00  | Rm   | Providing and laying earth continuity<br>conductor in ground/ on surface of<br>building<br>with necessary clamps as required, of<br>size GI strip 50X6mm                                                                                                                                                                                                                                                                                                                  |                                 | One<br>Running<br>meter |                  |
| 122       | 100.00 | Rm   | Providing and laying earth continuity<br>conductor in ground/ on surface of<br>building<br>with necessary clamps as required, of<br>size GI wire 8 SWG                                                                                                                                                                                                                                                                                                                    |                                 | One<br>Running<br>meter |                  |
| 123       | 20.00  | Rm   | Providing & laying earth continuity<br>conductor in ground/on surface<br>/concealed<br>of building as required with Al.<br>Conductor wire(single core), 10 square<br>mm, PVC insulated of black colour.                                                                                                                                                                                                                                                                   |                                 | One<br>Running<br>meter |                  |

No of Corrections:

| S.<br>No. | Quant  | iity | Description                                                                                                                                                                                                                                                                                                                                                                                                  | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|--------|------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
| 124       | 20.00  | Rm   | Providing & laying earth continuity<br>conductor in ground/on surface<br>/concealed<br>of building as required with Al.<br>Conductor wire(single core), 6 square<br>mm, PVC insulated of black colour.                                                                                                                                                                                                       |                                 | One<br>Running<br>meter |                  |
| 125       | 2.00   | Nos  | Supply, Erection of 8m Free Standing<br>Single Arm Bracket 8 sided<br>Octogonally continously tapered<br>structured pole with base plate of size<br>300 x 300 x 12mm as per IS-875 with<br>following specification.<br>Bottom Pole Dia - 130mm<br>Top Pole Dia - 70 mm<br>Thickness of Pole - 3 mm<br>The pole should be hot dip galvanized<br>confirming to BESN<br>ISO-1461 with thickness of 65 Micron    |                                 | Each                    |                  |
| 126       | 16.00  | Nos  | Supply, Erection of 8m Free Standing<br>Double Arm Bracket 8 sided<br>Octogonally continously tapered<br>structured pole with base plate of size<br>300 x 300 x 12mm<br>as per IS-875 with following<br>specification.<br>Bottom Pole Dia - 130mm<br>Top Pole Dia - 70 mm<br>Thickness of Pole - 3 mm<br>The pole should be hot dip galvanized<br>confirming to BESN<br>ISO-1461 with thickness of 65 Micron |                                 | Each                    |                  |
| 127       | 36.00  | Nos  | 60W LED Street Light Fitting with LED                                                                                                                                                                                                                                                                                                                                                                        |                                 | Each                    |                  |
| 128       | 350.00 | Rm   | Supply and Laying 4C 16 Sq.mm.<br>XLPE AI. Ar. Cable IN SUITABLE 50mm or<br>HDPE flexible cable buried at 750mm<br>below ground                                                                                                                                                                                                                                                                              |                                 | One<br>Running<br>meter |                  |
| 129       | 300.00 | Rm   | Excavating the ground for a Depth of 0.75 Mtrs for LT cables with required width for laying the LT Cables.                                                                                                                                                                                                                                                                                                   |                                 | One<br>Running<br>meter |                  |

| S.<br>No. | Quant  | ity | Description                                                                                                                                                                                                   | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|--------|-----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
| 130       | 1.00   | Nos | LDB-STREET LIGHT SECURITY ROOM- 1<br>6W TPN VERTICAL MCB DB<br>Incoming: 1no - 63A TPN RCCB, 1 No.<br>0-24 Hrs. Photo electric switch,timer<br>with 4p contactor with wiring<br>Outgoing: 6nos - 16A TPN MCB, |                                 | Each                    |                  |
| 131       |        |     | Data                                                                                                                                                                                                          |                                 |                         |                  |
| a         | 600.00 | Rm  | Cat6 UTP cable drum of 305 mtrs<br>inculding PVC Pipe                                                                                                                                                         |                                 | One<br>Running<br>meter |                  |
| b         | 1.00   | Nos | Cat6 24 port loaded Jack panel                                                                                                                                                                                |                                 | Each                    |                  |
| С         | 20.00  | Nos | Cat6 I/O for User side                                                                                                                                                                                        |                                 | Each                    |                  |
| d         | 20.00  | Nos | Cat6 Patch cord 1 mtr - Panel rack<br>side                                                                                                                                                                    |                                 | Each                    |                  |
| e         | 20.00  | Nos | Cat6 Patch cord 2 mtrs - User side                                                                                                                                                                            |                                 | Each                    |                  |
| f         | 12.00  | Nos | Dual Face Plate                                                                                                                                                                                               |                                 | Each                    |                  |

| S.<br>No. | Quan   | lity | Description                                                                  | Rate in figures and<br>in words | Unit                    | Amount in<br>Rs. |
|-----------|--------|------|------------------------------------------------------------------------------|---------------------------------|-------------------------|------------------|
| 132       |        |      | Voice                                                                        |                                 |                         |                  |
| а         | 300.00 | Rm   | Cat6 UTP cable drum of 305 mtrs                                              |                                 | One<br>Running<br>meter |                  |
| b         | 1.00   | Nos  | Cat6 24 port loaded Jack panel                                               |                                 | Each                    |                  |
| С         | 1.00   | Nos  | 24 port loaded panel for voice resource                                      |                                 | Each                    |                  |
| d         | 20.00  | Nos  | Cat6 I/O for User side                                                       |                                 | Each                    |                  |
| e         | 20.00  | Nos  | Cat6 Patch cord1 mtrs - Rack side                                            |                                 | Each                    |                  |
| f         | 1.00   | Nos  | Supply and Erection of EPABX<br>configured with 3 Trunk and 15<br>Extensions |                                 | Each                    |                  |
| g         | 1.00   | Nos  | Supply Erection of 24 Key Digital Key<br>Telephone for reception             |                                 | Each                    |                  |

| S.<br>No. | Quant | ity | Description                                                        | Rate in figures and<br>in words | Unit | Amount in<br>Rs. |
|-----------|-------|-----|--------------------------------------------------------------------|---------------------------------|------|------------------|
| h         | 15.00 | Nos | Supply and Erection of Basic<br>Telephone with Caller ID           |                                 | Each |                  |
| 133       |       |     | Rack & Accessories                                                 |                                 |      |                  |
| a         | 1.00  | Nos | 12 U closed 600*800mm 19inches with standard accessories(FAN,Tray) |                                 | Each |                  |
| b         | 1.00  | Nos | Mounting Hardware/OR/Pk-20                                         |                                 | Each |                  |
| С         | 1.00  | Nos | PDU 15/16 socket indian standard                                   |                                 | Each |                  |
| 134       |       |     | Active                                                             |                                 |      |                  |
| a         | 1.00  | Nos | 24 port switch with 4 SFP port                                     |                                 | Each |                  |
| b         | 12.00 | Nos | 2mp dome camera IR                                                 |                                 | Each |                  |
| С         | 12.00 | Nos | PVC camera back box                                                |                                 | Each |                  |

| S.<br>No. | Quant | ity | Description                            | Rate in figures and<br>in words | Unit      | Amount in<br>Rs. |
|-----------|-------|-----|----------------------------------------|---------------------------------|-----------|------------------|
| d         | 1.00  | Nos | 16 Channel - 2 SATA (2 Nos. Hard Disk) |                                 | Each      |                  |
| e         | 1.00  | Nos | 6TB Hard disk - AV                     |                                 | Each      |                  |
|           |       |     |                                        | Amount                          |           |                  |
|           |       |     |                                        |                                 |           |                  |
|           |       |     |                                        | Ν                               | let Total |                  |

## Foot Note:

The tenderer should quote the amount towards Goods and Service tax (GST) in the appropriate columns in terms of percentage (%). If not quoted, it will be considered that the rate quoted is inclusive of GST.